STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0519-01	2012	24	212

MKEC ENGINEERING CONSULTANTS, INC.
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

SUMMARY OF QUANTITIES - STORM SEWER PIPE AND STRUCTURES*

LINE NO.	STORM SEWER CONDUIT									STORM SEWER END SECTIONS				INLETS										
	Pipe, SWS 15" RCP	Pipe, SWS 15"	Pipe, SWS 18" RCP	Pipe, SWS 18"	Pipe, SWS 24" RCP	Pipe, SWS 24"	Pipe, SWS 30" RCP	Pipe, SWS 30"	Pipe, SWS 36"	Pipe, End Section 15"	Pipe, End Section 24"	Headwall RC 30"	Headwall RC 36"	Inlet, Curb (Type 2) (L=6'-4", W=3'-4")	Inlet, Curb (Type 2) Special (Front) (L=6'-4", W=7')	Inlet, Curb (Type 2) Special (Back) (L=6'-4", W=7')	Inlet, Curb (Type 2) Special (Back) (L=6'-4", W=9')	Inlet, Drop (Single)	Inlet, Drop (Double)	Inlet, Drop (Double / Double)	Inlet, Grated Driveway, Double	MH, Standard SWS (5')	MH, Standard SWS (6')	Stormwater Quality Separator
1	104													1	1									
2	135													1	1									
3		82		98				418	821				1				3	2		1		1	1	
3A			191													1								
4	53	29												2										
5						53	52	49			1			2										
6	211		560											5										
7	52													1										
8	52													1										
9	52													1										
10						543		438				1				1			2	1		3		1
10A	154													2										
11						302					1											1		
12		23								1														
13	211		603		55									6								1		
14	52													1										
15	52													1										
16	52													1										
17	231													2							1			
TOTALS	1411	134	1354	98	55	898	52	905	821	1	2	1	1	27	2	2	3	2	2	2	1	6	1	1

* All pipe conduit is measured per lineal feet and all end sections and structures are measured per each

Note: End Sections are not poid for Separately. They are paid for as length of pipe. This is reflected in the plan quantities.

BROADWAY BRIDGE
AT 34TH STREET SOUTH

STORM SEWER SUMMARY
SHEET TITLE

472-84830
PROJECT NUMBER

JRA
DESIGN BY
DPG
DRAWN BY
JRA
CHECKED BY

ISSUED
October 9, 2012
REVISED

SHEET NO.
24 of 212

PLOTTED: Thursday, October 11, 2012 @ 10:31AM

J:\Civil\090081\dwg\SWS\090081-SWS SUMMARY