

TREE ROW REMOVAL			
STATION	OFFSET	LENGTH	
CENTRAL AVENUE			
41+00.00 to 45+50.00	Lt.	450.0	
41+00.00 to 47+25.00	Rt.	625.0	
61+60.00 to 63+60.00	Lt.	200.0	
65+60.00	Lt.	25.0	
67+85.00 to 73+25.00	Lt.	540.0	
68+85.00 to 70+05.00	Rt.	120.0	
74+35.00 to 74+95.00	Rt.	80.0	
90+00.00 to 90+30.00	Lt.	50.0	
90+60.00 to 92+00.00	Lt.	160.0	
97+90.00 to 99+40.00	Lt.	140.0	
135TH STREET WEST			
46+30.00 to 48+75.00	Lt.	245.0	
48+60.00 to 49+00.00	Rt.	40.0	
51+90.00 to 57+05.00	Lt.	510.0	
TOTAL		3,185.0	

PERMANENT PAVEMENT PATCHING		
STATION	PERMANENT ASPHALT PVMT (WL PATCH) (6") (S.Y.)	PERMANENT AGGREGATE SURFACING (6") (S.Y.)
Water Items:		
23+60.9, Main 1	17.7	
12+18.6, Main 3	19.9	
16+86.4, Main 3	24.3	
25+34.9, Main 3		27.0
Water Item Totals:	61.9	27.0

TEMPORARY PAVEMENT PATCHING				
STATION	SIDE	OFFSET	TEMP. ASPHALT PAVEMENT (6") (S.Y.)	TEMP. AGGREGATE SURFACING (6") (S.Y.)
Road Items:*				
Central				
46+47	Rt.	0'	13.4	
73+67	Rt.	32'		33.4
85+77	Rt.	8.5'	17.8	
89+00	Rt.	36'	90.0	
93+24	Rt.	34'	53.4	
98+95	Rt.	0'	15.6	
Road Items Total:			190.2	33.4
Water Items: ##				
26+80, Main 3				9.13
31+00, Main 3				9.97
32+90, Main 3				7.14
36+40, Main 3				19.05
Water Item Totals:				45.29

Paid for as "Temporary Asphalt Pmt (WL Patch)" or "Temporary Aggregate Surface (WL Patch)".

* Paid for as "Temporary Asphalt Pmt (SWS Patch)" or "Temporary Aggregate Surface (SWS Patch)".

TREE REMOVAL											
STATION	OFFSET	LG	SM	STATION	OFFSET	LG	SM	STATION	OFFSET	LG	SM
CENTRAL AVENUE											
45+90.96	61.12' Lt.	x		59+14.10	49.48' Rt.	x		79+27.22	35.87' Rt.	x	
46+14.88	23.82' Lt.		x	59+75.72	85.93' Lt.	x		80+40.80	34.50' Rt.	x	
46+18.12	24.99' Lt.		x	59+94.29	43.13' Lt.	x		81+24.80	31.79' Rt.	x	
46+31.61	67.71' Lt.	x		59+95.24	84.63' Lt.	x		81+27.95	31.95' Rt.	x	
46+39.50	49.69' Lt.	x		61+46.80	57.42' Lt.	x		81+43.78	31.61' Rt.	x	
46+66.45	64.86' Lt.	x		61+62.44	72.90' Lt.	x		81+63.03	36.16' Rt.	x	
46+73.73	71.10' Lt.	x		61+71.78	24.61' Rt.	x		81+74.45	29.26' Rt.	x	
46+83.45	56.06' Lt.	x		62+01.29	70.47' Rt.	x		81+86.43	31.47' Rt.	x	
46+94.67	57.85' Lt.	x		62+37.71	109.26' Rt.	x		81+93.82	31.47' Rt.	x	
47+12.93	58.45' Rt.	x		63+99.59	27.34' Lt.	x		82+15.00	32.18' Rt.	x	
47+16.28	73.90' Lt.	x		64+22.26	34.19' Rt.	x		82+16.61	35.93' Rt.	x	
47+30.01	86.11' Lt.	x		64+49.36	29.67' Rt.	x		82+46.39	32.43' Rt.	x	
48+02.08	63.68' Lt.		x	64+49.91	29.69' Rt.	x		82+59.98	36.03' Rt.	x	
48+06.79	60.65' Rt.	x		66+25.52	33.68' Lt.	x		86+84.94	42.03' Lt.	x	
48+08.08	71.64' Rt.	x		66+28.64	23.16' Lt.	x		88+99.63	56.50' Rt.	x	
48+13.92	6.05' Rt.	x		66+80.37	21.78' Lt.	x		88+99.63	66.03' Rt.	x	
48+20.24	6.48' Rt.	x		66+94.43	27.93' Lt.	x		88+99.63	75.50' Rt.	x	
48+27.54	6.39' Rt.	x		67+40.96	27.38' Lt.	x		91+33.25	34.14' Lt.	x	
48+57.21	24.49' Rt.		x	67+56.73	45.42' Lt.	x		91+51.66	31.81' Lt.	x	
48+84.69	6.08 Rt.	x		68+20.39	23.86' Lt.	x		92+44.74	25.91' Lt.	x	
48+84.81	24.03' Rt.		x	70+32.75	45.02' Rt.	x		135TH STREET WEST			
49+02.81	64.67' Rt.	x		73+38.37	38.66' Rt.	x		45+62.74	42.67' Lt.	x	
49+11.77	25.52' Rt.	x		73+44.20	50.80' Rt.	x		48+86.63	48.64' Rt.	x	
49+52.81	51.87' Rt.	x		73+48.04	37.37' Rt.	x		48+89.78	41.96' Lt.	x	
49+92.99	60.89' Rt.	x		73+93.73	49.36' Rt.	x		49+09.51	39.09' Lt.	x	
50+27.56	59.87' Rt.	x		74+05.53	37.05' Rt.	x		49+18.40	24.24' Rt.	x	
50+29.33	83.30' Rt.	x		74+16.58	33.51' Rt.	x		49+18.61	44.49' Lt.	x	
50+53.15	137.55' Lt.	x		74+81.50	37.00' Rt.	x		49+25.46	45.69' Lt.	x	
51+13.19	144.79' Lt.	x		74+90.10	35.42' Rt.	x		51+05.15	22.91' Rt.	x	
51+61.46	57.16' Rt.	x		75+53.49	34.24' Rt.	x		51+18.44	48.46' Rt.	x	
51+64.28	48.78' Rt.	x		76+14.23	31.77' Rt.	x		51+18.77	39.21' Lt.	x	
52+05.69	60.17' Rt.	x		76+56.15	30.69' Lt.	x		51+25.58	45.93' Lt.	x	
53+38.97	57.70' Rt.	x		76+77.09	35.50' Rt.	x		51+27.86	53.22' Lt.	x	
58+00.60	26.45' Lt.	x		76+80.97	30.35' Lt.	x		51+31.61	26.53' Rt.	x	
58+26.19	73.79' Lt.	x		77+03.72	30.59' Rt.	x		51+32.07	35.16' Lt.	x	
58+26.89	49.94' Rt.	x		77+12.23	30.67' Lt.	x		51+43.01	59.77' Rt.	x	
58+28.40	51.02' Lt.	x		77+18.69	29.67' Lt.	x		51+51.04	48.51' Lt.	x	
58+29.11	15.57' Lt.	x		77+18.69	29.67' Lt.	x		51+51.68	29.32' Rt.	x	
58+29.68	63.19' Rt.	x		78+14.75	35.22' Rt.	x		51+51.68	29.32' Rt.	x	
58+30.12	42.69' Lt.	x		78+68.27	35.78' Rt.	x		51+53.63	41.36' Lt.	x	
58+57.15	91.53' Lt.	x		78+77.46	31.57' Rt.	x		51+67.38	23.18' Rt.	x	
58+92.87	27.38' Rt.	x		78+86.69	36.08' Rt.	x		51+78.27	23.24' Rt.	x	
				79+05.65	33.13' Rt.	x		51+85.61	130.12' Lt.	x	
				79+21.29	33.78' Rt.	x		51+98.82	105.09' Lt.	x	
TOTAL			30 12	TOTAL			16 27	TOTAL			18 24

REINFORCED CRUSHED ROCK BASE					
LOCATION	CRUSHED ROCK BASE (5") (SQ.YD.)	CRUSHED ROCK BASE (6") (SQ.YD.)	CRUSHED ROCK BASE (7") (SQ.YD.)	CRUSHED ROCK BASE (8") (SQ.YD.)	REMARKS
CENTRAL AVENUE					
40+69.14 to 46+96.93				3460.50	
46+96.93 to 48+64.41		2022.75			
48+64.41 to 57+73.85				5933.34	
57+73.85 to 58+26.16		369.76			
59+89.05 to 60+41.43		370.19			
60+41.43 to 99+29.58				26267.67	
64+31.59			181.83		Jennie
73+67.59			172.95		Wheatland
84+41.35	144.23		260.30		Bay Country
85+11.30			173.31		Bay Country
59+00.03	57		253.99		Cedar Downs
93+35.88			269.22		Cedar Park
99+29.58 to 99+83.09		527.04			
135TH STREET WEST					
42+82.10 to 49+16.31				3650.93	
47+15.44			165.80		Jennie
50+55.25 to 50+83.26		233.42			
52+45.75 to 52+78.75		254.83			
52+78.75 to 57+78.77				2492.52	
TOTAL	201.23	3,777.99	1,477.40	41,804.96	

STORM SEWER REMOVAL			
STATION	OFFSET	SIZE/TYPE	LENGTH
CENTRAL AVE.			
45+90.72	1.00' Lt.	30" CMP	38.5'
45+95.61	0.61' Lt.	24"x36" CMPHE	38.5'
46+46.97	2.64' Lt.	30" CMP	41.8'
67+70.35	13.50' Lt.	15" CMP	17.9'
68+30.42	25.61' Rt.	15" CMP	20.2'
70+20.32	22.91' Rt.	15" CMP	20.4'
73+71.43	22.21' Rt.	15"x24" CMPHE	37.9'
75+76.38	0.73' Rt.	36" RCP	33.5'
75+81.89	0.80' Rt.	36" RCP	33.5'
76+31.48	23.83' Lt.	24" RCP	21.3'
78+96.45	21.90' Lt.	12" CMP	31.8'
81+11.56	21.55' Lt.	18" RCP	33.3'
81+80.15	22.11' Lt.	15" CPP	20.4'
82+19.68	21.71' Lt.	24" CMP	24.0'
83+28.93	22.23' Lt.	18" CMP	20.3'
85+36.40	22.90' Lt.	RCB	121.8'
85+84.76	3.45' Lt.	RCB	158.9'
85+66.34	15.58' Rt.	RCB	3.5'
85+69.83	20.00' Rt.	Manhole	
89+00.26	32.87' Rt.	30" RCP	64.3'
89+43.14	22.09' Lt.	12" CMP	24.3'
90+45.30	22.35' Lt.	12" RCP	36.4'
93+24.32	34.14' Rt.	36" CMP	50.5'
93+04.70	56.25' Lt.	INLET	
93+35.81	56.10' Lt.	18" RCP	59.3'
93+66.89	56.09' Lt.	INLET	
93+83.20	35.90' Lt.	18" RCP	47.1'
94+00.41	17.95' Lt.	INLET	
94+00.37	5.58' Rt.	18" RCP	45.6'
96+22.66	21.17' Lt.	15" RCP	32.7'
97+63.16	23.42' Lt.	15" RCP	33.2'
98+95.13	1.63' Rt.	24" CMP	42.1'
99+10.88	41.79' Rt.	24" RCP	18.5'
JENNIE			
11+47.23	35.31' Lt.	12" CMP	29.7'
11+48.76	26.72' Rt.	18" CMP	24.3'
135TH ST. WEST			
46+86.18	2.00' Rt.	24"x36" CMPHE	43.1'
48+48.17	15.80' Rt.	15" RCP	22.2'
TOTAL			1290.8'

RECAPITULATION OF QUANTITIES		
BID ITEM DESCRIPTION	QUANTITY	UNIT
Lump Sum Bid Items - Paving		
Field Office and Laboratory (Type A)	1	ea
Mobilization	1	LS
Mobilization (DBE)	1	LS
Contractor Staking	1	LS
Compaction Testing	1	LS
Removal of Existing Structures	1	LS
Transport of Salvaged Materials (Non-Participating)	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Pavement &/or Curb Removed	19,212	sy
Excavation	31,967	cy
Excavation, Contractor Furnished	48,452	cy
Fill, Compacted (95% Density)	64,335	cy
Fill, Select Topsoil	1,322	cy
AC Pavement, 7" (5" Bit Base)	37,232	sy
AC Pavement, 6" (3" Bit Base)	150	sy
Concrete Approach 12", Bridge	1,159	sy
Concrete Pavement 9" (Reinf.)	1,944	sy
Concrete Pavement (VG) 8" Reinf.	1,379	sy
Concrete C&G, Type 1 (6" & 1-1/2")	10,116	lf
Concrete C&G, Type 2 (3-5/8")	44	lf
Concrete C&G, Type 3 (8")	4,321	lf
Concrete C&G, Type 4 (6-5/8")	87	lf
Crushed Rock Base 8", Reinforced	41,805	sy
Crushed Rock Base 7", Reinforced	1,478	sy
Cr		