

PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
472-84817 PHASE II	2011	22	93

SIDEWALK COORDINATE TABLE					
POINT NO.	NORTH COORDINATE	EAST COORDINATE	STATION	OFFSET	DESCRIPTION
1000	1,691,320.4701	1,628,531.2955	19+93.31	35.80' Rt.	€ Sidewalk P.I. (Begin 3.2' Sidewalk)
1001	1,691,320.4802	1,628,522.4946	19+93.50	27.00' Rt.	€ Sidewalk P.I. (Begin 6' Sidewalk)
1002	1,691,448.9473	1,628,519.7954	21+22.00	27.00' Rt.	€ Sidewalk P.C. (50' R.)
1003	1,691,461.1314	1,628,521.0397	21+34.16	28.50' Rt.	€ Sidewalk P.R.C.
1004	1,691,473.3154	1,628,522.2840	21+46.31	30.00' Rt.	€ Sidewalk P.T. (50' R.)
1005	1,691,555.2646	1,628,520.5622	22+28.28	30.00' Rt.	€ Sidewalk P.I. (Begin 5' Sidewalk)
1006	1,691,555.4162	1,628,526.5604	22+28.30	36.00' Rt.	€ Sidewalk P.I. (Begin 6' Sidewalk)
1007	1,691,557.9156	1,628,526.5078	22+30.80	36.00' Rt.	€ Sidewalk P.I. (WCR)(End 6' Sidewalk)
1008	1,691,606.9269	1,628,526.7284	22+79.80	37.25' Rt.	€ Sidewalk P.C. (15')(WCR)(Begin 4' Sidewalk)
1009	1,691,614.3768	1,628,528.5306	22+87.21	39.21' Rt.	€ Sidewalk P.R.C.
1010	1,691,621.8268	1,628,530.3328	22+94.62	41.17' Rt.	€ Sidewalk P.T. (15' R.)
1011	1,691,704.1887	1,628,528.6023	23+77.00	41.17' Rt.	€ Sidewalk P.I. (End 4' Sidewalk)
1012	1,691,744.1973	1,628,528.5952	24+17.00	42.00' Rt.	€ Sidewalk P.I. (Begin 6' Sidewalk)
1013	1,691,747.0382	1,628,528.5355	24+19.84	42.00' Rt.	€ Sidewalk P.C. (15' R.)
1014	1,691,755.3805	1,628,530.8608	24+28.13	44.50' Rt.	€ Sidewalk P.R.C.
1015	1,691,763.7227	1,628,533.1861	24+36.42	47.00' Rt.	€ Sidewalk P.T. (15' R.)
1016	1,691,801.2898	1,628,532.3968	24+74.00	47.00' Rt.	€ Sidewalk P.I.
1017	1,691,813.2871	1,628,532.1447	24+86.00	47.00' Rt.	€ Sidewalk P.I.
1018	1,691,915.6146	1,628,529.9947	25+89.78	45.66' Rt.	€ Sidewalk P.I. (WCR)
1019	1,691,958.7913	1,628,529.0612	26+33.62	43.96' Rt.	€ Sidewalk P.C. (20' R.)(WCR)
1020	1,691,974.4176	1,628,536.0510	26+49.70	50.51' Rt.	€ Sidewalk P.R.C.
1021	1,691,988.8871	1,628,543.0323	26+64.68	57.00' Rt.	€ Sidewalk P.R.C. (20' R., 2793' R.)
1022	1,692,163.0776	1,628,554.8062	28+42.86	57.00' Rt.	€ Sidewalk P.T./P.I. (2793' R.)
1023	1,692,268.2238	1,628,557.1460	29+49.51	47.00' Rt.	€ Sidewalk P.I./P.C. (2803' R.)
1024	1,692,338.3943	1,628,567.6671	30+21.66	47.00' Rt.	€ Sidewalk P.T. (2803' R.)
1025	1,692,713.0587	1,628,628.7008	34+01.26	47.00' Rt.	€ Sidewalk P.C. (1153' R.)
1026	1,692,810.1682	1,628,648.8417	35+04.51	47.00' Rt.	€ Sidewalk P.T. (1153' R.)
1027	1,692,833.3742	1,628,654.9637	35+29.49	47.00' Rt.	€ Sidewalk P.C. (1153' R.)
1028	1,693,181.0558	1,628,816.6980	39+30.44	47.00' Rt.	€ Sidewalk P.C.C./P.I. (1153' R., 2697.93' R.)
1029	1,693,331.9630	1,628,940.2471	41+31.38	48.11' Rt.	€ Sidewalk P.T. (2697.93' R.)
1030	1,693,499.6671	1,629,088.0639	43+54.93	47.80' Rt.	€ Sidewalk P.I. (WCR)
1031	1,693,547.9200	1,629,130.6059	44+19.26	47.72' Rt.	€ Sidewalk P.C. (16')(WCR)
1032	1,693,553.3118	1,629,141.9773	44+30.83	52.67' Rt.	€ Sidewalk P.R.C. (16' R., 14' R.)
1033	1,693,558.0296	1,629,151.9274	44+40.96	57.00' Rt.	€ Sidewalk P.T. (14' R.)
1034	1,693,600.7713	1,629,189.7064	44+98.00	57.00' Rt.	€ Sidewalk P.I.
1035	1,693,608.2640	1,629,196.3291	45+08.00	57.00' Rt.	€ Sidewalk P.I.
1036	1,693,609.0132	1,629,196.9914	45+09.00	57.00' Rt.	€ Sidewalk P.C. (7' R.)
1037	1,693,617.0744	1,629,197.8513	45+15.61	52.31' Rt.	€ Sidewalk P.R.C.
1038	1,693,625.1196	1,629,198.6971	45+22.20	47.61' Rt.	€ Sidewalk P.T. (7' R.)
1039	1,693,706.9446	1,629,270.5815	46+31.11	47.28' Rt.	€ Sidewalk P.C. (15' R.)
1040	1,693,718.7854	1,629,274.1864	46+42.37	42.14' Rt.	€ Sidewalk P.R.C.
1041	1,693,730.6602	1,629,277.8214	46+53.68	37.00' Rt.	€ Sidewalk P.T. (15' R.)
1042	1,693,791.5926	1,629,331.6791	47+35.00	37.00' Rt.	€ Sidewalk P.I.
1043	1,693,805.0794	1,629,343.5999	47+53.00	37.00' Rt.	€ Sidewalk P.I.
1044	1,693,887.6190	1,629,416.5560	48+72.56	24.41' Rt.	€ Sidewalk P.I.
1045	1,693,915.2941	1,629,502.1017	49+72.65	25.63' Rt.	€ Sidewalk P.I.
1046	1,693,916.0400	1,629,531.6138	50+05.00	27.00' Rt.	€ Sidewalk P.I.
1047	1,693,916.3431	1,629,543.6100	50+17.00	27.00' Rt.	€ Sidewalk P.I.
1048	1,693,918.4400	1,629,626.5835	51+00.00	27.00' Rt.	€ Sidewalk P.I. (Begin Trans. 6' to 4')
1049	1,693,917.6929	1,629,636.6056	51+10.00	28.00' Rt.	€ Sidewalk P.I. (End Trans. 6' to 4')
1050	1,693,918.0123	1,629,649.2429	51+22.64	28.00' Rt.	€ Sidewalk P.I. (End Sidewalk)

Plotted on: Monday, October 24, 2011 09:32 AM  
 Plot Queue: \\ovpww00\PLTBWLP  
 Plot Scale: 60,000,000,000,000 Pen Tables: \\ovpww00\Jobs\4809\Common\Highway\Library\lob\pen\CC-22x36.pen  
 Design Filename: \\ovpww00\Jobs\4809\Hoover\CD\Detail\Hvr-coor\dnate-geom\tr.ydgn



SIDEWALK COORDINATE TABLE

CITY ENGINEER		
JAMES L. ARMOUR, P.E., L.S.		
PROJECT NUMBER	OCA NUMBER	DATE
472-84817 PHASE II	770005	11/2011
CITY ENGINEER'S OFFICE		DESIGN
CITY HALL - SEVENTH FLOOR		DRAWN
455 NORTH MAIN STREET		SHEET
WICHITA, KANSAS 67202-1620		22 of 93
(316) 268-4501		

\\ovpww00\Jobs\4809\Hoover\CD\Detail\Hvr-coor\dnate-geom\tr.ydgn