

CURB AND GUTTER				
LOCATION	STATION TO STATION		TYPE 1 (L.F.)	TYPE 3 (L.F.)
39th St.	48+22.62	49+25.09	102.70	-
39th St.	47+57	47+63	-	12.00
39th St.	49+25.33	49+35.33	-	20.00
<b>Totals</b>			102.70	32.00

VALLEY GUTTERS				
LOCATION	STATION TO STATION		CONC. PVMT. (VG) (8") (S.Y.)	EDGE CURB (L.F.)
39th St.	49+25.33	49+77.82	137.12	78.75
<b>Totals</b>			137.12	78.75

7" A.C. PAVEMENT (BM-2)			
LOCATION	STATION TO STATION		QUANTITY (S.Y.)
39th St.	45+90	47+63	216.29
39th St.	48+22.76	49+25.48	57.56
<b>Total</b>			273.85

A.C. PAVEMENT 2" MILL & OVERLAY (BM-2, PG70-28)			
LOCATION	STATION TO STATION		QUANTITY (S.Y.)
39th St.	45+90	49+25.33	847.88
<b>Total</b>			847.88

REINFORCED CRUSHED ROCK BASE				
LOCATION	STATION TO STATION		8" RCRB QUANTITY (S.Y.)	7" RCRB QUANTITY (S.Y.)
39th St.	45+90	47+63	221.25	-
39th St.	48+22.62	49+77.82	97.50	145.80
39th St.	49+25.33	49+35.33	-	11.40
<b>Totals</b>			318.75	157.20

4" SIDEWALK PAVEMENT (MEASURED QTY.)					
LOCATION	STATION TO STATION		SIDE	WIDTH (FT)	QUANTITY (S.F.)
Webb Rd.	112+77.54	112+88.12	Lt.	6	121.21
Webb Rd.	112+77.54	113+03.24	Rt.	6	203.93
<b>Total</b>					325.14

WHEELCHAIR RAMPS			
LOCATION	STATION	SIDE	QUANTITY (EACH)
Webb Rd.	112+80.54	Lt.	1
Webb Rd.	112+80.54	Rt.	1
Webb Rd.	112+87.71	Lt.	1
Webb Rd.	113+03.27	Rt.	1
Webb Rd.	113+61.78	Lt.	1
Webb Rd.	113+78.26	Rt.	1
<b>Total</b>			6


* SODDING, BERMUDA			
LOCATION	STATION TO STATION	QUANTITY (S.Y.)	
39th St.	48+22.62	50+00	200
<b>Total</b>		200	

\* Quantity shown for information only. The Contractor will be required to sod all non-paved areas disturbed by construction.

SUMMARY OF EARTHWORK QUANTITIES								
STAGE	LOCATION	STATION TO STATION		EXCAVATION (C.Y.)	FILL (C.Y.)	FILL (BEHIND CURBS) (C.Y.)	COMPACTION THRU CUTS (C.Y.)	WASTE (C.Y.)
1	39th St.	45+90	50+00	259	0	22	158	232
<b>Totals</b>				259	0	22	158	232

Note: Fill, Backfill Behind Curbs, and Compaction thru Cuts are all paid for as "Fill, Compacted (95% Density)". Total Amount = 180 CY.

RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
<b>LUMP SUM BID ITEMS (706979)</b>		
Mobilization	1	LS
Site Clearing	1	LS
Concrete &/or Asphalt Pavement Removed	380	sy
Excavation	259	cy
Fill, Compacted (95% Density)	180	cy
Concrete Pavement (VG) 8" (Reinf)	138	sy
AC Pavement 7" (5" Bit Base) (BM-2)	274	sy
AC Pavement 2" Mill & Overlay (BM-2) (PG 70-28)	848	sy
Crushed Rock Base 7", Reinforced	158	sy
Crushed Rock Base 8", Reinforced	319	sy
Concrete C & G, Comb. Type 1 (6" & 1-1/2")	103	lf
Concrete C & G, Comb. Type 3 (8" & 1-1/2"), Median	32	lf
Concrete Curb, Mono Edge (6" & 1-1/2")	79	lf
Wheelchair Ramp w/Detectable Warnings	6	ea
Signage	1	LS
Pavement Marking	1	LS
Traffic Control	1	LS
Traffic Signal Installation (39th & Webb)	1	LS
<b>LUMP SUM BID ITEMS - LANDSCAPE (706979)</b>		
Sodding, Bermuda	1	LS
<b>MEASURED QUANTITY BID ITEMS (706979)</b>		
Concrete Sidewalk 4"	326	sf
Tree Removal (Small)	1	ea
<b>MEASURED QUANTITY BID ITEMS - BMP'S (706979)</b>		
BMP, Curb Inlet Protection	2	ea
BMP, Silt Fence	500	lf



No.	Revision	By	Date
39TH STREET & WEBB, RD.			
<b>SUMMARY OF QUANTITIES RECAP OF QUANTITIES</b>			
JAMES L. ARMOUR, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84720			
<b>Professional Engineering Consultants, P.A.</b> 303 S. TOPEKA - WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	DRM	Job No.	10312
Drawn by	SVB	Date	April 2011
			Sht. 11 of 31