GRAPHIC SCALE

60 0 30 60 120

(IN FEET)

1 INCH = 60 FT.

Point Table			
Point #	Description	Northing	Easting
1	Start	18409.31	11022.93
2	Bend	18398.29	11031.19
3	Bend	18392.68	11030.64
4	Bend	18386.11	11036.02
5	Bend	18353.39	11090.22
6	Bend	18351.58	11093.22
7	Bend	18354.48	11104.93
8	Bend	18353.29	11108.22
9	Bend	18343.64	11134.99
10	P.C.	18343.62	11148.55
11	P.R.C.	18290.18	11267.77
12	FH	18144.96	11612.63
13	Valve	18175.51	11747.97
14	P.T.	18181.01	11760.89
15	PropCrnr	18403.12	11146.81
16	PropCrnr	17907.96	11146.18
17	PropCrnr	17911.03	12481.73
18	PropCrnr	18442.20	11072.13
19	PropCrnr	18398.00	11017.88
20	PropCrnr	18333.12	11146.84

LEGEND

Temporary Seeding Area
2lbs/1000 S.F. Rye Grass
(Approx. 16,281 S.F).

No.	Date	By	Approved	Revision

WATER DISTRIBUTION SYSTEM IMPROVEMENTS TO SERVE NORTHBOROUGH 3RD ADDITION

Erosion Control Plan & Coords

CITY OF WICHITA, KANSAS

GARY JANZEN, P.E. - CITY ENGINEER

POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

TIMOTHY R. AUSTIN LICENSED 11496 KANSAS PROFESSIONAL ENGINEER

FINAL

Engineer: S. SERVIS
Designer: J. UNRUH
Dwg: P:\843\843C-WL-Base-2-SMALLER BEN DIST
Date:6/19/2013

Sheet 10 of 11