

STONE SCHEDULE

| | LIFT | MIX | LENGTH | DEPTH |
|----------------------|--------|-----|---------|-------|
| AT WEIR | | | | |
| | 12" | 50% | 36" | 36" |
| | 24" | 50% | 48" | 36" |
| AT WEIR (BEYOND 9') | | | | |
| | 9"-12" | 50% | 24" | 36" |
| | 12" | 25% | 24"-36" | 36" |
| | 24" | 25% | 36" | 36" |
| SHORELINE PROTECTION | | | | |
| | 9"-12" | 50% | 24" | 36" |
| | 12" | 25% | 24"-36" | 36" |
| | 24" | 25% | 36" | 36" |

NOTE: THE LIFTS OF STONE PROVIDING SHORELINE TREATMENT FOR LAKE EDGES SHALL BE CONSTRUCTED IN A RANDOM PATTERN, AS SHOWN. RESERVE LARGER STONES FOR THE BASE COURSE AND INCORPORATE SMALLER STONES AS REQUIRED TO MAKE TRANSITION FOR EACH LIFT. OVERLAP STONES OFTEN TO PROVIDE AN INTERLOCKING STRUCTURAL STABILITY WITHIN THE WALL.

H:\CIVIL\02167\DWG\Grad\POUNDS\02167BRM



MKEC
ENGINEERING CONSULTANTS

411 N. WEBB ROAD
WICHITA, KS. 67206
316-684-9600

HAWTHORNE ADDITION

PROJECT NAME

ADDENDUM 2 SCHEDULE

SHEET TITLE

DESIGN BY:

DRAWN BY:

DRK

CHECKED BY:

FEBRUARY 2003

DATE

02167

DRAWING NAME

2 / 46

SHEET / OF