P.C. ℄ Sta. 428+59.66
1. Found #5 Bar
2. No References

P.I. ℄ Sta. 440+23.07 (Bk.)=
P.I. ℄ Sta. 439+06.49 (Ahd.)
1. Not Set

P.T. ℄ Sta. 450+69.90
1. Found #5 Bar with Fogey Cap
2. Sta. Stamp 450+00 on outside edge driving lane 70'± W
3. Median inlet 1.85'± E
4. Monument in center of median

P.O.T. ℄ Sta. 460+00
1. Set #5 Bar with PEC Cap
2. Sta. Stamp 460+00 N and S
3. W end median guard rail 45' E
4. Monument in center of median

Horizontal Control Point #1003
1. Set #4 bar in median
2. 5.80' Lt. ℄ Greenwich Road Sta. 123+17.84
3. Center of K-96 130'± N

Horizontal Control Point #1004
1. Set mag nail in conc. sidewalk joint 1' W of E edge
2. 56.00' Lt. ℄ Greenwich Road Sta. 133+19.64
3. Center of Greenwich Road 45' E
4 Center of 26th St. N 175' N

Horizontal Control Point #116
1. "T" post set 1'± below grade
2. 69.12' Lt. ℄ Greenwich Road Sta. 127+51.04
3. San. MH 5' E
4. Center of Greenwich Road 60' E
5. Center of K-96 330'± S

P.C. ℄ Sta. 469+20.10
1. Found #5 Bar
2. Sta. Stamp 470+00
3. Median inlet 80'± E
4. Monument in center of Median 110'± E

Horizontal Control Point #1009
1. Set #4 bar in median K-96
2. 9.91' Lt. ℄ K-96 Sta. 454+85.15
3. Inside conc. sld. W. Bd. K-96 4' N
4. Mile marker 296.8 160' W

Horizontal Control Point #1011
1. Set #4 bar
2. 502.61' Lt. ℄ K-96 Sta. 458+10.94
3. N edge Bldg. to N "Image Quest" 4' S
4. Culvert under Ramp 200'± E

Horizontal Control Point #1008
1. Set #4 bar in median K-96
2. 8.55' Lt. ℄ K-96 Sta. 462+46.83
3. W top conc. embankment on W side Greenwich 8.5' E
4. Inside conc. sld. W. Bd. K-96 5' N

Horizontal Control Point #1007
1. Set #4 bar
2. 57.89' Lt. ℄ K-96 Sta. 469+91.08
3. N conc. shld. K-96 W. Bd. 4' S
4. P.T. K-96 75'± E

LEGEND

- Pavement Removal
- Denotes trees to be removed.
- Wheelchair Ramp w/Detectable Warning

REMOVAL OF EXISTING STRUCTURES ✱		
STATION	SIDE	ITEM
456+49	Lt.	4" PVC Edge Drain Outlet
461+04	℄	48" RCP and End Sections

✱ For Information Only

UTILITIES

Power	Westar Energy
Telephone	AT&T
Cable TV	Cox Communications
Gas	Kansas Gas Service
Water	Wichita Water and Sanitary Sewer
Water	Sedgwick County RWD No. 1
Sanitary Sewer	Wichita Water and Sanitary Sewer

Center Sec. 4, T27S, R2E
Found #5 Bar 0.1' below surface
1. 2,653.47' Lt. or W Greenwich Rd. Sta. 126+44+84 NW angle 90° 24' 04"
2. Face 2" steel fence post 2.75' NW
3. Mag nail S face hedge post 0.55' W
4. Mag nail N face 4"x4" corner post 37.80' W
5. Mag nail E face 4"x4" corner post 40.25' SSW
6. Mag nail W face 4"x4" gate post 46.81' SSE
7. N edge bike path 4.0' S

NW Cor. Sec. 3, T27S, R2E
1. Found 3/4" Iron Pipe in thimble at ℄ 29th St. N and Greenwich Rd.
2. ℄ Greenwich Road Sta. 153+25.77
3. Chiseled "+" top of curb 69.15' NW
4. Chiseled "+" E end median 62.33' W
5. Chiseled "+" top of curb 63.21' SW
6. Chiseled "+" S end median 88.14' N
7. Chiseled "+" top of curb 59.19' NW

W 1/4 Cor. Sec. 3, T27S, R2E
1. Found 3/4" Iron Pipe in thimble in grass median
2. ℄ Greenwich Road Sta. 126+44.84
3. Chiseled "+" W side median on top curb 15.41' WNW
4. Chiseled "+" E side median on top curb 6.08' ENE
5. Chiseled "+" E face curb inlet 67.16' SW
6. Chiseled "+" W face curb inlet 67.85' SE

SW Cor. Sec 3, T27S, R2E
Found long chiseled "+" in Center 21st St. N and Greenwich Rd.
1. ℄ Greenwich Road Sta. 100+00.00
2. Chiseled "+" on traffic signal base 86.35' NE
3. Chiseled "+" on traffic signal MH pad 92.87' NW
4. Chiseled "+" on traffic signal base 111.01' SW
5. Chiseled "+" on traffic signal MH pad 96.79' SE

Center Cor. Sec. 3, T27S, R2E
Found 3/4" Iron Pipe
1. 2,647.39' Lt. or E Greenwich Rd. Sta. 126+44.84 NE angle 89° 39' 47"
2. Chiseled "+" W conc. base electric tower 87.50' ENE
3. 60d nail top fence post 9.85' N
4. 60d nail top fence post 21.75' WNW
5. 60d nail E face 10" hedge tree 24.22' S

BM#13-Set 3' "T" Post W of Greenwich at 3'± S of Pl fence N R/W K-96 Ramp W. Bd. from Greenwich, adjacent to E end Pond outside of R/W
536.0' Lt. Sta. 456+80.4 Elev.=1371.02

BM#7-Set Chis. "□" W end N Hub Guard E. Bd. K-96 Bridge over Greenwich
12.7' Rt. K-96 Sta. 462+55.6 Elev.=1395.59

BM#1 Datum from Proj. 60X-04219-042 (BM#214) "T" Post 5' W of Sanitary Sewer Manhole 300' N of K-96 & 60' W of Greenwich
304.3' Lt. K-96 Sta. 462+77.2 Elev.=1369.78

BM#8-Set Chis. "□" E end S Hub Guard W. Bd. K-96 Bridge over Greenwich
12.7' Lt. K-96 Sta. 464+42.7 Elev.=1395.82

BM#9-Set Chis. "□" Ctr. W side SWS Median Inlet
2.6' Lt. K-96 Sta. 470+49.6 Elev.=1387.02

No.	Revision	By	Date

K-96 AND GREENWICH ROAD
K-96 RAMP E-NS AND RAMP NS-W
GARY JANZEN, P.E.-CITY ENGINEER
CITY OF WICHITA PROJECT NO. 472-85066

PEC
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
303 SOUTH TOPEKA WICHITA, KS 67202
316-262-2691 www.pec1.com

Designed by	JPS	Job No.	09521	Sht. 17 of 388
Drawn by	SVB	Date	Jan., 2014	

Plotted By: cp Date: 12/30/2013 11:33:58 AM
FILE: I:\2009\09521\Plan\09521-plRamp_E_NS.dgn