STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-85066	2014	193	388

QUANTITIES SHEET

SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT

PLAN SHEET NUMBER	PLAN STATION NUMBER	(CL) LOCATION / LATERAL POSITION	SIGN DESIGNATION (Φ Existing Sign to be Removed & Reset.)	SIGN SIZE	SIGN LAYOUT SHEET NUMBER	TYPE OF SIGN			4" X 6" POSTS			3l2.25 ALUMINUM BEAM	U-POSTS		GALVANIZED STEEL BEAM POSTS						PERFORATED SQUARE STEEL TUBE (PSST) POSTS								CONCRETE FOOTINGS					TYPE OF SIGN STRUCTURE OR SUPPORT MOUNT						MOUNT ABOVE SIGN DESIGNATION
									WOOD		STEEL				W6x9		W10x12		W10x22		1 3/4"		2"		2 1/4"				2 1/2"		WOOD POST	STEEL BEAM POST								
																															A36		A572 (ALT)						
						FLAT SHEET	REINFORCED PANEL	OVERLAY	FLAT SHEET SIGN	REINFORCED PANEL SIGN	STRUCTURAL TUBING		2 LB PER FT	3 LB PER FT	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	POST	FOOTING	POST	FOOTING	POST	FOOTING	COUPLER	COUPLER & FOOTING	POST	FOOTING	18" DIA.	24" DIA.	30" DIA.	24" DIA.	30" DIA.	OVERHEAD	CANTILEVER	BUTTERFLY	BRIDGE MOUNT	MAST ARM	VERT. SUPPORT	
GREENWICH RD. (N. Bd. & S. Bd.)																																							
180	110+50	R / M	M2-1	21" x 15"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M5-4	24" x 18"		X																																		
180	110+50	R / S	Φ M2-1	21" x 15"					1																				1@3'											
			Φ M1-5	24" x 24"																																				
			M5-4	24" x 18"		X																																		
180	114+30	R / M	M3-2	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-1L	21" x 15"		X																																		
180	114+30	R / M	M3-4	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-3	21" x 15"		X																																		
180	116+50	R / S	D1-2	9'-0" x 2'-0"	215		X			2																			2@3'											
181	117+50	L / M	M3-2	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-1L	21" x 15"		X																																		
181	118+00	R / S	M3-4	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-3	21" x 15"		X																																		
181	118+00	R / S	M3-2	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-1L	21" x 15"		X																																		
181	121+11	L / S	M3-2	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-1R	21" x 15"		X																																		
181	126+50	L / S	E4-1a	10'-0" x 6'-0"	215		X			2																			2@3'											
181	128+75	L / M	M3-4	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-1L	21" x 15"		X																																		
181	128+85	R / S	Φ M3-4	24" x 12"					1																				1@3'											
			Φ M1-5	24" x 24"																																				
			Φ M6-1L	21" x 15"																																				
181	133+00	L / S	M3-2	24" x 12"		X			1																				1@3'											
			M1-5	24" x 24"		X																																		
			M6-3	21" x 15"		X																																		
181	133+00	L / S	Φ M3-4	24" x 12"					1																				1@3'											
			Φ M1-5	24" x 24"																																				
			Φ M6-1R	21" x 15"																																				
182	134+00	L / S	Φ D1-2	9'-0" x 2'-0"						2																			2@3'											
182	137+00	L / S	Φ M2-1	21" x 15"		(Reset Sign on Existing Post)																																				
			Φ M1-5	24" x 24"		(Reset Sign on Existing Post)																																				

CENTERLINE LOCATION
L - LEFT OF CENTERLINE
R - RIGHT OF CENTERLINE
C - ON THE CENTERLINE

LATERAL POSITION
S - SHOULDER MOUNT
O - OFFSET MOUNT
G - GORE MOUNT
M - MEDIAN MOUNT

NOTE: SEE STANDARD PLAN SHEET TE590 FOR DETAILED SPECIFICATIONS.

NO.	DATE	REVISIONS	BY	APP'D
1	7/23/10	Added Coupler and Coupler/Footing Quantity	D.D.G.	D.B.

FHWA APPROVAL			7/23/2010	APP'D	Steven A. Buckley		
DESIGNED	D.D.G.	DETAILED	K.S.	QUANTITIES		TRACED	B.B.
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN. CK.		TRACE CK.	

TE430

7/1/03

Sh. No. 193

Drawn By : cp
File : I:\2009\09521\Standards\09521-TE430-02.dgn
Plotted : 31-DEC-2013 11:11