STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-85066	2014	194	388

QUANTITIES SHEET

SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT

PLAN SHEET NUMBER	PLAN STATION NUMBER	(CL) LOCATION / LATERAL POSITION	SIGN DESIGNATION (Φ Existing Sign to be Removed & Reset.)	SIGN SIZE	SIGN LAYOUT SHEET NUMBER	TYPE OF SIGN			4" X 6" POSTS			3I2.25 ALUMINUM BEAM	U-POSTS		GALVANIZED STEEL BEAM POSTS						PERFORATED SQUARE STEEL TUBE (PSST) POSTS										CONCRETE FOOTINGS					TYPE OF SIGN STRUCTURE OR SUPPORT MOUNT							MOUNT ABOVE SIGN DESIGNATION
									WOOD		STEEL				W6x9		W10x12		W10x22		1 3/4"		2"		2 1/4"				2 1/2"		WOOD POST	STEEL BEAM POST									
																															A36		A572 (ALT)								
						FLAT SHEET	REINFORCED PANEL	OVERLAY	FLAT SHEET SIGN	REINFORCED PANEL SIGN	STRUCTURAL TUBING		2 LB PER FT	3 LB PER FT	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	POST	FOOTING	POST	FOOTING	POST	FOOTING	COUPLER	COUPLER & FOOTING	POST	FOOTING	18" DIA.	24" DIA.	30" DIA.	24" DIA.	30" DIA.	OVERHEAD	CANTILEVER	BUTTERFLY	BRIDGE MOUNT	MAST ARM	VERT. SUPPORT	
RAMP NS-E																																								
178	452+50	R / S	W4-2R	36" x 36"		X			1																						1@3'										
178	455+00	L / S	W1-8R	24" x 30"		X															1	1																		
178	455+50	L / S	W1-8R	24" x 30"		X															1	1																		
178	456+00	L / S	W1-8R	24" x 30"		X															1	1																		
178	456+50	L / S	W1-8R	24" x 30"		X															1	1																		
178	457+00	L / S	W1-8R	24" x 30"		X															1	1																		
178	457+50	L / S	W1-8R	24" x 30"		X															1	1																		
178	458+00	L / S	W1-8R	24" x 30"		X															1	1																		
178	458+50	L / S	W1-8R	24" x 30"		X															1	1																		
178	459+00	L / S	W1-8R	24" x 30"		X															1	1																		
178	459+50	L / S	W1-8R	24" x 30"		X															1	1																		
RAMP E-NS																																								
179	454+00	L / S	R5-1a	36" x 24"		X			1																						1@3'										
179	455+00	R / S	W1-8R	24" x 30"		X															1	1																		
179	455+50	R / S	W1-8R	24" x 30"		X			1																						1@3'										
179			R5-1a	36" x 24"		X																																		
179	456+00	R / S	W1-8R	24" x 30"		X															1	1																		
179	456+00	L / S	D3-2	11'-6" x 2'-0"	215		X			2																					2@3'										
179	456+50	R / S	W1-8R	24" x 30"		X															1	1																		
179	457+00	R / S	W1-8R	24" x 30"		X															1	1																		
179	457+50	L / S	R3-8b	48" x 30"		X			2																						2@3'										
179	457+50	R / S	R3-8b	48" x 30"		X			2																						2@3'										
179	458+00	R / S	W1-8R	24" x 30"		X															1	1																		
179	458+50	R / S	W1-8R	24" x 30"		X															1	1																		
179	459+00	R / S	W1-8R	24" x 30"		X															1	1																		
179	459+50	R / S	W1-8R	24" x 30"		X															1	1																		
179	459+50	L / S	W3-3	48" x 48"		X			2																						2@3'										
RAMP W-NS																																								
178	451+00	R / S	W3-3	48" x 48"		X			2																						2@3'										
178	454+00	L / S	R3-8 (Spec.)	66" x 30"	215	X			2																						2@3'										
178	454+00	R / S	R3-8 (Spec.)	66" x 30"	215	X			2																						2@3'										
178	457+00	R / S	Φ D3-2	11'-6" x 2'-0"						2																					2@3'										
178	460+00	L / S	Φ R5-1a	36" x 24"					1																						1@3'										
178	460+00	C / OH	Φ R5-1a	36" x 24"																															1					
			R3-5L	30" x 36"		X																																		
			R3-5L	30" x 36"		X																																		
			R3-6R	30" x 36"		X																																		
			R3-5R	30" x 36"		X																																		
RAMP NS-W																																								
179	462+50	L / S	W4-2R	36" x 36"		X			1																						1@3'										

CENTERLINE LOCATION
L - LEFT OF CENTERLINE
R - RIGHT OF CENTERLINE
C - ON THE CENTERLINE

LATERAL POSITION
S - SHOULDER MOUNT
O - OFFSET MOUNT
G - GORE MOUNT
M - MEDIAN MOUNT

NOTE: SEE STANDARD PLAN SHEET TE590 FOR DETAILED SPECIFICATIONS.

NO.	DATE	REVISIONS	BY	APP'D
1	7/23/10	Added Coupler and Coupler/Footing Quantity	D.D.G.	D.B.

FHWA APPROVAL			7/23/2010	APP'D	Steven A. Buckley		
DESIGNED	D.D.G.	DETAILED	K.S.	QUANTITIES		TRACED	B.B.
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN. CK.		TRACE CK.	

TE430

7/1/03

Sh. No. 194

Plotted : 31-DEC-2013 11:11
Drawn By : cp
File : I:\2009\09521\Standards\09521-TE430-03.dgn