



SITE GRADING NOTES

THE CONTRACTOR SHALL USE EXCESS EXCAVATED MATERIAL FROM THIS BORROW AREA TO GRADE LOTS WITHIN GLEN MEADOWS 2ND ADDITION.

ALL FILL PLACED AS PART OF BORROW AREA GRADING SHALL BE COMPACTED TO 90% STD. DENSITY REQUIREMENTS.

ALL FILL MATERIAL SHALL BE BLADED SMOOTH AND SLOPED TO DRAIN.

CONTRACTOR SHALL STRIP TOPSOIL FROM BORROW AREA PRIOR TO EARTHWORK OPERATIONS AND REPLACE AFTER EARTHWORK OPERATIONS IN ACCORDANCE WITH SPECIFICATIONS. THIS WORK SHALL BE INCLUDED IN THE LUMP SUM BID ITEM "MASS GRADING".

NO WASTE MATERIAL SHALL BE PLACED IN ANY STREET RIGHT-OF-WAY OTHER THAN AS NECESSARY FOR STREET CONSTRUCTION AS SHOWN IN THESE PLANS.

THE LUMP SUM BID ITEM "MASS GRADING" SHALL INCLUDE PLACING, GRADING, AND COMPACTING OF SOIL MATERIAL TO THE REQUIREMENTS OF THIS GRADING PLAN; AND FOR ALL EQUIPMENT, LABOR, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK.

THE ACTUAL EXCAVATION OF MATERIAL FOR SITE GRADING IS INCLUDED IN THE BID ITEM "UNCLASSIFIED EXCAVATION".

LEGEND

- PROPOSED CONTOUR
- - - EXISTING CONTOUR
- - - - GRADING LIMITS/MATCH LINE
- x-x- SILT FENCE BARRIER

CONTOUR INTERVAL: 1 FOOT

Saved 01-28-2014 8:58:54 AM by BJS
 Plot Scale 1:1 01-28-2014 3:54:05 PM by BJS
 C:\2013\13428\13428-002-01C-BORROW AREA GRADING PLAN

No.		Revision		By	Date
GLEN MEADOWS 2ND ADDITION STORM WATER DRAIN NO. 359 BORROW AREA GRADING PLAN GARY JANZEN, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 468-84634					
				Designed by BMM Job No. 35-13438-002 Sht. 07 of 28 Drawn by BJS Date September 2013	
				PROFESSIONAL ENGINEERING CONSULTANTS, P.A. 303 SOUTH TOPEKA WICHITA, KS 67202 316-262-2691 www.pec1.com	