



NW of Maize and Central Park - 2727 N Maize Rd



Attachment A - 472-85156 Bench and Shelter Installation, West Side Service, Wichita, KS

Install concrete pad, electrical conduit, and relocate 7' x 14' shelter. Refer to appropriate details, manufacturer's specifications, and General Notes. Shelter must have at least 30" clearance, minimum, between the back of curb and all points of the front of the shelter facing the street (with the exception of its roof and gutter). Bolt locations to anchor the shelter are to avoid cracks and joints in the pad. Final location of the pad and shelter shall be coordinated with the Engineer.

Disassemble, remove from other location, transport, assemble, and install relocated bus shelter. Contractor is responsible for any damage to the structure or sites for said work and shall notify the Engineer and Philip Zevenbergen with Transit of any damage to structures or sites, prior to performing any work. The existing shelter to be relocated is currently on the south edge of the property at 6110 W Kellogg St. Work shall be performed per City details, the manufacturer's specifications, to City standards, or as directed by the Engineer or Zevenbergen.

Pad shall extend, full width, from sidewalk to the curb.

Joints and joint type in the pad shall match the sidewalk and be continued through the pad.

Legend

Improvement, Approx. Location



Approx. Property Line



5-ft Contours



1-ft Contours (NAVD88)

