



Phase VI

Complete Marking, Signing, Signalization, Seeding and Sodding Work.
 Warning Signs and Reflectorized Cones as Required for Local Work Areas.
 Two-way Traffic at all Times on New Pavement.
 Maintain Access to Businesses at all Times.

NOTE:
 REMOVE PAVEMENT MARKINGS AS NEEDED FOR LANE CHANGES LASTING > 3 CALENDAR DAYS

TRAFFIC CONTROL PLAN LEGEND

	- DENOTES WORK ZONE
	- DENOTES TRAFFIC FLOW
	- DENOTES REFLECTORIZED CONES
	- DENOTES TUBULAR MARKERS
	- DENOTES TYPE III BARRICADE
	- DENOTES TRAFFIC SIGN
	- DENOTES TEMP. DOUBLE YELLOW STRIPE

NO SCALE