Curve No. FC7500

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9500	101+27.46	36.00' Rt.	1,685,752.4874	1,649,019.9854	–	–	P.C.
9501	101+29.22	31.76' Rt.	1,685,756.7623	1,649,021.6628	–	–	½ Pt.
9502	101+33.46	30.00' Rt.	1,685,758.5990	1,649,025.8718	–	–	P.T.

Curve No. FC7501

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9503	101+65.29	30.00' Rt.	1,685,759.1962	1,649,057.6955	1,685,751.1976	1,649,057.8456	P.C.
9504	101+79.39	35.82' Rt.	1,685,753.6450	1,649,071.9031	1,685,747.8669	1,649,066.3702	½ Pt.
9505	30+49.80	15.00' Rt.	1,685,739.6913	1,649,078.0648	1,685,739.4947	1,649,070.0672	P.T.

Curve No. FC7502

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9506	30+58.15	15.00' Rt.	1,685,731.3379	1,649,078.2701	–	–	P.C.
9507	30+62.40	16.76' Rt.	1,685,727.0534	1,649,076.6176	–	–	½ Pt.
9508	30+64.15	21.00' Rt.	1,685,725.1923	1,649,072.4194	–	–	P.T.

Curve No. FC7503

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9509	30+64.15	21.00' Lt.	1,685,726.2246	1,649,114.4067	–	–	P.T.
9510	30+62.40	16.76' Lt.	1,685,727.8771	1,649,110.1222	–	–	½ Pt.
9511	30+58.15	15.00' Lt.	1,685,732.0753	1,649,108.2611	–	–	P.C.

Curve No. FC7504

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9512	30+50.20	15.00' Lt.	1,685,740.0216	1,649,108.0657	1,685,740.2182	1,649,116.0633	P.C.
9513	102+21.11	35.90' Rt.	1,685,754.3455	1,649,113.6144	1,685,748.8126	1,649,119.3925	½ Pt.
9514	102+35.29	30.00' Rt.	1,685,760.5097	1,649,127.6844	1,685,752.5111	1,649,127.8345	P.T.

Curve No. FC7505

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9515	103+07.97	30.00' Rt.	1,685,761.8734	1,649,200.3513	–	–	P.C.
9516	103+12.21	31.76' Rt.	1,685,760.1959	1,649,204.6262	–	–	½ Pt.
9517	103+13.97	36.00' Rt.	1,685,755.9870	1,649,206.4628	–	–	P.T.

Curve No. FC7507

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9521	108+81.54	36.00' Rt.	1,685,766.6366	1,649,773.9348	–	–	P.C.
9522	108+83.30	31.76' Rt.	1,685,770.9115	1,649,775.6122	–	–	½ Pt.
9523	108+87.54	30.00' Rt.	1,685,772.7482	1,649,779.8212	–	–	P.T.

Curve No. FC7508

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9524	109+10.04	30.00' Rt.	1,685,773.1703	1,649,802.3132	1,685,765.1717	1,649,802.4633	P.C.
9525	109+24.19	35.87' Rt.	1,685,767.5695	1,649,816.5724	1,685,761.8112	1,649,811.0188	½ Pt.
9526	30+50.05	20.50' Rt.	1,685,753.5224	1,649,822.6855	1,685,753.3829	1,649,814.6867	P.T.

Curve No. FC7509

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9527	30+57.31	20.50' Rt.	1,685,746.2636	1,649,822.8120	–	–	P.C.
9528	30+61.56	22.26' Rt.	1,685,741.9910	1,649,821.1288	–	–	½ Pt.
9529	30+63.31	26.50' Rt.	1,685,740.1600	1,649,816.9175	–	–	P.T.

Curve No. FC7510

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9530	30+63.22	26.50' Lt.	1,685,741.1768	1,649,869.9078	–	–	P.T.
9531	30+61.46	22.26' Lt.	1,685,742.8599	1,649,865.6352	–	–	½ Pt.
9532	30+57.22	20.50' Lt.	1,685,747.0713	1,649,863.8041	–	–	P.C.

Curve No. FC7511

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9533	30+49.93	20.50' Lt.	1,685,754.3614	1,649,863.6771	1,685,754.5009	1,649,871.6758	P.C.
9534	109+76.89	35.85' Rt.	1,685,768.5910	1,649,869.2755	1,685,763.0386	1,649,875.0349	½ Pt.
9535	109+91.02	30.00' Rt.	1,685,774.7063	1,649,883.2907	1,685,766.7078	1,649,883.4440	P.T.

Curve No. FC7512

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9536	110+52.30	30.00' Rt.	1,685,775.8810	1,649,944.5599	–	–	P.C.
9537	110+56.54	31.76' Rt.	1,685,774.2053	1,649,948.8354	–	–	½ Pt.
9538	110+58.30	36.00' Rt.	1,685,769.9971	1,649,950.6738	–	–	P.T.

Curve No. FC7519

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9557	116+50.57	36.00' Rt.	1,685,781.3499	1,650,542.8338	–	–	P.C.
9558	116+52.33	31.76' Rt.	1,685,785.6255	1,650,544.5095	–	–	½ Pt.
9559	116+56.57	30.00' Rt.	1,685,787.4638	1,650,548.7177	–	–	P.T.

Curve No. FC7520

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9560	116+77.03	30.00' Rt.	1,685,787.8561	1,650,569.1794	1,685,779.8576	1,650,569.3328	P.C.
9561	116+91.18	35.86' Rt.	1,685,782.2686	1,650,583.4331	1,685,776.5051	1,650,577.8850	½ Pt.
9562	30+50.01	13.00' Rt.	1,685,768.2380	1,650,589.5592	1,685,768.0867	1,650,581.5606	P.T.

Curve No. FC7521

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9563	30+58.36	13.00' Rt.	1,685,759.8906	1,650,589.7171	–	–	P.C.
9564	30+62.60	14.76' Rt.	1,685,755.6155	1,650,588.0403	–	–	½ Pt.
9565	30+64.36	19.00' Rt.	1,685,753.7782	1,650,583.8317	–	–	P.T.

Curve No. FC7522

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9566	30+64.36	19.00' Lt.	1,685,754.4969	1,650,621.8249	–	–	P.T.
9567	30+62.60	14.76' Lt.	1,685,756.1737	1,650,617.5497	–	–	½ Pt.
9568	30+58.36	13.00' Lt.	1,685,760.3824	1,650,615.7125	–	–	P.C.

Curve No. FC7523

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9569	30+49.98	13.00' Lt.	1,685,768.7552	1,650,615.5541	1,685,768.9065	1,650,623.5526	P.C.
9570	117+28.88	35.85' Rt.	1,685,783.0019	1,650,621.1399	1,685,777.4545	1,650,626.9041	½ Pt.
9571	117+43.02	30.00' Rt.	1,685,789.1297	1,650,635.1620	1,685,781.1312	1,650,635.3174	P.T.

Curve No. FC7524

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9572	118+02.24	30.00' Rt.	1,685,790.2801	1,650,694.3705	–	–	P.C.
9573	118+06.48	31.76' Rt.	1,685,788.6055	1,650,698.6465	–	–	½ Pt.
9574	118+08.24	36.00' Rt.	1,685,784.3978	1,650,700.4859	–	–	P.T.

Curve No. FC7527

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9581	126+54.77	36.00' Rt.	1,685,800.8436	1,651,546.8569	–	–	P.C.
9582	126+56.53	31.76' Rt.	1,685,805.1196	1,651,548.5315	–	–	½ Pt.
9583	126+60.77	30.00' Rt.	1,685,806.9590	1,651,552.7392	–	–	P.T.

Curve No. FC7528

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9584	126+75.80	30.00' Rt.	1,685,807.2511	1,651,567.7700	1,685,799.2526	1,651,567.9254	P.C.
9585	126+90.01	35.92' Rt.	1,685,801.6043	1,651,582.0903	1,685,795.8645	1,651,576.5176	½ Pt.
9586	30+50.37	19.88' Rt.	1,685,787.4571	1,651,588.1575	1,685,787.3762	1,651,580.1579	P.T.

Curve No. FC7529

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9587	30+49.63	19.59' Lt.	1,685,788.5966	1,651,627.6201	1,685,788.6775	1,651,635.6197	P.C.
9588	127+41.20	35.79' Rt.	1,685,802.7306	1,651,633.2697	1,685,797.1579	1,651,639.0094	½ Pt.
9589	127+55.28	30.00' Rt.	1,685,808.7951	1,651,647.2306	1,685,800.7966	1,651,647.3860	P.T.

Curve No. FC7530

POINT NO.	STATION	OFFSET	ON CURVE		8' OFFSET		COMMENT
			NORTH	EAST	NORTH	EAST	
9590	128+24.21	30.00' Rt.	1,685,810.1343	1,651,716.1503	–	–	P.C.
9591	128+28.46	31.76' Rt.	1,685,808.4596	1,651,720.4263	–	–	½ Pt.
9592	128+30.21	36.00' Rt.	1,685,804.2519	1,651,722.2658	–	–	P.T.

Saved 12-17-2013 2:37:23 PM by CP
Plot Scale 1:1 12-18-2013 8:56:52 AM by CP
I:\2012\12738\FINAL PLANS\PEC PROPOSED GEOMETRY LAYOUT

PRINTS ISSUED

DATE	PURPOSE	NO.
04.29.13	FIELD CHECK	
05.31.13	OFFICE CHECK	
12.23.13	FOR CONSTRUCTION	

DOUGLAS AVE. BUS
FACILITY IMPROVEMENTS
(472-85080)
WICHITA, KS

LawKingdon Architecture
Engineering · Planning · Interiors · Landscapes

LawKingdon Architecture
345 RIVERVIEW,WICHITA,KS 67203
Phone (316) 268-0230 Fax: (316) 268-0205
©

CONTACT: Jeffery A. Best, ASLA

PROJECT NUMBER:
12856

SHEET TITLE:
COORDINATE GEOMETRY

SHEET NUMBER:
C9

PEC PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
303 SOUTH TOPEKA WICHITA, KS 67202
316-262-2691 www.pec1.com