

Conc. &/or Asph. Sdwk, Dr, &/or Pkg Lot Removed	
LOCATION	AREA S. Y.
<i>Path</i>	563
<i>Hillside Pause Point</i>	41
<i>17th Street Trail Head</i>	22
<b>Total</b>	626

PAVEMENT &/OR CURB REMOVED	
LOCATION	AREA S. Y.
<i>Path</i>	381
<i>Kickoff Trail Head</i>	15
<i>Hillside Pause Point</i>	21
<i>17th Street Trail Head</i>	18
<b>Total</b>	435

REMOVAL OF EXISTING STRUCTURES * (1201000)		
PATH STATION	OFFSET	ITEM
<i>0+19.5</i>	<i>16' Rt</i>	<i>Concrete RR Base</i>
<i>2+01</i>	<i>13' Lt</i>	<i>Concrete RR Base</i>
<i>2+07</i>	<i>18' Rt</i>	<i>Concrete RR Base</i>
<i>26+83.5</i>	<i>17' Rt</i>	<i>Concrete RR Base</i>
<i>54+20</i>	<i>12' Rt</i>	<i>Concrete RR Base</i>
<i>54+37</i>	<i>13' Rt</i>	<i>Concrete RR Base</i>
<i>55+88 (Base Line)</i>	<i>22' Rt</i>	<i>Concrete RR Base</i>
<i>56+02 - 56+52</i>	<i>1' Lt</i>	<i>Brick Retaining Wall</i>
<i>114+67</i>	<i>17' Lt</i>	<i>Concrete RR Base</i>
<i>115+05</i>	<i>18' Rt</i>	<i>Concrete RR Base</i>
<i>115+12</i>	<i>26' Lt</i>	<i>Concrete RR Base</i>
<i>115+17</i>	<i>27' Lt</i>	<i>Concrete RR Vault</i>
<i>131+89</i>	<i>Centerline</i>	<i>Stone Box Culvert</i>
<i>136+25</i>	<i>67' Rt</i>	<i>Concrete RR Vault</i>
<i>137+02</i>	<i>36' Rt</i>	<i>Concrete RR Base</i>
<i>137+53.5</i>	<i>60' Rt</i>	<i>Concrete RR Base</i>

\* For Information Only Removal of all items shall be SUBSIDIARY to bid item "Removal of Existing Structures."  
All RR Bases to be removed to a minimum depth of 3'.