

KENNEDY - Earthwork Totals (Unadjusted)							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
0+37	0.0	0.0	0.0	0.0	0.0	0.0	0.0
0+50	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1+00	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1+32	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1+50	23.8	12.2	17.6	6.0	17.6	6.0	11.6
2+00	11.5	14.0	32.8	23.7	50.4	29.7	20.7
2+50	11.8	12.7	21.6	25.0	72.0	54.7	17.3
3+00	15.8	9.6	25.7	21.5	97.7	76.2	21.5
3+50	19.6	6.4	32.8	14.6	130.5	90.9	39.7
4+00	20.2	3.1	36.9	8.8	167.4	99.7	67.7
4+50	9.1	40.3	27.2	40.2	194.5	139.8	54.7
5+00	28.0	0.2	34.4	37.4	229.0	177.3	51.7
5+49.21	14.2	16.6	38.5	15.3	267.4	192.6	74.9
5+86.17	30.2	0.0	30.4	11.4	297.8	204.0	93.9
6+29.87	21.6	11.0	41.9	8.9	339.8	212.9	126.9
6+50	14.5	10.0	13.5	7.8	353.2	220.7	132.5
7+00	9.0	16.1	21.7	24.2	374.9	244.9	130.1
7+50	12.8	15.9	20.4	27.8	395.4	272.6	122.7
8+00	17.2	10.6	28.0	23.2	423.4	295.9	127.6
8+50	25.6	8.0	40.0	16.7	463.4	312.6	150.8
9+00	20.2	8.3	43.8	12.6	507.2	325.2	182.0
9+50	14.3	14.5	33.9	14.6	541.1	339.8	201.4
10+00	19.4	11.4	32.2	18.7	573.3	358.5	214.8
10+50	16.1	9.6	33.3	17.4	606.6	375.9	230.7
11+00	16.2	8.6	30.0	16.8	636.6	392.7	243.8
11+50	20.4	9.2	34.0	16.8	670.5	409.5	261.0
11+81.48	25.2	11.9	26.7	12.7	697.2	422.3	274.9
12+03.15	40.9	0.0	25.9	4.8	723.2	427.1	296.1

