



△XX LF - REMOVE "X" LF STORM SEWER PIPE.



ALL STORM SEWER ON THIS PROJECT UNDER PAVEMENT OR CURB SHALL BE SAND BACKFILLED, JETTED AND VIBRATED.

Gas line conflict. Rotated inlet ccw putting E side 6'N of plan & W side 18"N of plan.

Station	Line 1	Line 1A	Line 2	Line 2A
0+00	STA. 0+00.00, SWS LINE 1 TOP ELEV. 1311.78	STA. 0+00.00, SWS LINE 1A= STA. 0+18.29, SWS LINE 1 TOP ELEV. 1311.88	STA. 0+00.00, SWS LINE 2 TOP ELEV. 1311.78	STA. 0+00.00, SWS LINE 2A= STA. 0+00.00, SWS LINE 2 TOP ELEV. 1311.78
0+18.29	STA. 0+18.29, SWS LINE 1 TOP ELEV. 1311.88	STA. 0+62.74, SWS LINE 1A TOP ELEV. 1311.85	STA. 0+27.69, SWS LINE 2 TOP ELEV. 1312.10	STA. 0+08.96, SWS LINE 2A TOP ELEV. 1312.10
0+60.46	Line 1	Line 1A	Line 2	Line 2A
1+29.98	STA. 1+29.98, SWS LINE 1 TOP ELEV. 1312.49	STA. 1+32.24, SWS LINE 1A TOP ELEV. 1311.71		
0+00	STA. 0+00.00, SWS LINE 1A= STA. 0+18.29, SWS LINE 1 TOP ELEV. 1311.88	STA. 0+62.74, SWS LINE 1A TOP ELEV. 1311.85		
0+62.74		Line 1A		
1+32.24		STA. 1+32.24, SWS LINE 1A TOP ELEV. 1311.71		
0+00			Line 2	
0+27.69			STA. 0+27.69, SWS LINE 2 TOP ELEV. 1312.10	
0+00				Line 2A
0+07.09				STA. 0+07.09, SWS LINE 2A TOP ELEV. 1312.10
1305	1307.75 (E) 1307.75 1307.82 (E) 1307.95 (S) 1307.95 (W)	1307.95 (S) 1307.95	1307.75 1307.95 1308.20	1307.75 1307.95 1308.20
1310	1308.11 1308.20	1308.14 1308.24	1308.45	
1315				
1320				
Proposed	18.29 L.F. of 30" RCP @ 0.40%	62.74 L.F. of 24" RCP @ 0.30%	27.69 L.F. of 15" RCP @ 0.90%	8.96 L.F. of 15" RCP @ 2.79%
Existing	42.17 L.F. of 30" RCP @ 0.38%	69.51 L.F. of 24" RCP @ 0.38%	69.50 L.F. of 30" x 19" HEROP @ 0.30%	

PROJECT NUMBER: AMIDON IMPROVEMENTS  
 DRAWING FILE: SWS LINES 1, 1A, 2 & 2A  
 WICHITA, KANSAS  
 DESIGN: KWL  
 DRAWN: [Name]  
 REVIEW: [Name]  
 DATE: Oct. 23, 2014  
 RB JOB: 3647T  
 SHEET: 26 OF 133