STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84780	2015	92	227

QUANTITIES SHEET

SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT

PLAN SHEET NUMBER	PLAN STATION NUMBER	(CL) LOCATION / LATERAL POSITION	SIGN DESIGNATION	SIGN SIZE	SIGN LAYOUT SHEET NUMBER	TYPE OF SIGN			4" X 6" POSTS			3\12.25 ALUMINUM BEAM	U-POSTS		GALVANIZED STEEL BEAM POSTS						PERFORATED SQUARE STEEL TUBE (PSST) POSTS								CONCRETE FOOTINGS					TYPE OF SIGN STRUCTURE OR SUPPORT MOUNT						MOUNT ABOVE SIGN DESIGNATION
									WOOD		STEEL				W6x9		W10x12		W10x22		1 3/4"		2"		2 1/4"				2 1/2"		WOOD POST	STEEL BEAM POST									
																															A36		A572 (ALT)							
						FLAT SHEET	REINFORCED PANEL	OVERLAY	FLAT SHEET SIGN	REINFORCED PANEL SIGN	STRUCTURAL TUBING		2 LB PER FT	3 LB PER FT	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	POST	FOOTING	POST	FOOTING	POST	FOOTING	COUPLER	COUPLER & FOOTING	POST	FOOTING	18" DIA.	24" DIA.	30" DIA.	24" DIA.	30" DIA.	OVERHEAD	CANTILEVER	BUTTERFLY	BRIDGE MOUNT	MAST ARM	VERT. SUPPORT	
K-96 RAMP E-NS																																							
88	812+48	L/S	R1-1	36"x36"		X			1																															
88	812+48	L/S	R5-1	30"x30"		X																																		
88	812+48	L/S	R6-1L	36"x12"		X																																		
88	812+48	L/S	R6-1R	36"x12"		X																																		
88	812+56	R/S	R1-1	36"x36"		X			1																															
88	812+56	R/S	R5-1	30"x30"		X																																		
88	812+56	R/S	R6-1L	36"x12"		X																																		
88	812+56	R/S	R6-1R	36"x12"		X																																		
88	815+50	L/S	R5-1a	36"x24"		X			1																															
88	815+50	R/S	R5-1a	36"x24"		X			1																															
88	816+75	L/S	D3-2	120"x24"	109		X			2																														
88	819+50	L/S	W3-1a	48"x48"		X			2																															
88	820+13	L/G	E5-1	72"x60"			X			2																														
K-96 HWY.																																							
89	826+80	R/S	W4-1R	48"x48"		X			2																															
89	828+44	L/S	D10-9	18"x48"		X							1																											
89	832+00	L/S	E4-1	156"x78"	109		X								2																									
89	836+50	L/S	R2-1	36"x48"		X			2																															
89	838+96	R/S	D10-9	18"x48"		X							1																											
91	869+00	L/S	E1-3a	144"x72"	109		X								2																									
HOOVER RD.																																							
87	116+75	R/S	M2-1	21"x15"		X			1																															
87	116+75	R/S	M3-2	24"x12"		X																																		
87	116+75	R/S	M1-5	24"x24"		X																																		
87	120+10	R/S	M3-2	24"x12"		X			1																															
87	120+10	R/S	M1-5	24"x24"		X																																		
87	120+10	R/S	M6-1	21"x15"		X																																		
87	122+00	L/S	M3-2	24"x12"		X			1																															
87	122+00	L/S	M1-5	24"x24"		X																																		
87	122+00	L/S	M6-1	21"x15"		X																																		
87	122+00	L/S	W12-2	36"x36"		X			1																															
87	128+35	L/S	M3-2	24"x12"		X			1																															
87	128+35	L/S	M1-5	24"x24"		X																																		
87	128+35	L/S	M5-1L	21"x15"		X																																		
87	132+00	L/S	W12-2	36"x36"		X			1																															
87	134+00	L/S	M2-1	21"x15"		X			1																															
87	134+00	L/S	M3-2	24"x12"		X																																		
87	134+00	L/S	M1-5	24"x24"		X																																		

CENTERLINE LOCATION
L - LEFT OF CENTERLINE
R - RIGHT OF CENTERLINE
C - ON THE CENTERLINE

LATERAL POSITION
S - SHOULDER MOUNT
O - OFFSET MOUNT
G - GORE MOUNT
M - MEDIAN MOUNT

NOTE: SEE STANDARD PLAN SHEET TE590 FOR DETAILED SPECIFICATIONS.

NO.	DATE	REVISIONS	BY	APP'D
1	7/23/10	Added Coupler and Coupler/Footing Quantity	D.D.G.	D.B.

FHWA APPROVAL			7/23/2010	APP'D	Steven A. Buckley		
DESIGNED	D.D.G.	DETAILED	K.S.	QUANTITIES		TRACED	B.B.
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN. CK.		TRACE CK.	

~~TE430~~

7/1/03

Sh. No. 92

Drawn By : drp
File : I:\2008\08807\001\Standards\08807-001 TE430.dgn
Plotted : 16-JAN-2015 07:54