STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84780	2015	96	227

RECAPITULATION OF SIGNING & DELINEATION BID ITEMS

BID ITEMS	APPROXIMATE QUANTITIES		UNITS
SIGN (FLAT SHEET) (HIGH PERFORMANCE)	163.4		SQUARE FOOT
SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)	206.5		SQUARE FOOT
SIGN (OVERLAY) (HIGH PERFORMANCE)			SQUARE FOOT
SIGN POST (4" x 6" WOOD) (FLAT SHEET SIGN)	255.0		LINEAR FOOT
SIGN POST (4" x 6" WOOD) (REINFORCED PANEL SIGN)	56.0		LINEAR FOOT
SIGN POST (2 LB/FT "U" STEEL)	22.0		LINEAR FOOT
SIGN POST (3 LB/FT "U" STEEL)			LINEAR FOOT
SIGN POST (1-3/4" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2-1/4" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (2-1/2" PERFORATED SQUARE STEEL TUBE)			LINEAR FOOT
SIGN POST (4" X 6" STRUCTURAL STEEL)			LINEAR FOOT
SIGN POST (3 I 2.25 ALUMINUM)			LINEAR FOOT
	A36	A572(ALT)	
SIGN POST (W6X9 STEEL BEAM)	68.0		LINEAR FOOT
SIGN POST (W10X12 STEEL BEAM)			LINEAR FOOT
SIGN POST (W10X22 STEEL BEAM)			LINEAR FOOT
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W6X9)	4		EACH
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W10X12)			EACH
SIGN POST STUB WITH BREAKAWAY BASE PLATE (W10X22)			EACH
SIGN POST BREAKAWAY BASE PLATE (W6X9)	4		EACH
SIGN POST BREAKAWAY BASE PLATE (W10X12)			EACH
SIGN POST BREAKAWAY BASE PLATE (W10X22)			EACH
SIGN POST FOOTING (24" Dia. CONCRETE)(STEEL BEAM POST)	12.0		LINEAR FOOT
SIGN POST FOOTING (30" Dia. CONCRETE)(STEEL BEAM POST)			LINEAR FOOT
SIGN POST FOOTING (18" Dia. CONCRETE)(WOOD POST)	18.0		LINEAR FOOT
SIGN POST FOOTING (1-3/4" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2-1/4" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (2-1/2" PERFORATED SQUARE STEEL TUBE)			EACH
SIGN POST FOOTING (SIGN POST SQUARE COUPLER) (2-1/4")			EACH
SIGN POST SQUARE COUPLER (2-1/4")			
SIGNING OBJECT MARKER (TYPE 2)			EACH
SIGNING OBJECT MARKER (TYPE 3)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE RIGID, "U" POST)	33		EACH
SIGNING DELINEATOR (TYPE A)(YELLOW RIGID, "U" POST)	2		EACH
SIGNING DELINEATOR (TYPE B)(WHITE RIGID, "U" POST)	22		EACH
SIGNING DELINEATOR (TYPE B)(YELLOW RIGID, "U" POST)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(YELLOW FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(WHITE FLEXIBLE)(TYPE I ANCHOR)	1		EACH
SIGNING DELINEATOR (TYPE B)(YELLOW FLEXIBLE)(TYPE I ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(WHITE FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE A)(YELLOW FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(WHITE FLEXIBLE)(TYPE 3 ANCHOR)			EACH
SIGNING DELINEATOR (TYPE B)(YELLOW FLEXIBLE)(TYPE 3 ANCHOR)			EACH

BID ITEMS	APPROXIMATE QUANTITIES	UNITS
SIGN (REMOVE AND RESET)	LUMP SUM	LS

NOTE:
THE QUANTITIES FOR STEEL BEAM POSTS, STUB POSTS, BASE PLATES, AND FOOTINGS IN THE CONTRACT ARE FOR A36 STEEL. WHEN FURNISHING A572 ALTERNATE STEEL BEAM POSTS, STUB POSTS, BASE PLATES, AND FOOTINGS, PAYMENT FOR THESE ITEMS WILL BE BASED ON THE A36 STEEL UNIT PRICES INCLUDED IN THE CONTRACT.

NO.	DATE	REVISIONS	BY	APP'D
1	7/23/10	Changed Bid Items as per Spec Book (2007)	D.D.G.	D.B.

KANSAS DEPARTMENT OF TRANSPORTATION
RECAPITULATION OF SIGNING & DELINEATION BID ITEMS

~~TE450~~ 7/1/03

FHWA APPROVAL		7/23/2010	APP'D	Steven A. Buckley	
DESIGNED	D.D.G.	DETAILED	K.D.S.	QUANTITIES	TRACED
DESIGN CK.	S.A.B.	DETAIL CK.	D.D.G.	QUAN. CK.	TRACE CK.

Plotted : 16-JAN-2015 08:03
Drawn By : drp
File : I:\2008\08807\001\Standards\08807-001 TE450.dgn