STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84780	2015	120	227

SUMMARY OF PAVEMENT MARKINGS

LOCATION	4" Solid WHITE Edge Line	6" Solid WHITE Edge Line	6" Broken WHITE Lane Line	6" Broken WHITE Lane Line (PCP)	6" Dotted WHITE Extension Line	6" Broken WHITE Lane Drop Line	6" Solid WHITE Lane Line	8" Broken WHITE Lane Drop Line	8" Solid WHITE Gore Line	8" Dotted WHITE Extension Line	12" Solid WHITE Diagonal Line	12" Solid WHITE Chevron Line	12" Solid WHITE Type I Crosswalk Line	24" Solid WHITE Type II Crosswalk Line	24" Solid WHITE Stop Line	4" Solid YELLOW Edge Line	4" Solid YELLOW Double Line	4" Solid YELLOW Line	4" Broken YELLOW Line	6" Solid YELLOW Edge Line	12" Solid YELLOW Diagonal Line
Multi-Component Striping																					
Ramp NS-E																					
Sta. 810+00 to Sta. 826+00		1507														319				1061	
Sta. 826+00 to Sta. 842+00		1600			1034				377											388	
Ramp E-NS																					
Sta. 810+00 to Sta. 826+00		1415	80						920		135	166				48				1018	
Sta. 826+00 to Sta. 842+00		634			460				349			32									
TOTALS		5156	80		1494				1646		135	198				367				2467	
Thermoplastic Striping																					
37th St.																					
Sta. 73+64 to Sta. 87+00		2672																	340		
Sta. 87+00 to Sta. 100+00		2526																	310		
Hoover Rd.																					
Sta. 110+00 to Sta. 126+00		2732					240										4546		20		485
Sta. 126+00 to Sta. 142+00		1841															4436				550
TOTALS		9771					240										8982		670		1035
Intersection Grade Striping																					
Ramp E-NS																					
Sta. 810+00 to Sta. 826+00															59						
TOTALS															59						

RECAPITULATION OF QUANTITIES

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(4")		FT
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(6")	6730	FT
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(8")	1646	FT
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(12")	333	FT
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(4")	367	FT
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(6")	2467	FT
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(12")		FT
PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(4")		FT
PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(6")	10011	FT
PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(8")		FT
PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(12")		FT
PAVEMENT MARKING (THERMOPLASTIC)(YELLOW)(4")	9652	FT
PAVEMENT MARKING (THERMOPLASTIC)(YELLOW)(6")		FT
PAVEMENT MARKING (THERMOPLASTIC)(YELLOW)(12")	1035	FT
PAVEMENT MARKING (EPOXY)(WHITE)(4")		FT
PAVEMENT MARKING (EPOXY)(WHITE)(6")		FT
PAVEMENT MARKING (EPOXY)(WHITE)(8")		FT
PAVEMENT MARKING (EPOXY)(WHITE)(12")		FT
PAVEMENT MARKING (EPOXY)(YELLOW)(4")		FT
PAVEMENT MARKING (EPOXY)(YELLOW)(6")		FT
PAVEMENT MARKING (EPOXY)(YELLOW)(12")		FT
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(12")		FT
PAVEMENT MARKING (INTERSECTION GRADE)(WHITE)(24")	59	FT
PAVEMENT MARKING (INTERSECTION GRADE)(YELLOW)(12")		FT
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)(LEFT ARROW)	7	EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)(RIGHT ARROW)	4	EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(US-SHIELD)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(K-SHIELD)( )		EACH
PAVEMENT MARKING SYMBOL (INTERSECTION GRADE)(I-SHIELD)( )		EACH
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(6")		FT
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(8")		FT
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(12")		FT
PAVEMENT MARKING REMOVAL	2435	FT

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION	STOP	ONLY	X-ING	SCHOOL	70	435	24	400	18
Hoover Rd.									
	3								
Ramp E-NS									
	4	4							
TOTALS	7								

NOTE: FOR SPECIFIC PAVEMENT MARKING DETAILS AND DIMENSIONS SEE PLAN SHEETS

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

NOTE:
WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

NO.	DATE	REVISIONS	BY	APP'D
2	5/25/12	Added Line Types, Symbols, and Shields	B.A.H.	B.D.G.
1	7/26/05	New FHWA Approval Date	J.F.F.	B.D.G.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

TE311

FHWA APPROVAL		5/25/2012	APP'D	Brian D. Gower	
DESIGNED	J.F.F.	DETAILED	J.F.F.	QUANTITIES	TRACED
DESIGN CK.	B.D.G.	DETAIL CK.	B.D.G.	QUAN. CK.	TRACE CK.

Plotted : 16-JAN-2015 09:07
Drawn By : drp
File : I:\2008\08807\001\Standards\08807-001 te311.dgn