



	AREAS TO BE SODDED with BUFFALO Total Area = 4,400 S.Y.		LANDSCAPED MEDIANS TO BE SODDED (Buffalo Grass "Prestige") Total Area = 620 S.Y.
	AREAS TO BE SODDED with FESCUE Total Area = 9,400 S.Y.		AREAS TO BE SEEDDED with BUFFALO Total Area = 12,750 S.Y.

NOTE: Restoration Limits Shown on This Sheet are Not Considered to be Exact. Modify as Needed to Match Existing Conditions or as Directed by the Engineer.

The Quantities on This Sheet are FOR INFORMATION ONLY. All cost associated with the Sodding activities shall not be paid for directly, but shall be SUBSIDIARY to the Lump Sum Bid Item for each.

The Sodding Quantities shown in this table are for the hatched areas only. The Contractor Shall be responsible for sodding all areas disturbed by construction activities. All costs associated with any additional sodded areas that are not hatched on this plan shall be SUBSIDIARY to the Lump Sum Bid Item for the specific type of Sod.

Drawing File: E:\ang\Tyler 29th to 37th\Erosion\Tyler 29th to 37th Erosion Contol.dwg (Sodding)
 Design: TVoith
 Drawn: JDM
 Approved: TVoith
 Scale: NOTED

Project No. 0802.E057 CAPITAL IMPROVEMENT PROJECT
 TYLER ROAD PAVING
 SEEDING / SODDING PLAN
 TYLER ROAD - 29TH STREET NORTH TO 37TH STREET NORTH

Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

March 2015
 SHEET
 OF
 68
 95