

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
5+08.26	89.97	3.42	0.00	0.00	0.00	0.00	0.00
5+50.00	114.67	7.69	158.18	8.58	158.18	8.58	149.60
6+00.00	136.19	4.94	232.27	11.69	390.45	20.28	370.18
6+50.00	132.18	15.01	248.49	18.47	638.94	38.75	600.19
7+00.00	143.47	16.76	255.23	29.42	894.17	68.17	826.00
7+39.37	160.45	22.38	221.60	28.54	1115.77	96.70	1019.07
7+50.00	141.18	42.26	59.36	12.72	1175.13	109.43	1065.70
8+00.00	168.19	26.90	286.46	64.04	1461.58	173.47	1288.12
8+31.62	147.93	58.40	185.11	49.95	1646.70	223.42	1423.28
8+50.00	184.54	19.88	113.16	26.64	1759.86	250.06	1509.80
9+00.00	202.82	4.25	358.67	22.34	2118.52	272.40	1846.12
9+50.00	206.42	2.85	378.92	6.57	2497.45	278.98	2218.47
10+00.00	198.13	3.61	374.58	5.98	2872.03	284.96	2587.07
10+50.00	179.83	9.26	349.96	11.92	3221.99	296.88	2925.11
11+00.00	188.41	1.65	340.96	10.10	3562.95	306.98	3255.97
11+50.00	188.72	11.74	349.19	12.40	3912.14	319.38	3592.76
12+00.00	197.50	0.03	357.61	10.90	4269.75	330.28	3939.47
12+50.00	209.18	1.31	376.55	1.24	4646.30	331.52	4314.78
13+00.00	173.45	1.18	354.29	2.30	5000.59	333.83	4666.76
13+50.00	157.46	0.16	306.40	1.23	5306.99	335.06	4971.93

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
14+00.00	140.38	2.23	275.78	2.21	5582.77	337.27	5245.50
14+50.00	151.52	2.24	270.28	4.15	5853.05	341.42	5511.63
15+00.00	154.53	0.00	283.38	2.08	6136.43	343.50	5792.93
15+50.00	119.16	7.27	253.42	6.73	6389.85	350.23	6039.62
16+00.00	112.45	0.57	214.46	7.26	6604.31	357.50	6246.81
16+09.05	125.39	0.78	39.84	0.23	6644.15	357.72	6286.43
16+50.00	131.10	19.84	194.52	15.64	6838.67	373.36	6465.32
16+93.06	166.20	13.35	237.07	26.46	7075.74	399.82	6675.92
17+00.00	165.33	15.81	42.61	3.75	7118.36	403.57	6714.78
17+50.00	134.82	27.70	277.92	40.28	7396.27	443.86	6952.42
17+73.07	141.57	31.30	118.09	25.21	7514.36	469.06	7045.30
18+00.00	131.60	4.13	136.22	17.67	7650.58	486.73	7163.85
18+50.00	105.63	25.99	219.66	27.89	7870.25	514.61	7355.63
18+88.11	145.83	0.00	177.44	18.34	8047.69	532.95	7514.74
19+00.00	132.34	1.53	61.27	0.34	8108.96	533.29	7575.67
19+50.00	115.13	9.15	229.14	9.88	8338.10	543.17	7794.93
20+00.00	114.22	36.54	212.36	42.31	8550.46	585.48	7964.98
20+25.00	97.60	46.66	98.06	38.52	8648.52	624.00	8024.52
20+50.00	96.01	44.96	89.63	42.42	8738.15	666.42	8071.74
21+00.00	88.46	53.66	170.80	91.31	8908.96	757.73	8151.22

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
21+50.00	92.23	50.62	167.30	96.55	9076.25	854.28	8221.97
22+00.00	101.71	91.42	179.57	131.52	9255.83	985.80	8270.03
22+50.00	150.28	68.58	233.33	148.14	9489.16	1133.94	8355.21
23+00.00	167.38	36.73	294.13	97.50	9783.28	1231.45	8551.84
23+50.00	171.53	29.02	313.81	60.88	10097.09	1292.32	8804.77
24+00.00	180.39	44.28	325.85	67.87	10422.95	1360.19	9062.75
24+50.00	201.43	32.42	353.53	71.01	10776.48	1431.21	9345.27
25+00.00	194.76	75.86	366.84	100.26	11143.31	1531.46	9611.85
25+50.00	180.34	21.63	347.32	90.27	11490.63	1621.74	9868.89
26+00.00	166.62	29.96	321.26	47.77	11811.89	1669.50	10142.39
26+50.00	172.02	47.89	313.56	72.08	12125.45	1741.59	10383.86
27+00.00	123.29	96.98	273.44	134.15	12398.89	1875.74	10523.15
27+45.38	108.56	140.45	194.85	199.54	12593.73	2075.28	10518.46
27+50.00	105.86	146.38	18.34	24.53	12612.07	2099.81	10512.26
28+00.00	200.97	30.29	284.10	163.58	12896.17	2263.39	10632.78
28+50.00	119.08	108.60	296.34	128.60	13192.51	2391.99	10800.52
28+63.11	109.94	118.00	55.58	55.00	13248.09	2446.99	10801.10
29+00.00	105.72	94.50	147.34	145.18	13395.44	2592.17	10803.26
29+50.00	103.30	70.96	193.54	153.20	13588.97	2745.37	10843.60
30+00.00	95.43	38.23	184.01	101.10	13772.98	2846.47	10926.51

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
30+02.44	94.30	40.93	8.57	3.57	13781.55	2850.05	10931.50
30+43.49	63.21	97.09	119.74	104.93	13901.29	2954.97	10946.31
30+50.00	61.62	100.99	15.05	23.88	13916.34	2978.86	10937.48
31+00.00	81.27	86.90	132.31	173.98	14048.65	3152.83	10895.81
31+50.00	49.12	68.17	120.73	143.58	14169.38	3296.42	10872.96
32+00.00	41.34	103.07	83.76	158.56	14253.13	3454.97	10798.16
32+50.00	47.28	123.96	82.06	210.21	14335.19	3665.19	10670.00
33+00.00	34.46	119.76	75.69	225.67	14410.88	3890.85	10520.02
33+50.00	29.19	130.37	58.94	231.61	14469.82	4122.46	10347.36
34+00.00	29.99	113.49	54.79	225.80	14524.61	4348.26	10176.35
34+50.00	29.46	125.89	55.04	221.66	14579.66	4569.92	10009.74
34+73.99	27.31	191.43	25.23	141.00	14604.88	4710.92	9893.97
35+00.00	38.59	78.61	31.74	130.05	14636.62	4840.96	9795.66
35+15.05	37.29	88.29	21.14	46.50	14657.77	4887.47	9770.30
35+50.00	52.03	109.21	57.82	127.84	14715.58	5015.31	9700.28
35+75.00	52.43	125.36	48.36	108.60	14763.94	5123.91	9640.04
36+00.00	69.09	103.93	56.26	106.15	14820.20	5230.06	9590.15
36+15.50	80.74	73.83	43.01	51.02	14863.21	5281.08	9582.13
36+50.00	72.75	48.63	98.07	78.24	14961.28	5359.32	9601.96
37+00.00	68.38	60.14	130.68	100.71	15091.95	5460.03	9631.93

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
37+19.15	73.23	79.35	50.21	49.46	15142.16	5509.48	9632.68
37+50.00	87.09	52.91	91.60	75.56	15233.77	5585.05	9648.72
38+00.00	103.61	78.38	176.58	121.57	15410.35	5706.61	9703.73
38+50.00	159.59	76.83	243.71	143.71	15654.05	5850.33	9803.72
39+00.00	237.99	71.73	368.13	137.55	16022.18	5987.88	10034.30
39+50.00	275.32	39.60	475.29	103.09	16497.47	6090.97	10406.50
40+00.00	313.64	93.36	545.34	123.12	17042.81	6214.09	10828.72
40+50.00	304.69	85.75	572.53	165.85	17615.34	6379.94	11235.40
41+00.00	270.52	59.82	532.60	134.79	18147.93	6514.73	11633.21
41+50.00	239.36	62.83	472.10	113.57	18620.04	6628.30	11991.74
42+00.00	209.45	55.10	415.56	109.19	19035.60	6737.48	12298.11
42+50.00	164.15	43.61	345.93	91.39	19381.52	6828.88	12552.65
43+00.00	133.74	58.03	275.83	94.11	19657.35	6922.99	12734.36
43+50.00	113.18	46.64	228.63	96.92	19885.98	7019.91	12866.08
43+53.23	111.96	47.32	13.48	5.63	19899.47	7025.53	12873.93
44+00.00	158.78	12.89	234.47	52.14	20133.94	7077.68	13056.26
44+50.00	186.96	1.39	320.13	13.22	20454.07	7090.90	13363.17
44+54.70	185.46	1.33	32.44	0.24	20486.51	7091.14	13395.37
44+74.99	183.17	4.37	138.49	2.14	20625.00	7093.27	13531.72
45+00.00	177.35	12.41	166.98	7.77	20791.97	7101.05	13690.92

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
45+50.00	171.06	28.34	322.60	37.74	21114.57	7138.78	13975.79
46+00.00	182.06	16.10	326.96	41.15	21441.53	7179.93	14261.60
46+50.00	162.77	25.57	319.28	38.58	21760.81	7218.51	14542.30
47+00.00	159.12	24.99	298.04	46.81	22058.86	7265.32	14793.53
47+50.00	160.93	33.19	296.34	53.87	22355.19	7319.19	15036.00
48+00.00	128.51	49.05	268.00	76.16	22623.19	7395.35	15227.84
48+50.00	87.73	65.29	200.22	105.87	22823.40	7501.22	15322.18
49+00.00	76.63	49.54	152.18	106.32	22975.58	7607.54	15368.04
49+21.50	65.72	1.51	56.68	20.33	23032.27	7627.87	15404.40
49+28.89	0.00	0.00	9.00	0.21	23041.26	7628.08	15413.19

