

GABIONS		
Sta. to Sta.		Cu. Yds.
WEST BRANCH		
10+00	10+25	83
10+25	10+55	75
10+55	10+90	58
10+90	11+27	86
11+27	11+57	75
11+57	12+20	200
12+20	14+15	715
14+15	14+33	69
14+33	14+42	38
14+42	15+89	735
15+89	16+13	140
16+13	16+85	432
16+85	17+35	292
17+35		19
EAST BRANCH		
10+12	10+23	31
10+23	10+42	32
10+42	10+75	94
10+75	12+34.5	155
12+34.5	12+72	41
12+72	12+78	15
12+78	12+82	13
12+82	12+85	11
12+85	12+93	33
12+93	12+94	5
12+94	14+08	619
14+08	14+32	144
14+32	16+30	1,353
16+30	16+64	204
16+64	18+90	1,318
18+90	19+00	50
19+00		14
ACCESS LANE		
10+25	10+76	83
10+75	11+06	20
Sub-Total		7,252
RENO MATTRESS		
WEST BRANCH		522
EAST BRANCH		468
ACCESS LANE		35
Sub-Total		1,015
Total		8,267

3				
2				
1				
NO.	DATE	REVISIONS	BY	APP'D
CITY OF WICHITA				
SUMMARY OF QUANTITIES				
SHEET NO.	OF	SCALE	APP'D	
DESIGNED		DETAILED	QUANTITIES	TRACED
DESIGN CK.		DETAIL CK.	QUAN.CK.	TRACE CK.

CURB & GUTTER/SIDEWALK CONSTRUCTION					
STATION TO STATION		SIDE	CURB & GUTTER LIN. FT.	SIDEWALK SQ. FT.	REMARKS
70+21	70+92	Lt. & Rt.	95	88	Bluff Area Outfall
94+08 to 96+00 Belmont		Lt.	192		
57+01	58+14	Lt. & Rt.	243		Pinecrest (Includes Orm
15+83	17+35	Rt.	154		W. Br. Dry Creek
TOTAL			684	88	