FHWA REGION NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	54-87 K-4445-01	1996	68	73

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

DELINEATORS & CHANNELIZING DEVICES (EACH)

BARRICADES			PAVEMENT MARKERS			VERTICAL PANELS	
TY I OR TY II	TYPE III (9'TO 14')	DRUMS	TUBULAR	TYPE I	TYPE II	SINGLE	BACK TO BACK
10	12	74					

LIGHTING DEVICES (EACH)

CONSTRUCTION WARNING LIGHT (TYPE "B" HIGH INTENSITY)	26
ARROW DISPLAY	1
TEMP. TRAFFIC SIGNALS (SETS)	

CONCRETE SAFETY BARRIER (SECTIONS)

TYPE I (TEMPORARY)	47
TYPE IV (TEMPORARY)	

CONSTRUCTION SIGNS (EACH)

MUTCD NO.	SIZE - SQ.FT. 0-9.25	9.26-16.25	16.26 & OVER
W20-7a		2	
W1-4L	1		
W4-2R	1		
W4-2L	2		
W13-1	1		
W20-3		12	
W20-5		6	
R11-2		6	
R11-4		12	
W20-1		2	

RECAPITULATION OF QUANTITIES

ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 9.25 SQ.FT.)		EACH PER DAY
CONSTRUCTION SIGNS (9.26 TO 16.25 SQ.FT.)		EACH PER DAY
CONSTRUCTION SIGNS (16.26 SQ.FT. & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE I OR II)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 4' TO 8')		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 9' TO 14')		EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE "B" HIGH INTENSITY)		EACH PER DAY
REFLECTORIZED DRUM		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
TUBULAR MARKERS		EACH PER DAY
VERTICAL PANELS (SINGLE TYPE)		EACH PER DAY
VERTICAL PANELS (BACK TO BACK TYPE)		EACH PER DAY
OBJECT MARKERS		EACH PER DAY
CONCRETE SAFETY BARRIER (TYPE I) (TEMPORARY)		SECTION/DAY
CONCRETE SAFETY BARRIER (TYPE IV) (TEMPORARY)		SECTION/DAY
PAVEMENT MARKING (TEMPORARY)		
4" BROKEN (12.5') (TYPE I TAPE)		STA./LINE
4" SOLID (TYPE I TAPE)		STA./LINE
4" BROKEN (12.5') (TYPE II TAPE)		STA./LINE
4" SOLID (TYPE II TAPE)		STA./LINE
PAVEMENT MARKING (TEMPORARY STRIPING)		
4" BROKEN (4') (TYPE II TAPE)		MILE/LINE
4" SOLID (TYPE II TAPE)		MILE/LINE
EXISTING PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
INERTIAL BARRIER SYSTEM	2	EACH
MODULE F200 (REPLACEMENT)		EACH
MODULE F400 (REPLACEMENT)		EACH
MODULE F700 (REPLACEMENT)		EACH
MODULE F1400 (REPLACEMENT)		EACH
MODULE F2100 (REPLACEMENT)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL	LUMP SUM	LUMP SUM
FLAGGER (SET)	1	HOUR

Note: Quantities shown for "Information Only".

NO.	DATE	REVISIONS	BY	APP'D
3				
2	7/8/94	REVERSE TYPE I AND TYPE II TAPE DESIGNATIONS	WPR	NAB
1	5/23/94	1994 MUTCD REVISIONS	WPR	NAB

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

TE751 10/13/93

FHWA Approval	8-22-94	APP'D	Nelda A. Buckley
DESIGNED	DETAILED	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

Design Filename: i:\15690\phase\kdotstd\te751.dgn
Plotted on 13-JUN-1996 Settings File: NONE
Plot Scale: 1.000000:1.000000
Pen Table: i:\15690\phase\pentable\kdotstd.pen
lmorris