

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 TE-0623-01	2014	35	35

**Measured Quantity Bid Items (Demo/ Removal)**

Curb & Gutter Removal	135	LF
Sidewalk, Driveway or Ramp Pvmt. Removal	1975	SY
Pavement Marking Removal	1	LS

**Measured Quantity Bid Items (Pavement)**

Wheelhair Ramp w/ Detectable Warnings	13	EA
Sidewalk Pavement (5")	33747	SF
Concrete Pavement (8")(Reinforced)	475	SY
Combined C&G (6-5/8")	10	LF
Median Combined C&G (6-5/8")	171	LF
Mono Edge Curb (6-5/8")	0	LF
Concrete Pavers	51	SY
Traffic Manhole Adj	2	EA

**Measured Quantity Bid Items (Traffic)**

Pavement Marking (Thermoplastic)(Sharrow)	123	EA
Bike Route Signage	77	EA
Pavement Marking (Multi-Component)(White)(12" Solid)	158	LF
Pavement Marking (Multi-Component)(White)(24" Solid)	1800	EA
Rect. Rapid Flash Beacon Sign Assembly	4	EA
Ped. Signal Head Modification	3	EA
Ped. Signal Pole Relocation	1	EA
Collapsible Bollard	2	EA

**Lump Sum Bid Items**

Seeding	1	LS
Erosion Control	1	LS
Site Restoration	1	LS
Traffic Control	1	LS
Mobilization	1	LS



REVISIONS  
 BDT  
 REVIEW  
 DATE  
 Sep 2, 2014

DESIGN  
 BDT  
 UTILITY

PROJECT NUMBER  
 472-05717  
 DRAWING FILE  
 Details Sheets.dwg {35-...}

RB JOB  
 4181H  
 SHEET  
 35  
 of  
 35

**PAVEMENT MARKING DETAILS**  
**ARMOUR BIKE BOULEVARD**  
**WICHITA, KANSAS**