



Total Volume Table (C.Y. Unadjusted)

Station	Fill Area	Cut Area	Fill Volume	Cut Volume	Cumulative Fill Vol	Cumulative Cut Vol
0+64.96	11.46	13.12	0.00	0.00	0.00	0.00
1+00.00	11.59	13.12	14.93	17.02	14.93	17.02
1+50.00	11.71	13.12	21.47	24.29	36.40	41.31
2+00.00	11.46	13.12	21.45	24.29	57.85	65.60
2+50.00	11.46	13.12	21.21	24.29	79.06	89.89
3+00.00	11.46	13.12	21.21	24.29	100.28	114.18
3+50.00	11.46	13.12	21.21	24.29	121.49	138.47
4+00.00	11.46	13.12	21.21	24.29	142.70	162.76
4+50.00	11.46	13.12	21.21	24.29	163.92	187.05
5+00.00	11.46	13.17	21.22	24.34	185.14	211.39
5+19.26	11.62	13.12	8.23	9.38	193.37	220.77
5+43.90	14.64	35.15	11.98	22.02	205.35	242.79
5+56.58	12.10	25.17	6.28	14.16	211.62	256.95
5+69.25	12.38	17.83	5.75	10.09	217.37	267.04
5+84.25	12.26	20.87	6.84	10.75	224.21	277.79
6+04.25	23.96	8.67	13.42	10.94	237.63	288.73
6+19.25	0.65	0.00	6.84	2.41	244.47	291.14

45TH COURT NORTH



Baughman Engineering | Surveying | Planning | Landscape Architecture

315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149

PROJECT NUMBER: _____ SHEET: **21 OF 24**

E:\Projects\Falcon Falls 5th_14-02-P019\Engineering\Phase 1\Str_14-04-E065\STREET_XS.dwg