




FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87-N-0223-01	2002	24	47





TYPICAL TRAFFIC CONTROL SIGN MOUNTING INSTALLATION
CURB AND GUTTER SECTION



SIGN PLACEMENT ON PATH



DETAIL B
230mm METRO



STREET NAME SIGN
BLADE DETAILS


SIGN ASSEMBLY TABLE			
STATION	OFFSET	SIGN	QUANTITY*
0+035.742	7.52m Lt.	OM-3	1
0+038.793	8.15m Lt.	OM-3	1
0+095.073	9.67m Lt.	W10-1	1
0+196.199	10.81m Lt.	R2-1	1
0+199.600	13.00m Lt.	0-3(230mm Metro)	2
0+215.951	19.00m Lt.	OM-1	1
0+222.285	17.15m Rt.	OM-1	1
0+238.778	11.12m Rt.	0-3(230mm Metro)	2
0+251.532	11.42m Rt.	R1-2	1
0+286.253	10.63m Rt.	R2-1	1
0+397.076	8.14m Rt.	OM-3	1
0+400.000	7.61m Lt.	OM-3	1
TOTAL			

* FOR INFORMATION ONLY

NOTE: REFERENCES BELOW TO "STANDARD SPECIFICATIONS" DENOTE "STANDARD SPECIFICATION FOR STATE ROAD AND BRIDGE CONSTRUCTION EDITION 1990" BY THE KANSAS DEPARTMENT OF TRANSPORTATION.

- POST ANCHORS: POSTS SHALL BE ANCHORED WITH A YIELDING BASE POST SUPPORT AS DETAILED.
- POSTS FOR TRAFFIC CONTROL SIGNS: POSTS SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 1620 OF THE STANDARD SPECIFICATIONS EXCEPT THAT ALL POSTS SHALL WEIGH 4.46kg/m MINIMUM.
- STREET NAME SIGNS (SNS) SHALL BE POSITIONED SO THAT THE BOTTOM OF THE BLADES ARE 2.1M ABOVE GRADE.
- POSTS FOR END OF ROADWAY SIGN TO BE 2.4M LONG AND INSTALLED A MINIMUM OF 1.2M FROM ROADWAY TO BOTTOM OF SIGN.
- SIGN BLANKS FOR TRAFFIC CONTROL SIGNS: SIGN BLANKS SHALL BE FABRICATED FROM 0.2030M ALUMINUM ALLOY 6063-T6 CONFORMING TO THE REQUIREMENTS OF SUBSECTION 1626 OF THE STANDARD SPECIFICATIONS.
- SIGN BLADES FOR STREET NAME SIGNS: EXTRUDED ALUMINUM BLADES SHALL BE ALUMINUM ALLOY CONFORMING TO 6063-T6 OR 5052-H38 (ASTM SPECIFICATION B221, LATEST ISSUE). BLADES SHALL HAVE AN ALODINE OR PHOSPHATE ETCHED FINISH. BLADES SHALL HAVE SQUARE CORNERS AND NO HOLES. MINIMUM BLADE LENGTH SHALL BE 600mm. MAXIMUM BLADE LENGTH SHALL BE 1200mm. LENGTH VARIES BY INCREMENTS OF 150mm. BLADES BEARING THE STREET NAMES SHALL BE FIRMLY ATTACHED TO THE MOUNTING BRACKETS USING SCREWS. THE BLADES SHALL BE ORIENTED PARALLEL TO THE STREET.
- MOUNTING BRACKETS FOR SIGNS: ALUMINUM BRACKETS SHALL BE ALUMINUM ALLOY 360 HAVING A TENSILE STRENGTH OF 44,000 PSI. THE BRACKETS SHALL BE SMOOTHLY FINISHED FREE OF PITS, BURRS, AND FLAWS.
- FASTENERS: ALL STEEL FASTENERS FOR TRAFFIC CONTROL SIGNS SHALL BE GALVANIZED AND SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 1614 OF THE STANDARD SPECIFICATIONS.
- REFLECTIVE SHEETING: REFLECTIVE SHEETING SHALL BE TYPE II - HIGH PERFORMANCE CLASS HA IN ACCORDANCE WITH SUBSECTION 2201 OF THE STANDARD SPECIFICATIONS.
- PROCESS INK: ALL PROCESS INK SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 2202 OF THE STANDARD SPECIFICATIONS.
- DETAILS: REGULATORY AND WARNING SIGNS SHALL CONFORM TO THE DETAILS IN "STANDARD HIGHWAY SIGNS", FHWA, 1979.
- THE REFLECTIVE SHEETING FOR THE 230MM METRO SIZE SNS IS TO BE THE HIGHWAY GREEN BACKGROUND WITH SILVERWHITE #2 COPY WITH 130MM UPPER CASE AND LOWER CASE PRIMARY COPY AND SUFFIX COPY, BOTH SERIES "C". THE CARDINAL DIRECTION CENTERED DIRECTLY BELOW THE BLOCK NUMBER SHALL BE AN UPPER CASE, 75MM SERIES "C" LETTER. FACES TO TRIM TO A 216MM WIDTH. (SEE DETAIL B.)

STREET NAME	NO. BLADES REQ'D	
	6 3/4" STD.	9" METRO
Lincoln 500W	1	
McLean 1100S	1	
Lincoln 600W	1	
McLean 1200S	1	



TYPICAL STREET NAME SIGN MOUNTING INSTALLATION
CURB AND GUTTER SECTION

PROJECT NUMBER 472-83799		SHEET NAME Mnsdct		ENGINEERING DIRECTORY F:\LinMcIn\Traff	
DESIGN STAFF	DRAWN STAFF	APPROVED JFB	DATE July 2003	SCALE None	BAUGHMAN NO 01-03-E944

CAPITAL IMPROVEMENT PROJECT
SIGNING DETAILS
LINCOLN AND MCLEAN INTERSECTION IMPROVEMENTS

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

SHEET
24
OF
47