



EXCAVATION				LOOSE FILL				COMPACTED FILL			
Station	Area	Volume	Cumulative Vol.	Station	Area	Volume	Cumulative Vol.	Station	Area	Volume	Cumulative Vol.
0+41.19	13.99	0.00	0.00	0+41.19	16.59	0.00	0.00	0+41.19	7.10	0.00	0.00
0+50.00	10.86	4.05	4.05	0+50.00	18.68	5.75	5.75	0+50.00	5.14	2.00	2.00
1+00.00	27.14	35.18	39.24	1+00.00	14.49	30.71	36.47	1+00.00	2.66	7.22	9.21
1+14.99	27.52	15.17	54.41	1+14.99	14.12	7.94	44.41	1+14.99	2.78	1.51	10.72
1+20.99	21.49	5.45	59.86	1+20.99	22.52	4.07	48.48	1+20.99	0.81	0.40	11.12
1+50.00	23.24	24.03	83.89	1+50.00	22.57	24.22	72.70	1+50.00	0.74	0.83	11.95
1+66.49	22.73	14.04	97.92	1+66.49	29.06	15.77	88.47	1+66.49	4.48	1.59	13.55
1+72.49	19.20	4.66	102.58	1+72.49	26.35	6.16	94.63	1+72.49	11.40	1.76	15.31

WOODRIDGE