



BLUELAKE

EXCAVATION			
Station	Area	Volume	Cumulative Volume
1+28.24	0.00	0.00	0.00
1+50.00	0.00	0.00	0.00
2+00.00	0.00	0.00	0.00
2+50.00	0.00	0.00	0.00
2+88.50	0.00	0.00	0.00
3+00.00	0.00	0.00	0.00
3+50.00	0.00	0.00	0.00
4+00.00	0.00	0.00	0.00
4+50.00	45.92	42.38	42.38
4+97.16	31.46	67.54	109.92

LOOSE FILL			
Station	Area	Volume	Cumulative Volume
1+28.24	66.53	0.00	0.00
1+50.00	72.64	56.07	56.07
2+00.00	74.07	135.98	192.06
2+50.00	70.55	134.09	326.14
2+88.50	54.31	88.96	415.10
3+00.00	71.74	26.85	441.95
3+50.00	63.89	125.12	567.06
4+00.00	57.97	112.73	679.80
4+50.00	53.78	103.43	783.22
4+97.16	50.06	90.46	873.68

COMPACTED FILL			
Station	Area	Volume	Cumulative Volume
1+28.24	145.81	0.00	0.00
1+50.00	136.84	113.88	113.88
2+00.00	124.16	241.58	355.46
2+50.00	122.33	228.28	583.73
2+88.50	83.37	146.53	730.27
3+00.00	69.98	32.66	762.93
3+50.00	43.43	106.01	868.94
4+00.00	26.22	65.02	933.96
4+50.00	5.98	30.12	964.08
4+97.16	0.17	5.52	969.60