| FHWA REGION NO. | STATE | PROJECT NUMBER | FISCAL YEAR | SHEET NUMBER | TOTAL SHEETS |
|---|---|---|---|---|---|
| 7 | KANSAS | 87TE-0115-01 | 1997 | 25 | 49 |

| BY | DATE |
|---|---|
| | |
| | |
| | |
| | |
| REFERENCES NOTED | |
| REFERENCES CHECKED | |

STA. 11+480

N 6773.6506 E 7085.6093
STA: 11+484.404, P.T.

PART OF FOUNTAIN
STREET R/W

CONSTRUCTION
LIMITS

STA. 11+490 LT.
SIGN W1-2R.

N 6761.4431 E 7090.8846
STA: 11+497.702, P.C.

N 6752.5319 E 7143.1555
STA: 11+556.744, P.R.C.

N 6756.0212 E 7160.7636
STA: 11+576.557, P.T.

RE-GRADE CHANNEL AS NEEDED TO
MATCH RCB END SECTIONS
(UPSTREAM AND DOWNSTREAM).

INSTALL 9.000 m GUARDRAIL LEFT AND
RIGHT. CENTER OVER RCBC, 1.0 m
CLEAR OF EDGE OF PATH.

UNPLATTED
C-31413

Δ = 55°05'14"
R = 17 000
L = 16 345

Δ = 87°19'28"
R = 13 000
L = 19 813

Δ = 37°56'38"
R = 30 000
L = 19 867

CONSTRUCT 100mm A.C.
PAVEMENT (3 000 WIDE).
SLOPE RIGHT.

STA. 11+530 RT.
SIGN W1-5L.

N 6751.5305 E 7103.0885
STA: 11+514.047, P.T.

N 6755.8738 E 7182.1813
STA: 11+600.452, P.C.
SIGN W1-5L RT.

N 6752.5144 E 7176.6071
STA: 11+593.944, P.T.

Δ = 66°24'45"
R = 15 000
L = 17 387

Δ = 63°31'48"
R = 10 000
L = 11 088

STA. 11+590.678, INSTALL 12.802 m
OF 2.134 m (WIDE) X 1.828 m (HEIGHT)
RCBC INCLUDING END SECTIONS.
FL. LT. 405.590, FL. RT. 405.628.
PLACE 8.000 SQ. m CONCRETE BAG
RIPRAP (LEFT).

N 6752.6409 E 7166.0791
STA: 11+582.856, P.C.

N 6746.4665 E 7127.8864
STA: 11+539.357, P.C.

STA. 11+620

BROOKS
(UNIMPROVED)
60' (18.288 m)
R/W

CHISHOLM PARK ESTATES

SCALE 1:200

E. Fork Chisholm Creek
100-yr. water surface elev. 409.5±.

11+500 PVI
11+520 PVI
11+545 PVI
11+568.140 PVI
11+598.860 PVI

10 000 m V.C.
PVI 407.843

10 000 m V.C.
PVI 407.843

STA. 11+590.678,
INSTALL 12.802 m
RCBC.

0%
2.00%
-1.40%
-5.00%
0.00%
+5.00%

408.400
408.900

408.950 +484.404 408.950
+497.702 408.950 408.950
+514.047 409.231
409.350
+539.357 409.097
+545 409.000
+556.744 408.413
+563.140 408.093
+568.140 407.843
+573.140 407.843
+576.557 407.843
+582.856 407.843
+593.860 407.843
+598.860 407.843
+600.452 407.852
+603.860 408.093

11+480 +500 +520 +540 +560 +580 +600 +620

406 407 408 409

**STA. 11+480 TO 11+620**
**K96 BIKE PATH - GROVE PARK TO OLIVER**
**WICHITA, KANSAS**


SRB
924 NORTH MAIN
WICHITA, KANSAS 67203
316-264-8008
FAX 264-4621
www.srb1.com
E-Mail: srb@srb1.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING


PROJECT NUMBER

| DRAWN | DESIGN | REVIEW | DATE | UTILITY | SRB JOB |
|---|---|---|---|---|---|
| JTS | TCR | - | July 3, 2001 | | 1554T |

REVISED

SHEET 25
TOTAL 49