

Excavation (CY Unadjusted)				Compacted Fill (CY Unadjusted)				Loose Fill (CY Unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+00.00	0.00	0.00	0.00	0+00.00	0.00	0.00	0.00	0+00.00	0.00	0.00	0.00
0+50.00	0.00	0.00	0.00	0+50.00	0.00	0.00	0.00	0+50.00	0.00	0.00	0.00
0+87.11	0.00	0.00	0.00	0+87.11	0.00	0.00	0.00	0+87.11	0.00	0.00	0.00
1+87.08	0.00	0.00	0.00	1+87.08	0.00	0.00	0.00	1+87.08	0.00	0.00	0.00
2+00.00	0.00	0.00	0.00	2+00.00	0.00	0.00	0.00	2+00.00	0.00	0.00	0.00
2+50.00	0.00	0.00	0.00	2+50.00	0.00	0.00	0.00	2+50.00	0.00	0.00	0.00
3+00.00	0.00	0.00	0.00	3+00.00	0.00	0.00	0.00	3+00.00	0.00	0.00	0.00
3+50.00	0.00	0.00	0.00	3+50.00	0.00	0.00	0.00	3+50.00	0.00	0.00	0.00
3+88.85	0.00	0.00	0.00	3+88.85	0.00	0.00	0.00	3+88.85	0.00	0.00	0.00
4+23.18	0.00	0.00	0.00	4+23.18	159.86	101.65	101.65	4+23.18	0.00	0.00	0.00
4+57.30	0.00	0.00	0.00	4+57.30	51.54	133.54	235.20	4+57.30	48.44	30.60	30.60
5+00.00	0.00	0.00	0.00	5+00.00	23.14	58.83	294.02	5+00.00	46.52	74.89	105.49
5+50.00	2.09	1.98	1.98	5+50.00	1.95	22.79	316.82	5+50.00	34.30	74.30	179.79
6+00.00	34.17	33.67	35.65	6+00.00	0.00	1.78	318.60	6+00.00	6.85	37.64	217.43
6+50.00	50.55	78.38	114.02	6+50.00	0.00	0.00	318.60	6+50.00	1.13	7.38	224.82
7+00.00	73.09	115.09	229.11	7+00.00	0.00	0.00	318.60	7+00.00	0.24	1.19	226.00
7+50.00	89.47	151.32	380.43	7+50.00	0.00	0.00	318.60	7+50.00	0.00	0.21	226.21
8+00.00	47.60	127.37	507.80	8+00.00	0.00	0.00	318.60	8+00.00	3.09	2.73	228.94
8+50.00	20.32	62.61	570.41	8+50.00	0.00	0.00	318.60	8+50.00	16.39	18.44	247.38
9+00.00	5.73	24.04	594.45	9+00.00	0.00	0.00	318.60	9+00.00	31.44	44.75	292.13
9+50.00	0.31	5.54	599.99	9+50.00	7.01	6.52	325.13	9+50.00	41.60	68.10	360.23
10+00.00	0.00	0.29	600.28	10+00.00	20.80	25.75	350.87	10+00.00	47.00	82.03	442.27
10+50.00	0.00	0.00	600.28	10+50.00	46.54	61.97	412.84	10+50.00	48.43	88.27	530.54
11+00.00	0.00	0.00	600.28	11+00.00	83.29	119.81	532.66	11+00.00	48.43	89.68	620.22
11+50.00	0.00	0.00	600.28	11+50.00	121.30	189.26	721.92	11+50.00	48.43	89.68	709.90
11+68.45	0.00	0.00	600.28	11+68.45	129.97	85.84	807.76	11+68.45	48.42	33.08	742.98
12+00.00	0.00	0.00	600.28	12+00.00	187.69	182.88	990.64	12+00.00	61.76	62.82	805.80
12+19.32	0.00	0.00	600.28	12+19.32	226.72	143.75	1134.39	12+19.32	50.68	38.58	844.38
12+34.68	0.00	0.00	600.28	12+34.68	242.29	128.77	1263.16	12+34.68	48.00	27.03	871.42
12+50.00	0.00	0.00	600.28	12+50.00	211.87	128.88	1392.04	12+50.00	50.53	27.96	899.38
12+69.67	0.00	0.00	600.28	12+69.67	127.16	123.48	1515.52	12+69.67	86.91	50.06	949.43
12+82.64	0.00	0.00	600.28	12+82.64	47.42	41.95	1557.47	12+82.64	0.00	20.88	970.31

