

BILL OF MATERIALS		
ITEM	UNIT	QTY
PAD MOUNTED CONTROLLER & CABINET	EACH	1
TRAFFIC SIGNAL HEAD (SEE CHART A) W/ MOUNTING HARDWARE	EACH	22
HARDWARE		
TRAFFIC SIGNAL POLE (SEE CHART B) STEEL	EACH	4
CONCRETE CONTROLLER PAD	EACH	1
CONCRETE FOOTING - POLE	EACH	4
CONDUIT ELBOW 90°	EACH	As Req'd
CONDUIT ELBOW 90° 3"	EACH	As Req'd
BACK PLATE 5" - 3 SECTION	EACH	12
BACK PLATE 5" - 5 SECTION	EACH	3
TRAFFIC MANHOLE	EACH	4
GROUND ROD & CLAMP	EACH	6
CONDUIT CLAMP	EACH	As Req'd
TRAFFIC SIGNAL LAMP RED LED KIT	EACH	15
TRAFFIC SIGNAL LAMP YELLOW LED KIT	EACH	15
TRAFFIC SIGNAL LAMP GREEN LED KIT	EACH	15
TRAFFIC SIGNAL LAMP GREEN ARROW LED KIT	EACH	3
TRAFFIC SIGNAL LAMP YELLOW ARROW LED KIT	EACH	3
TRAFFIC SIGNAL LAMP WALK LED KIT	EACH	8
TRAFFIC SIGNAL LAMP DON'T WALK LED KIT	EACH	8
ENTRANCE HEAD	EACH	1
CIRCUIT BREAKER & BOX	EACH	1
GUY WIRE GUARD	EACH	As Req'd
GUY WIRE CLAMP	EACH	As Req'd
THIMBLE EYE ANCHOR ROD	EACH	As Req'd
PEDESTRIAN PUSHBUTTON W/SIGN	EACH	8
LEAD-IN WIRE No. 6 A.W.G. 1/C (TYPE THWN)	LIN. m	44m
STANDARD 1C #8 (GROUND)	LIN. m	199.1m
MULTI-CONDUCTOR CABLE No. 16 A.W.G. 3/C (V3)	LIN. m	177.1m
MULTI-CONDUCTOR CABLE No. 14 A.W.G. 7/C	LIN. m	354.2m
VIDEO CABLE 75 OHM COAXIAL (BELDON 8281) (CX)	LIN. m	177.1m
CONDUIT 50mm PVC - WESTAR	LIN. m	114.0m
CONDUIT 25mm RGC	LIN. m	22.0m
CONDUIT 50mm RGC	LIN. m	8.5m
CONDUIT 75mm RGC	LIN. m	145.8m
CAMERA HOUSING	EACH	4
VIDEO DETECTION CAMERA & MOUNTING HARDWARE (RISER BRACKET)	EACH	4
VIDEO DETECTION PROCESSOR UNIT	EACH	4
VIDEO MONITOR	EACH	1
CAMERA CHARGED COUPLING DEVICE	EACH	4
TETHER WIRE 1/4" ASTM A475 SIEMENS-MARTIN	LIN. m	As Req'd
GRADE MIN.		
REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT **	L.S.	-
STREET NAME SIGNS W/MOUNTING HARDWARE (D-3)	EACH	4
LEFT TURN YIELD ON GREEN W/MOUNTING HARDWARE (R10-12)	EACH	3
SPLICE KIT (TRAFFIC INTERCONNECT)	EACH	X

General Notes

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING AND INSTALLING THE CONTROLLER, CABINET, CONCRETE BASE, AND FOR ALL EQUIPMENT NECESSARY FOR THE COMPLETE AND SATISFACTORY OPERATION OF THE TRAFFIC SIGNAL, WHETHER SAID EQUIPMENT IS SPECIFICALLY MENTIONED OR NOT.
- LENGTHS GIVEN ARE TO CENTERLINE OF POLE/BOX AND DO NOT INCLUDE LENGTHS FOR ELBOW AND RISERS.
- SIGNAL HEADS, PEDESTRIAN SIGNALS, TRAFFIC SIGNS & ETC. INCLUDE ALL BRACKETS, HARDWARE & OTHER INCIDENTALS NECESSARY FOR INSTALLATION.
- SEE CITY OF WICHITA STANDARDS SPECIFICATIONS FOR ADDITIONAL WIRING NOTES.

SPECIAL FINISH FOR TRAFFIC SIGNAL EQUIPMENT:

The traffic signal controller cabinet, brackets, sign blank backs, signal backs and other exposed surfaces shall be shop painted with an aerosol lacquer cellulose ester to match the traffic signal pole color. The contractor shall submit two copies of the proposed coating system to the City for approval application.

TRAFFIC SIGNAL POLE & PEDESTAL EXTERIOR COATING:

In addition to being galvanized, all exterior surfaces shall be coated with zinc rich epoxy powder to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and partially cured in a gas fired convection oven by heating the steel substrate to minimum of 250 degrees Fahrenheit.

The powder primed surface shall be coated with a intermediate coat of polyester powder to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and cured by heating the substrate in a convection oven to a minimum of 350 degrees and a maximum of 400 degrees Fahrenheit.

The intermediate coat shall be top coated with one coat if high-build acrylic polyurethane enamel to a minimum dry film thickness of 2.0 mils. The coating shall be electrostatically applied and cured by heating the substrate in a convection oven to a minimum of 225 degrees Fahrenheit. The final top coating shall be BLACK.

CHART 'A' - SIGNAL INVENTORY				
NO. WAYS	NO. SECTIONS (Per Face)	SIGNAL FACE ARRANGEMENT	MOUNTING TYPE	QTY
1	3	A	TYPE I	8
1	5	I	TYPE I	3
1	3	A	TYPE III	4
1	2	K (SYMB)	TYPE II	4

TRAFFIC MANHOLE SUMMARY	
STATION	DIST. - SIDE
B.L. 'A' Sta. 0+482.5	5.1m Lt
B.L. 'A' Sta. 0+474.9	22.4m Rt
B.L. 'B' Sta. 1+014.5	8.5m Rt
B.L. 'B' Sta. 1+024.5	17.2m Lt


CHART C		
CONDUIT SIZE (Millimeters)	TRENCHED (Meters)	PUSHED (Meters)
50mm PVC	114.0	-
25mm RGC	22.0	-
50mm RGC	8.5	-
75mm RGC	145.8	-

CHART 'B' - TRAFFIC SIGNAL POLES						
STATION	DIST.	SIDE	ARM LENGTH (Meters)	NO. OF SIGNALS ON ARM	SIGNAL SPACING (Meters)	TYPE
B.L."A"Sta. 0+482.1,	5.9m	Lt.	15.2m	3	7.8-3.4-3.4	JU
B.L."A"Sta. 0+476.3,	25.3m	Rt.	12.2m	3	5.0-3.4-3.4	JU
B.L."B"Sta. 1+014.8,	9.4m	Rt.	14.0m	3	6.3-3.4-3.4	JU
B.L."B"Sta. 1+023.0,	20.1m	Lt.	13.4m	2	9.3-3.4	JU

CHART 'D' - STREET NAME SIGN SUMMARY				
LEGEND	TYPE	QTY	UNITS	SIZE (Millimeters)
Harry	D-3	2	EA	750 x 1500
McLean Blvd.	D-3	2	EA	750 x 1500

TYPE 170 CONTROLLER SETTINGS																				
WAPITI PROGRAM									Nominal Display											
Phase									Time Clock		Features									
Interval		1	2	3	4	5	6	7	8				1	2	3	4	5	6	7	8
	WBLT	EB	SBLT	NB	EBLT	WB	NBLT	SB												
Max.	0	0	80	30	80	30	80	30	80	0	Year	Veh Recall					X			X
Max. 2	1	0	80	30	80	30	80	30	80	1	Month	Ped Recall								
Walk	2	0	8	0	8	0	8	0	8	2	Day/Month	Red Lock								
Fl. Dw.	3	0	15	0	15	0	15	0	15	3	Day/Week	Yel Lock								
Max. Init.	4	0	10	6	10	6	10	6	10	4	Hour	0 Permit					X	X	X	X
Min. Green	5	0	8	5	8	5	8	5	8	5	Minute	Ped Phases		X		X				
TBR	6	0	15	1	15	1	15	1	15	6	Second	Lead Phases			X		X		X	
TTR	7	0	25	1	25	1	25	1	25	7		Dbl Entry								
	8									8		Sequential								
Passage	9	0.0	3.0	1.0	3.0	1.0	3.0	1.0	3.0	9		Start Up Yel		X				X		
Min. Gap	a	0.0	1.5	1.0	1.5	1.0	1.5	1.0	1.5	a		Overlap A								
Add Act	b	0.0	1.3	1.0	1.3	1.0	1.3	1.0	1.3	b		Overlap B								
Yellow	c	0.0	3.0	3.0	4.0	3.0	3.0	3.0	4.0	c		Overlap C								
Red Cir	d	0.0	1.5	1.0	1.5	1.0	1.5	1.0	1.5	d		Overlap D								
Red Rev	e	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	e		Exclusive								
Walk II	f	0	0	0	0	0	0	0	0	f		Sim Gap								
Contractor shall time the signals based on the information above.																				

Contractor shall time the signals based on the information above.



NOTE

ALL SIGNAL CABLE SPLICES SHALL BE MADE ABOVE GROUND IN POLE OR PEDESTAL BASES.

2 m OF SLACK OR EXCESS CABLE, AS APPLICABLE, SHALL BE LEFT IN EACH TRAFFIC MANHOLE.

ONE SEVEN CONDUCTOR CABLE SHALL BE RUN FROM THE CONTROLLER TO EACH SIGNAL POLE FOR APPLICABLE FIVE-SECTION SIGNAL HEAD (LEFT TURN SIGNAL). THE FOLLOWING COLOR CODES SHALL BE USED:

WHITE	COMMON
RED	RED BALL
GREEN	GREEN BALL
ORANGE	YELLOW BALL
BLUE	GREEN ARROW
BLACK	YELLOW ARROW
WHITE W/BLACK	STREET NAME SIGN (WHERE)

ONE SEVEN CONDUCTOR CABLE SHALL BE RUN FROM THE CONTROLLER TO EACH SIGNAL POLE FOR PEDESTRIAN MOVEMENT. THE FOLLOWING COLOR CODES SHALL BE USED:


RED	DON'T WALK (PHASE 2 OR 6)
GREEN	WALK (PHASE 2 OR 6)
ORANGE	PUSH BUTTON (PHASE 2 OR 6)
WHITE W/BLACK	DON'T WALK (PHASE 4 OR 8)
BLUE	WALK (PHASE 4 OR 8)
BLACK	PUSH BUTTON (PHASE 4 OR 8)
WHITE	COMMON

A SINGLE CONDUCTOR STRANDED NO. 8 GREEN WIRE SHALL CARRY THE EQUIPMENT GROUND FROM THE GROUNDING LUG OF ALL SIGNAL POLES TO THE CONTROLLER CABINET AND THE POWER DISCONNECT BOX.

ONE 75 OHM COAXIAL CABLE (BELDON 8281) SHALL BE RUN FROM THE CONTROLLER TO EACH SIGNAL POLE FOR VIDEO TRANSMISSION (CX).

ONE THREE CONDUCTOR CABLE SHALL BE RUN FROM THE CONTROLLER TO EACH SIGNAL POLE FOR CAMERA POWER (V3).

TYPICAL TRAFFIC SIGNAL HEADS



PROJECT NUMBER 472-83781		SHEET NAME Wiring	ENGINEERING DIRECTORY F:\HarryMcLean\Traffic	
DESIGN JFB	DRAWN KWR	APPROVED JFB	DATE Aug 2003	SCALE Noted
		BAUGHMAN NO 01-03-E943		

CAPITAL IMPROVEMENT PROJECT WIRING PLAN	
HARRY & MCLEAN INTERSECTION IMPROVEMENTS	

BAUGHMAN COMPANY, P.A. ENGINEERING, SURVEYING, & PLANNING 318-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211	
SHEET OF 25 56	