FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87-N-0223-01	2002	29	56

BENCHMARK
BM #1 – City of Wichita Disc Located at the SW Corner of the Harry Street Bridge at McLean. Elev. 394.998 SI Units (1295.93)

Scale: 1:200

B.L. 'A' Sta. 0+422. 10.3m Lt. Install R2–1 per Detail See Marking & Signing Detail

B.L. 'A' Sta. 0+413.2 11.4m Lt. Install RJ–9b per Detail See Marking & Signing Detail

B.L. "A" Sta. 0+482.1, 5.9m Lt. Install SNS per Detail See Marking & Signing Detail

B.L. 'A' Sta. 0+371.0, 8.8m Rt Install R3–9b per Detail See Marking & Signing Detail

B.L. "B" Sta. 1+014.8, 9.4m Rt. Install SNS per Detail See Sheet 32.

B.L. 'A' Sta. 0+478.9 30.5m Rt. Install R2–1 per Detail See Marking & Signing Detail

B.L. 'A' Sta. 0+035.740 Match Existing Pavement Markings & Begin Marking & Signing

McLEAN BLVD.

HARRY STREET BRIDGE
Baseline C

Baseline A

Baseline B

ARKANSAS RIVER

	MARKING TOTALS THIS SHEET	UNIT	TOTAL
1	150mm White	m	64.83
2	100mm White	m	0.00
3	300mm White	m	0.00
4	100mm Yellow	m	386.00
5	300mm Yellow	m	10.53
6	600mm White	m	22.30
	* FOR INFORMATION ONLY		

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472-83781	Mark01	F:\\HarryMcLean\Traffic

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
JFB	TA	JFB	Aug 2003	1:200	01-03-E943

CAPITAL IMPROVEMENT PROJECT
MARKING & SIGNING PLAN
HARRY & MCLEAN INTERSECTION IMPROVEMENTS

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

SHEET 29 OF 56

KDOT METRIC