F.H.W.A. REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87 N-0230-01	2003	16	73

SCHEDULE OF INLETS & MANHOLES

INLET NO.	STATION	SIDE	TYPE (EACH) TYPE 1 INLET	TYPE (EACH) TYPE P MANHOLE	SEWER DATA INFLOW PIPES SIZE mm	INFLOW PIPES ℄ ELEV.	INFLOW PIPES SIZE mm	INFLOW PIPES ℄ ELEV.	INFLOW PIPES SIZE mm	INFLOW PIPES ℄ ELEV.	OUTFLOW PIPES SIZE mm	OUTFLOW PIPES ℄ ELEV.	OUTFLOW PIPES GRADE %	ELEV. TOP *	ELEV. FLOOR	SEWER EXCAVATION Common cu m For Info. Only	SEWER EXCAVATION Rock cu m For Info. Only	DIMENSIONS H m	DIMENSIONS W m	DIMENSIONS L m	NO. STEPS	Cast Iron kg	Cl. A Conc. cu m	Reinf. Steel kg	Struct. Steel kg	Cl. III Exc. cu m	STORM SEWER (RCP) (METERS) DIAMETER (mm) 375	450	525	600	END SECTION (RC) (EACH) 375 mm	450 mm	600 mm
																						← (For Information Only) →											
	1+660	Lt.									375	406.200	2.46			23										32.3				1		
	1+660	Rt.									375	406.000	2.14			23										32.9				1		
	1+693.5	Lt.	1		375	405.405					375	405.352	0.40	406.845	405.276	15		1.719	1.319	3.444		163.4	3.7	160		13.4	14.6						
	1+693.5	Rt.	1		375	405.296	375	405.294			450	405.218	0.40	406.845	405.142	73		1.853	1.319	3.444		163.4	3.9	160		14.6		79.2				
	1+775	Rt.		1	450	404.901					450	404.896	0.40	407.75	404.756	112											77.4				1	
	1+940	Lt.	1								375	407.500	1.00	408.993	407.424	15		1.719	1.321	1.900		81.7	2.4	27.2		10.6	14.6						
	1+940	Rt.	1		375	407.354	525	407.063			600	407.000	5.46	408.993	406.898	202		2.245	1.625	1.900		81.7	3.5	36.7		17.1			84.3	18.3			1
	TOTALS															463						409.2	13.5	383.9		55.7	94.4	156.6	84.3	18.3	2	1	1

* Note: Top Elevation is located as follows:
1. Curb Inlet – Top of Curb.

Note: Storm Sewer pipe shall be Class III reinforced concrete pipe in accordance with the city of Wichita Standard Specifications.

KANSAS_DEPARTMENT_OF_TRANSPORTATION

SCHEDULE OF INLETS

13TH STREET NORTH OVER COWSKIN CREEK

CITY OF WICHITA SEDGWICK COUNTY

Cook, Flatt & Strobel ENGINEERS, P.A.

DESIGNED ___ SCALE ___
DETAILED ___ DATE ___
QUANTITIES ___ SHEET ___ OF ___

02-517

J:\02-517\SCHEDULE SCALE