STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0230-01	2003	738	73

SUMMARY OF PAVEMENT MARKINGS

LOCATION	100 mm Solid WHITE Edge Line	150 mm Broken WHITE Lane Line	150 mm Broken WHITE Lane Line	150 mm Dotted WHITE Extension Line	150 mm Solid WHITE LANE LINE	200 mm Solid WHITE Gore Line	300 mm Solid WHITE Diagonal Line	300 mm Solid WHITE Chevron Line	300 mm Solid WHITE Type I Crosswalk Line	600 mm Solid WHITE Type II Crosswalk Line	600 mm Solid WHITE Stop Line	100 mm Solid YELLOW Edge Line	100 mm Solid YELLOW Double Line	100 mm Solid YELLOW Line	100 mm Broken YELLOW Line	300 mm Solid YELLOW Diagonal Line
Sta. 1+600 to Sta. 1+675 (Transition)	150												150			
Sta. 1+675 to Sta. 2+048.37		187											717			
Sta. 14+01.44 to Sta. 37+01.19	1402													250	176	
TOTALS	1552	187											867	250	176	

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION								STOP	ONLY	X-ING	SCHOOL
TOTALS											

NOTE: For specific pavement marking details and dimensions see plan sheets

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

RECAPITULATION OF QUANTITIES

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(100 mm)		m
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(150 mm)		m
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(200 mm)		m
PAVEMENT MARKING (MULTI-COMPONENT)(WHITE)(300 mm)		m
		m
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(100 mm)		m
PAVEMENT MARKING (MULTI-COMPONENT)(YELLOW)(300 mm)		m
		EACH
		EACH
		EACH
		EACH
		m
PAVEMENT MARKING (EPOXY)(WHITE)(100mm)		m
PAVEMENT MARKING (EPOXY)(WHITE)(150mm)		m
PAVEMENT MARKING (EPOXY)(WHITE)(200mm)		m
PAVEMENT MARKING (EPOXY)(WHITE)(300mm)		m
PAVEMENT MARKING (EPOXY)(YELLOW)(100mm)		m
PAVEMENT MARKING (EPOXY)(YELLOW)(300mm)		m
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(100mm)	1552	m
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(150mm)	187	m
PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(YELLOW)(100mm)	1293	m
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)( )		EACH
PAVEMENT MARKING (PATTERNED COLD PLASTIC)(WHITE)(150mm)		m
		m
		m
PAVEMENT MARKING REMOVAL		m

NOTE: PAVEMENT MARKING MATERIAL AND INSTALLATION SHALL CONFORM TO KDOT SPECIFICATIONS.

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

NO.	DATE	REVISION	BY	APP'D
3				
2	01/02/03	Change materials, RR symbol	GJI	LGV
1	03/06/98	Add "NO PASSING" zone note	JFF	LGV

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

~~TEJIIST~~ 03/15/96

FHWA APPROVAL	01/17/03	APP'D JAMES E. TOBABEN	
DESIGNED JFF	DETAILED GSB	QUANTITIES GJI	TRACED
DESIGN CK. JET	DETAIL CK. JFF	QUAN. CK. GJO	TRACE CK.

Plotted By : @@USERNAME@@ Thacher Bldg., 4th Floor
Plot File : @@@@@@@@@@@@DGNSPEC@@@@@@@@@@@@
Plot Date : @@@@@SYTIME@@@@@

CAB 262