5+00
MATCH POINT

INSTALL 222.2 SQ. YARDS OF 7" SHOULDER ROCK

4" WHITE STRIPE

CENTRAL MAIZE MIDDLE SCHOOL

INSTALL 333.4 SQ. YARDS 7" A.C. PAVEMENT (2" SURFACE)

10+00
MATCH POINT

REGRADE DITCH AS NEEDED, TYP.

4" BROKEN YELLOW (Typ.)

5+00 SAWED EDGE TYLER 6+00 7+00 CENTERLINE = SECTION LINE 8+00 S. 00°35'33" W. 9+00 10+00

36' E-E

11'
12'
11'

EXISTING A.C. PAVEMENT

1/2" Rebar

4"

4" YELLOW (Typ.)

4" WHITE STRIPE

REGRADE DITCH AS NEEDED, TYP.

Rebar

TYLER'S LANDING ADDITION

INSTALL 222.2 SQ. YARDS OF 7" SHOULDER ROCK

INSTALL 333.4 SQ. YARDS 7" A.C. PAVEMENT (2" SURFACE)

5+00
MATCH POINT

10+00
MATCH POINT

SCALE: 1"=20'

TYLER PAVING
Sta. 5+00 to Sta. 10+00
WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN	MWS
DRAWN	TEB
REVIEW	
UTILITY	
DATE	April 17, 2003
RB JOB	22YT
SHEET	4 OF 14
DRAWING FILE	Base [PAVE01]
PROJECT NUMBER	472-83713/83693