LINE 1C
SEE SHEET 24

STA 7+47.91 LINE 1 =
STA 0+00 LINE 1C
MILLRUN STA 2+02.90, 16.17' RT F.I.F.
CONSTRUCT STD TYPE 1-A
CURB INLET (DOUBLE)
10' X 5'
TOP ELEV. = 1392.04

STA 9+77.38 LINE 1
CONSTRUCT STANDARD
TYPE P MH
W/ BEEHIVE INLET
TOP ELEV. = 1391.40

STA 11+30.27 LINE 1
CONSTRUCT STANDARD
TYPE P MH
W/ BEEHIVE INLET
TOP ELEV. = 1392.0

STA 5+82.7 TO
STA 6+29.9
PLACE 47 L.F.
FLOWABLE FILL

STA 5+80.16 LINE 1
CONSTRUCT STANDARD
TYPE P MH
5.0' DIAMETER
SEE SHEET 21

Spyglass
Proposed AC Pavement

Sawmill Creek Addition

Prop Water
Prop SS
Exist SS
20' Utility Easement
Utility Easement by Separate Instrument

SCALE 1" = 20'

STA 5+80.16 LINE 1
CONSTRUCT STANDARD
TYPE P MH
5.0' DIAMETER

STA 5+82.7 TO
STA 6+29.9
PLACE 47.2 L.F.
FLOWABLE FILL

Prop 8" Water

STA 7+47.91 LINE 1 =
STA 0+00 LINE 1C
CONSTRUCT STD TYPE 1-A
CURB INLET (DOUBLE)
11' X 5'

LINE 1

EXISTING GROUND
FINISHED GRADE

STA 9+77.38 LINE 1
CONSTRUCT STANDARD
TYPE P MH
W/ BEEHIVE INLET
TOP ELEV. = 1391.40

STA 11+30.27 LINE 1
CONSTRUCT STANDARD
TYPE P MH
W/ BEEHIVE INLET
TOP ELEV. = 1392.0

PROP SS

SS SERVICE

SS SERVICE

167.8 L.F. 24" PIPE @ 0.45%

229.5 L.F. 18" PIPE @ 0.86%

152.9 L.F. 18" PIPE @ 0.86%

1381.52' FL OUT
1381.62' FL OUT
1382.17' FL
1382.39' FL OUT
1383.05' FL IN (NE)
1382.80' FL IN (SW)
1383.25' FL
1384.11' FL
1384.78' FL OUT
1384.78' FL IN
1384.98' FL
1385.94' FL
1386.10' FL OUT
1386.35' FL IN

5+80.16
7+00
7+47.91
8+00
9+00
9+77.38
10+00
11+00
11+30.27

1390
1385
1380
1375

REVISED	
DRAWN	EJG
DESIGN	CMB
UTILITY	
DATE	Nov. 26, 2002
REVIEW	
PROJECT NUMBER	472-83624
DRAWING FILE	Storm Sewer [SWS 02]

Sawmill Creek Addition
Storm Sewer
WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4821 fax
E-mail: info@rbkansas.com

RB JOB 2183E
SHEET 22 OF 40