



**K** SIDEWALK DEMOLITION PLAN  
 1" = 10'-0"  
 NORTH

NOTE: TREES TO BE REMOVED  
 W/ EX. TREE GRATE - SAVE  
 GRATE FOR REUSE.

- NOTE:
- ALL HARDSCAPE REMOVAL FROM BACK OF CURB TO CENTERLINE OF ROAD - REFER TO CIVIL DRAWINGS.
  - CONCRETE CURB REMOVAL - REFER TO CIVIL SHEETS.
  - STORM SEWER ADJUSTMENT - REFER TO CIVIL SHEETS FOR SWS LINE AND INLET ADJUSTMENTS.
  - VALVES, METERS, AND VAULTS - TO REMAIN IN PLACE UNLESS OTHERWISE SPECIFIED.
  - STRIPING REMOVAL - REFER TO CIVIL SHEETS.
  - SIDEWALK CONCRETE REMOVAL - SAW-CUT ALL EDGES AT NEAREST CONTROL JOINT BEYOND INDICATED LIMITS
  - PAVER REMOVAL - PULL PAVERS & BASE MATERIAL (SEE PAVER SCHEDULE FOR ASSUMED BASE) (NOTIFY LANDSCAPE ARCHITECT IF OTHER BASE MATERIAL IS FOUND).
  - LIMITS OF DEMOLITION WORK TO BE APPROXIMATELY 8LF FROM BACK-OF-CURB AT CURB RAMP LOCATION, 8LF FROM BACK-OF-CURB AT BUS SHELTER LOCATIONS, & 5LF FROM BACK-OF-CURB IN ALL OTHER LOCATIONS NOT OTHERWISE INDICATED.

DOUGLAS AVE.  
 STREETSCAPE  
 IMPROVEMENTS  
 WICHITA, KS

**LKArchitecture**  
 Architecture • Engineering • Planning • Interior Design • Landscape Architecture

LK Architecture Inc. ©  
 345 RIVERVIEW WICHITA, KS 67203  
 Phone (316) 268-0230 Fax: (316) 268-0205

CONTACT: Jeffery A. Best, ASLA

PROJECT NUMBER:  
**15749.01**

SHEET TITLE:  
**SIDEWALK  
 DEMOLITION PLAN**

SHEET NUMBER:  
**DE1.11**