


|        |               |      |           |              |
|--------|---------------|------|-----------|--------------|
| STATE  | PROJECT NO.   | YEAR | SHEET NO. | TOTAL SHEETS |
| KANSAS | 87 xx-xxxx-01 | 2016 | 24        | 24           |

|  | Qty   | UOM |
|--|-------|-----|
| <b>Measured Quantity Bid Items (Removal)</b>                     |       |     |
| Concrete Curb Removal  | 167   | LF  |
| Concrete Sidewalk, Drive & Curb Removal                          | 153   | SY  |
| Removal of Existing Markings (Grinding)                          | 310   | LF  |
| Fence Removed (Chainlink)  | 130   | LF  |
| Tree Removed, Small  | 5     | EA  |
| <b>Measured Quantity Bid Items (Pavement)</b>                    |       |     |
| Wheelchair Ramp w/ Detectable Warnings                           | 11    | EA  |
| Concrete Sidewalk (5")   | 11548 | SF  |
| Concrete Sidewalk (5") with Curb                                 | 1807  | SF  |
| Concrete Curb & Gutter   | 14    | LF  |
| Precast Concrete Block Retaining Wall                            | 39    | LF  |
| <b>Measured Quantity Bid Items (Traffic)</b>                     |       |     |
| Pavement Marking (Thermoplastic)(Sharrows)                       | 102   | EA  |
| Pavement Marking (Multi-component)(White)(24" x 36")(Sharktooth) | 40    | EA  |
| Pavement Marking (Multi-Component)(White)(12" Solid)             | 65    | LF  |
| Pavement Marking (Multi-Component)(White)(24" Solid)             | 412   | LF  |
| Rectangular Rapid Flash Beacon Assembly                          | 8     | EA  |
| <b>Measured Quantity Bid Items (Site Restoration)</b>            |       |     |
| Sodding (Bermuda)  | 360   | SY  |
| Fence (4', Black Vinyl Coated)                                   | 130   | LF  |
| <b>Lump Sum Bid Items</b>  |       |     |
| Traffic Control  | 1     | LS  |
| Site Clearing & Restoration                                      | 1     | LS  |
| Mobilization   | 1     | LS  |
| Street Signage   | 1     | LS  |

F:\Projects\Projects 4100-4199\4180H (NSU to Schweiter Bikeway)\4180-Detail Base-Phase 2.dwg

|   |  |  |                           |
|---|--|--|---------------------------|
| <b>Green Street Bikeway<br/>Summary of Quantities</b>                   |  |  |                           |
| SEAL  | <br><b>RUGGLES &amp; BOHM</b> | ENGINEERING   SURVEYING   LANDSCAPE ARCHITECTURE   GOVERNMENT  |                           |
|   |  | <small>924 NORTH MAIN WICHITA, KANSAS 67203 P (316) 264-8008 F (316) 264-4621 WWW.RBKANSAS.COM</small> |                           |
| PROJECT NUMBER<br><b>472-85112</b>                                      | RB JOB NO.<br><b>4180H</b>   | DWG. SCALE<br>...  | DATE<br><b>APRIL 2016</b> |
| DRAWING FILE<br><b>4180-Detail Base-Phase 2 [Summary of Quantities]</b> |  |  | DESIGN<br><b>BDT</b>      |
|   |  |  | DRAWN<br><b>DK</b>        |
|   |  |  | REVIEW                    |
|   |  |  | SHEET<br><b>24</b>        |
|   |  |  | OF<br><b>24</b>           |