

CREST CY Excavation (unadjusted)				CREST CY Compacted Fill (unadjusted)				CREST CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+38.89	15.45	0.00	0.00	0+38.89	1.25	0.00	0.00	0+38.89	14.52	0.00	0.00
0+50	15.46	6.36	6.36	0+50	1.25	0.51	0.51	0+50	13.78	5.82	5.82
1+00	15.46	28.63	34.99	1+00	1.25	2.52	3.03	1+00	13.30	24.89	30.71
1+50	15.46	28.63	63.62	1+50	1.25	2.53	5.57	1+50	13.30	24.47	55.18
2+00	15.46	28.63	92.25	2+00	1.25	2.39	7.95	2+00	13.30	24.58	79.76
2+50	15.46	28.63	120.88	2+50	1.25	2.31	10.26	2+50	13.30	24.64	104.40
2+85.25	15.46	20.18	141.06	2+85.25	2.16	2.23	12.49	2+85.25	12.87	17.09	121.49
3+19.25	23.15	24.31	165.37	3+19.25	3.97	3.86	16.36	3+19.25	7.10	12.57	134.06
3+53.25	15.46	24.31	189.68	3+53.25	2.17	3.87	20.22	3+53.25	12.87	12.57	146.63
4+00	15.46	26.77	216.45	4+00	1.25	2.96	23.18	4+00	13.31	22.67	169.30
4+50	15.46	28.63	245.08	4+50	1.25	2.31	25.50	4+50	13.31	24.65	193.95
5+00	15.46	28.63	273.71	5+00	1.25	2.24	27.74	5+00	13.31	24.70	218.65
5+10.51	15.46	6.02	279.73	5+10.51	1.25	0.39	28.13	5+10.51	13.31	5.25	223.90

FAIRFAX CY Excavation (unadjusted)				FAIRFAX CY Compacted Fill (unadjusted)				FAIRFAX CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+38.58	15.45	0.00	0.00	0+38.58	0.00	0.00	0.00	0+38.58	15.77	0.00	0.00
0+50	15.46	6.53	6.53	0+50	0.00	0.00	0.00	0+50	14.53	6.42	6.42
1+00	15.46	28.63	35.17	1+00	0.00	0.00	0.00	1+00	14.54	26.80	33.22
1+50	15.46	28.63	63.80	1+50	0.00	0.00	0.00	1+50	14.55	26.82	60.04
2+00	15.46	28.63	92.43	2+00	0.00	0.00	0.00	2+00	14.55	26.88	86.92
2+50	15.46	28.63	121.06	2+50	0.00	0.00	0.00	2+50	14.55	27.01	113.93
2+58.32	15.46	4.76	125.83	2+58.32	0.00	0.00	0.00	2+58.32	14.56	4.50	118.42

