SCALE: 1" = 60'
• = Iron

Contractor to Construct 1000 L.F. V-ditch for pond outfall. Contractor shall grade ditch from Elev. = 147.0 to Elev. = 145.0. Cost of ditch incidental to "Mass Grading." Install 15 S.Y. Light Stone Rip-Rap as Shown.

Area to be graded

145 Existing Grade

145 Proposed Grade

TYLER ROAD (79TH ST. W.)

BROOKVIEW

W. 34TH CT. N.

W. 34TH CT. S.

W. 34TH ST. NORTH

VALENE CIR.

LANG

RIDGE

RIDGE

SEC. 33, 27

KANSAS GAS AND ELECTRIC COMPANY RIGHT-OF-WAY EASEMENT (CASE # 1021)

KANSAS GAS AND ELECTRIC COMPANY RIGHT-OF-WAY EASEMENT (MISC. BOOK 445, PG. 381)

TYLER'S LANDING ADDITION
MASS GRADING PLAN
CITY OF WICHITA, KANSAS

BAUGHMAN COMPANY P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

PROJECT NUMBER	SHEET
488-83579	14 OF 32

DESIGN	DRAWN	APPROVED	DATE	SCALE
SCL	SCL	NBW	11/04/02	1"=60'

GRADE.DWG