


RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
<i>LUMP SUM BID ITEMS - PAVING (707092)</i>		
Mobilization	1	LS
Removal of Existing Structures	1	LS
Concrete &/or Asphalt Pavement Removed	117	sy
Concrete C & G Removed	816	lf
Excavation	488	cy
Fill, Compacted (95% Density)	173	cy
<i>MEASURED QUANTITY BID ITEMS - PAVING (707092)</i>		
Concrete Pavement (VG) 8" (Reinf.)	40	sy
AC Pavement 7" (5" Bit. Base) (BM-2)	368	sy
2" AC Pavement Mill & Overlay (BM-2, PG 70-28)	286.3	sy
Crushed Rock Base 7", Reinforced	46	sy
Crushed Rock Base 8", Reinforced	685	sy
Concrete C & G, Comb. Type I (6" & 1-1/2")	815	lf
Concrete Curb, Mono Edge (6" & 1-1/2")	56	lf
Wheelchair Ramp w/ Detectable Warnings	4	ea
Concrete Sidewalk 4"	2923	sf
Concrete Driveway 8" (Reinforced)	351	sf
Saw & Seal Joints	852	lf
Fence (Temporary Construction)	15	lf
Valve Box Adjusted	2	ea
<i>MEASURED QUANTITY BID ITEMS - DRAINAGE (707092)</i>		
Inlet, Curb (Type I) (Single) (L=5', W=3')	2	ea
Inlet Hookup	2	ea
Pipe, SWS 15" (RCP)	16	lf
Fill, Sand (Flushed & Vibrated)	16	lf
Pipe, PVC 4", Perforated (Inlet Underdrain)	22	lf
<i>LUMP SUM BID ITEMS - TRAFFIC (707092)</i>		
Signing	1	LS
Pavement Marking	1	LS
Traffic Signalization (35th & Oliver)	1	LS
Traffic Control	1	LS
<i>MEASURED QUANTITY BID ITEMS - TRAFFIC (707092)</i>		
Sign, Electronic Portable Message	100	Day
<i>LUMP SUM BID ITEMS - LANDSCAPING (707092)</i>		
Concrete Pavement 4" (Plain)	11	sy
Sodding, Buffalo	1	LS
Sodding, Fescue	1	LS
<i>MEASURED QUANTITY BID ITEMS - LANDSCAPING (707092)</i>		
Small Tree Removal	7	ea
<i>MEASURED QUANTITY BID ITEMS - BMP's (707092)</i>		
BMP, Curb Inlet Protection	2	ea
BMP, Silt Fence	475	lf
BMP, Back of Curb Protection	914	lf

See Sh. No. 26 for Traffic Signal Bill of Materials.
 See Sh. No. 30 for Summary of Pavement Markings.

Saved: 03-30-2017 10:04:25 AM by CP
 Plot Scale: 1:1 04-04-2017 9:43:33 AM by CP
 U:\Wichita-Civil\2015\15954\Drawings\15954-000-166-RECAPITULATION OF QUANTITIES

No.	Revision	By	Date
35TH STREET NORTH AND OLIVER STREET TRAFFIC SIGNALIZATION RECAPITULATION OF QUANTITIES GARY JANZEN, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-85278			
		PROFESSIONAL ENGINEERING CONSULTANTS, P.A. 303 SOUTH TOPEKA WICHITA, KS 67202 316-262-2691 www.pec1.com	
Designed by	SAC, BMM	Job No.	31-15954-000
Drawn by	BJS	Date	April 2017
			Sht. 16 of 36