



RIDGE PORT

Ridge Port CL CY Excavation (unadjusted)			
Station	Area	Volume	Cumulative Volume
6+92.01	35.26	0.00	0.00
7+50.00	15.78	54.81	54.81
8+00.00	16.47	29.86	84.67
8+17.01	19.39	11.29	95.97
8+51.01	41.11	38.09	134.06
8+85.01	20.12	38.55	172.61
9+50.00	24.65	53.88	226.49
10+00.00	36.55	56.80	283.29
10+50.00	50.69	81.44	364.73
11+25.00	65.12	161.36	526.09
11+74.96	24.34	82.33	608.42
12+07.63	22.07	28.05	636.47

Ridge Port CL CY Loose Fill (unadjusted)			
Station	Area	Volume	Cumulative Volume
6+92.01	4.64	0.00	0.00
7+50.00	18.57	24.93	24.93
8+00.00	16.44	32.42	57.35
8+17.01	15.09	9.93	67.27
8+51.01	0.00	9.50	76.77
8+85.01	17.01	10.71	87.48
9+50.00	12.35	35.33	122.82
10+00.00	2.83	14.18	137.00
10+50.00	0.85	3.13	140.13
11+25.00	1.28	2.84	142.97
11+74.96	8.62	8.98	151.94
12+07.63	13.43	12.89	164.83

Ridge Port CL CY Compacted Fill (unadjusted)			
Station	Area	Volume	Cumulative Volume
6+92.01	0.17	0.00	0.00
7+50.00	5.07	5.62	5.62
8+00.00	3.74	8.15	13.78
8+17.01	2.70	2.03	15.81
8+51.01	0.00	1.70	17.51
8+85.01	2.98	1.87	19.38
9+50.00	3.07	7.28	26.66
10+00.00	2.50	4.89	31.55
10+50.00	1.82	3.60	35.15
11+25.00	2.30	5.49	40.64
11+74.96	1.95	4.32	44.96
12+07.63	2.85	3.19	48.14