FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0191-01	2002	2	92

BY	DATE
REFERENCES NOTED	
REFERENCES CHECKED	

1. Underground utility service lines and overhead utility pole lines are to be adjusted by utility companies if necessary prior to construction unless the plans specifically call for their adjustment by the Contractor. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.

2. Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved.

3. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agricultural permit. Any material dumped in waters of the United States or wetlands is subject to U.S Corps of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.

4. The Contractor shall give all property owners and/or tenants of developed property abutting the construction of this project a minimum of ten (10) days notice prior to start of construction and again 48 hours prior to any work actually starting.

5. The Contractor shall be responsible for preserving shown property irons. The Contractor will be required to reestablish any shown property irons which are disturbed by his construction operations. Such irons shall be reestablished by a licensed Land Surveyor in accordance with state laws.

6. Contractor is required to provide a minimum notice of forty-eight (48) hours to utility companies prior to starting any excavation as follows:

   Kansas One-Call 687-2470

   The Contractor must notify the following before construction and in case of an emergency.

Cox Communications	262-0661
Kansas Gas Service	1-888-482-4950
Westar	383-8600
Aquila Net (UtiliCorp United)	1-800-303-0357
Southwestern Bell Telephone Company	1-800-870-8390
City of Wichita Water Department	262-6000
City of Wichita Sewer Maintenance	268-4071

7. Trees and shrubs to be removed are marked X. Trees or shrubs marked for removal, which in the opinion of the Engineer can be saved, shall be be spared. Tree and shrub disposal areas and disposal methods shall be approved by the Engineer.

8. Underground Irrigation Systems. Properties within the project may have underground irrigation systems (lawn sprinklers) which conflict with new construction. Contractor shall remove such components as needed during construction of the project. The irrigation system shall be reinstalled in like kind before project completion. Any irrigation system modifications required because of project improvements shall be coordinated with the property owner. Portions of underground irrigation systems not in conflict with new construction shall be protected from damage and shall remain in place. All work related to underground irrigation/sprinklers shall be bid 'SPRINKLER SYSTEM REPAIRS'. (Non-Participating)

9. Provide a full depth saw cut at locations where proposed construction abuts an existing surface course or pavement for which partial removal of that surface or pavement is required. Sawed joints to facilitate removal within one (1) meter of the existing joint will not be permitted and for such instances the limits of removal shall extend to the existing joint. Such saw cuts will not be paid for directly and this cost shall be considered as %%usubsidiary%%u to the removal of the surface or pavement.

10. All salvageable drainage pipes, manhole rings and covers, inlet grates, street signs, traffic poles and any other salvageable items shall be transported to the appropriate City yards for stockpile. Delivery of the items shall be paid through bid item "Transportation of Salvageable Materials". (Non-Participating)

11. Contractor shall arrange with the city survey crew for the replacement of section monuments as indicated on the plans according to the monument box detail on sheet _ of __ to be bid "Monument Box" per each.

12. Connection of proposed storm sewer to existing storm sewer and existing structure shall be Subsidiary to new pipe being connected to.

13. Driveways replaced with this project shall be a minimum of 3.65m in width.

14. Neither the City of Wichita nor the contractor shall be responsible for moving and resetting fences that are on the public right of way. The property owner shall be notified prior to construction to move the fence. If the fence is not removed by the time of construction, the contractor shall remove the fence and the fence shall be placed on private property.

15. Contractor shall maintain two-way traffic during the project for the entire length of the project. Traffic control shall be bid 'Lump Sum Traffic Control'.

16. Water meters lids shall be adjusted as needed. (Non-participating).

17. Manhole adjustments shall conform to City of Wichita Standard Specifications.

UTILITY CONTRACTOR LIST

Westar
1900 East Central
P.O. Box 208
Wichita, KS 67202
316-261-6251
Contact:

Kansas Gas Service
1021 East 26th Street North
P.O. Box 208
Wichita, KS 67202
316-832-3101
Contact: Jim Stoltz

Aquila Net (UtiliCorp United)
1611 S. Hoover
Wichita, KS 67209
316-941-1608
Contact: Calvin Briggs

Cox Communications
701 East Douglas
Wichita, KS 67202
316-262-4270
Contact: Bryan Rine

Southwestern Bell Telephone Co.
154 North Broadway
Wichita, KS 67202
316-268-2245
Contact: Bob Alley

Stormwater Utility
City of Wichita
City Hall - 8th Floor
455 North Main
Wichita, KS 67202
316-268-4498
Contact: Chris Carrier

Dept. of Water & Sewer
City of Wichita
City Hall - 8th Floor
455 North Main
Wichita, KS 67202
316-268-4555
Contacts: LaDonna Lawrenz (Sewer)
Bill Perkins (Water)

Traffic Engineering
City of Wichita
City Hall - 7th Floor
455 North Main
Wichita, KS 67202
316-268-4446
Contact: Scott Logan

Sedgwick County Emergency
Management Agency
535 N. Main, Suite B10
Wichita, KS 67203-3702
316-383-7546
Contact: Jack Kegley

HARRY IMPROVEMENTS
GENERAL NOTES
WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4821 fax
E-mail: info@rbkansas.com

DESIGN	MWS
DRAWN	TEB
REVIEW	
UTILITY	
DATE	Jan. 30, 2003

RB JOB 13041

SHEET 2 OF 92

DRAWING FILE	PROJECT NUMBER
General Notes	472-83685