CONDUIT DATA

ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL			CONDUIT FLOWLINES			STORM SEWER (LIN. FT.)								END SECTIONS (EACH)					
					TYPE OF CONDUIT																			
FROM	TO	STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	SIZE	MATERIAL	LENGTH (FT.)	INFLOW ELEVATION	OUTFLOW ELEVATION	COMMON (CU. YDS.)	12"	15"	18"	24"	48"	60"	7'X3'	7'X5'	12"	15"		AASHTO CONCRETE CLASS	SAND FILL, FLUSH & VIBRATE (L.F.)	REMARKS
101	100	96+79.00	Tyler Rd.	27.15' Rt.	15"	RCP	5.0	15" (W)	1323.14			5.0											5.0	Connect to Ex. SWS
102	101	96+76.00	Tyler Rd.	35.50' Rt.	12"	RCP	6.9	1325.58	1324.90		6.9								1					
151	150	97+95.00	Tyler Rd.	30.25' Rt.	4"	PVC	17.0	1325.69	1326.12															
201	200	50+59.00	2nd St.	17.77' Rt.	15"	RCP	5.0	15" (N)	1322.06			5.0											5.0	Connect to Ex. SWS
301	300	101+00.00	Tyler Rd.	70.00' Rt.	48"	RCP	107.5	48" (N)	1318.22						107.5								33.1	
302	301	100+65.88	Tyler Rd.	70.81' Rt.	48"	RCP	34.1	1320.07	1318.95						34.1									
303	301	101+00.00	Tyler Rd.	60.00' Rt.	15"	RCP	10.0	15" (E)	1321.20			10.0												
311	310	102+26.00	Tyler Rd.	37.67' Rt.	2-60"	RCP	15.7	2-60" (W)	1317.41							31.4							31.4	Connect to Ex. SWS
312	311	102+26.00	Tyler Rd.	52.00' Rt.	2-60"	RCP	14.3	2-60" (W)	1317.65							28.6								
313	311	101+95.00	Tyler Rd.	37.67' Rt.	15"	RCP	31.0	15" (N)	1321.40			31.0											31.0	
401	400	107+03.75	Tyler Rd.	28.50' Rt.	24"	RCP	43.0	24" (E)	1320.38					43.0									43.0	Connect to RCB
501	500	107+50.00	Tyler Rd.	37.67' Rt.	15"	RCP	13.2	15" (W)	1323.20			13.2											13.2	
551	550	109+25.00	Tyler Rd.	37.67' Rt.	15"	RCP	31.1	1321.61	1320.83			31.1								1				
601	602	113+03.00	Tyler Rd.	111.25' Rt.	7'x3'	RCB	25.8	1324.50	1324.40								25.8							
602	600	113+03.00	Tyler Rd.	81.00' Rt.	7'x5'	RCB	30.8	7'x5' (S)	1321.85									30.8						
603	602	113+15.00	Tyler Rd.	28.00' Rt.	48"	RCP	54.3	48" (E)	1322.03						54.3								25.3	
701	700	116+20.00	Tyler Rd.	37.50' Rt.	18"	RCP	30.0	18" (W)	1327.09				30.0										30.0	
TOTALS											6.9	95.3	30.0	43.0	195.9	60.0	25.8	30.8	1	1			217.0	

No.	Revision	By	Date

TYLER ROAD BETWEEN MAPLE AND CENTRAL
PAVING AND INCIDENTAL DRAINAGE IMPROVEMENTS

SCHEDULE OF INLETS AND MANHOLES

GARY JANZEN, P.E.- CITY ENGINEER
CITY OF WICHITA PROJECT NO. 472-85282

PEC
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
303 SOUTH TOPEKA WICHITA, KS 67202
316-262-2691 www.pec1.com

Designed by	CKC	Job No.	31-15956-000	Sht.	32 of 96
Drawn by	CP	Date	JULY 2017		

Saved: 07-20-2017 1:32:44 PM by CP
Plotted: 07-20-2017 1:33:37 PM by CP
U:\Wichita-Civil\2015\15956\000\Main-Trans\Drawings\15956-000-32C-SWS Schedule2