FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0229-01	2004	62	62

SUMMARY OF QUANTITIES

ITEM	QUANTITY	UNIT
Site Clearing and Preparation	1	L.S.
Common Excavation	1479	Cu. Meters
Uncompacted fill	67	Cu. Meters
Compaction of Earthwork (Type B) (MR-90)	453	Cu. Meters
Pavement Removal	6010	Sq. Meters
Removal of Existing Structures	1	L.S.
Crushed Stone Subgrade (150mm)	3378	Sq. Meters
Crushed Stone Subgrade (175mm)	2657	Sq. Meters
Geogrid Reinforcement (For Base)	6035	Sq. Meters
Concrete Pavement (250mm) (AE) (Reinf.)	3043	Sq. Meters
Concrete Pavement (200mm) (AE) (Reinf.)	1682	Sq. Meters
Concrete Pavement (250mm)(Reinf.) (V. Gutter)	883	Sq. Meters
Combined Curb and Gutter (150mm)	1300	Meters
Bituminous Base 100mm (BC-1)	1812	Sq. Meters
Overlay Surface 65mm (SC-1)	7773	Sq. Meters
Edge Curb (150mm)	200	Meters
Sidewalk Pavement (100mm)	1600	Sq. Meters
Wheelchair Ramp w/ Detectable Warning	26	Each
Inlet (Drop)	1	Each
Inlet (Type II)(Curb)	2	Each
Inlet (Type I)(Curb)	14	Each
Manhole (Type P)	1	Each
375mm Storm Sewer (RCP)	93	Meters
600mm Storm Sewer (RCP)	5	Meters
Manhole Adjustments (Include Frame & Cover)	14	L.S.
Field Office and Laboratory (Type A)	1	L.S.
Pavement Marking	1	L.S.
Monument Box	1	Each
Temporary signalization	1	L.S.
Traffic Control	1	L.S.
Traffic Signing	1	L.S.
Signalization	1	L.S.
Erosion Control (includes temporary seeding)	1	L.S.
Site Restoration (Includes Permanent Sodding)	1	L.S.
Mobilization	1	L.S.
Mobilization (DBE)	1	L.S.
MEASURED QUANTITY		
Concrete Pavement (200mm)(Reinf.) (Drives)	362	Sq. Meters
Concrete Pavement (200mm)(Reinf.) (Parking Lot)	44	Sq. Meters
Asph. Concrete Pavement (150mm) (Parking lot)	160	Sq. Meters
Asphalt overlay joint saw and seal	2775	Meters
Drive resurface (SA-X)	35	Sq. Meters
NON-PARTICIPATING		
Traffic Signs	1	L.S.
Transportation of Salvageable Material	1	L.S.

6-24-04 REVISED QUANTITIES
5-17-04 REVISED QUANTITIES

Revised 6-21-2004

HARRY STREET IMPROVEMENTS
SUMMARY OF QUANTITIES
WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN TCR
DRAWN TEB
REVIEW
UTILITY
DATE Apr. 29, 2004
R&B JOB 1827
SHEET 62 OF 62
DRAWING FILE SOFQ2
PROJECT NUMBER 472-83688