FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0080-01	1997	9	162

BY	DATE
REFERENCES NOTED	
REFERENCES CHECKED	

STATION 0+475.191 (BURTON), SAW EXISTING PAVEMENT TO NEAT LINE AND MATCH.

STATION 0+482.504 RT. (BURTON), CONSTRUCT INLET (TYPE II) (CURB). INSTALL 375 mm x 8.389 m STORM SEWER (RCP) (N.) SEE SHEETS

STATION 0+482.504 LT. (BURTON), CONSTRUCT INLET (TYPE II) (CURB). INSTALL 450 mm x 11.699 m STORM SEWER (RCP) (E.) SEE SHEETS 35, 61

DILLON 6TH ADDITION

STATION 0+482.487, 10 189 LT. (BURTON), CONSTRUCT INLET (DROP) (610 mm x 610 mm). INSTALL 375 mm x 5.087 m STORM SEWER (RCP) (S.) SEE SHEETS 35, 65

DILLON 4TH ADDITION

SMITHSON'S ADDITION

STATION 0+188.169, 4 562 LT., CONSTRUCT MANHOLE (TYPE P) (1.525 m DIA.). INSTALL 750 mm x 15.651 m STORM SEWER (RCP) (N.). INSTALL 450 mm x 22.251 m STORM SEWER (RCP) (E.) SEE SHEETS 35, 61

SEE CONCRETE INTERSECTION DETAIL, SHEET

Lot 1

Lot 1

STATION 0+205.348, 4 562 LT., CONSTRUCT MANHOLE (TYPE P) (1.525 m DIA.). INSTALL 750 mm x 99.127 m STORM SEWER (RCP) (N.) SEE SHEETS 10, 66

Access control except 2 openings

CONSTRUCTION LIMITS

BURTON

Concrete Pavement w/ Monolithic Curb

BM#2

4 572 x 3 048 Drainage Easement

+209.925, 15 240 Lt. Exist. R/W

+193.128, 9 144 Lt. Exist. R/W

20 mm Iron

9 225 R. Fc.

W.V.

F.H.

700 mm

250 mm

600 mm

Sign

Δ=26°26.40"

+200

0+200.734 P.I. = 0+500 (Burton)

0+187.004 2 612 Lt.

0+214.500 2 612 Lt.

0+285.396 2 612 Lt.

+300

MERIDIAN

Project Baseline = Section Line

℄ Improvement = 2 438 Right

900 mm Water Line

0+192.786 P.I. = 0+500 (Burton)

0+178.938 7 688 Rt.

0+206.401 7 688 Rt.

179°54'59"

Twin MH

500 mm

75 mm

450 mm

Cos Test

Sign

+180.575, 14 021 Rt. Exist. R/W

+204.944, 14 021 Rt. Exist. R/W

150 mm

1000 mm

20 mm

USD #259 U.G. Comm. Cable

Concrete Pavement w/ Monolithic Curb

Block 3

Block 2

MERIDIAN PARK ADDITION

MERIDIAN PARK ADDITION

CONSTRUCT 1 500 SIDEWALK (AE) (100 mm).

STATION 0+518.817 RT. (BURTON), CONSTRUCT INLET (TYPE II) (CURB). INSTALL 375 mm x 8.376 m STORM SEWER (RCP) (N.) SEE SHEETS 35, 61

SEE CONCRETE INTERSECTION DETAIL, SHEET

STATION 0+518.716 LT. (BURTON), CONSTRUCT INLET (TYPE II) (CURB). SEE SHEETS 35, 61

STATION 0+521.320 (BURTON), SAW EXISTING PAVEMENT TO NEAT LINE AND MATCH.

BM #2 "□" CUT IN TOP OF CURB AT 30 m± WEST OF CENTERLINE OF MERIDIAN ON NORTH SIDE OF BURTON ELEV. 396.291

SRB

SCALE

5 0 5 10

PLAN: Lat. & Long. (meters)

MERIDIAN
STATION 0+150 TO STATION 0+300

SRB 924 NORTH MAIN WICHITA, KANSAS 67203 http://www.feist.com/~srb
316-264-8008 FAX 264-48821 E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER
472-76-245-82740-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
J. Lang/TEB	T.C.R.	JCR	Jan. 8, 1999		539T

REVISED

SHEET NO. 9 OF 162