FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0080-01	1997	76	162

DATE	BY
REFERENCES NOTED	
REFERENCES CHECKED	

COMBINED CURB & GUTTER (AE)

STA. TO STA.	ROADWAY	SIDE	TYPE I (LIN. METERS)	TYPE II (LIN. METERS)	TYPE III (LIN. METERS)	STATION
0+031.426 to 0+031.728	Meridian	Lt.	0.322			
0+035.137 to 0+048.553	Meridian	Lt.	13.416			
0+048.553 to 0+059.125	Meridian	Lt.		10.572		
0+059.125 to 0+077.007	Meridian	Lt.	17.882			
0+065.888 to 0+070.837	Meridian	Rt.	4.949			
0+070.837 to 0+079.893	Meridian	Rt.		9.056		
0+079.893 to 0+086.679	Meridian	Rt.	6.786			
0+077.007 to 0+086.008	Meridian	Lt.		9.001		
0+086.008 to 0+090.503	Meridian	Lt.	4.495			
0+086.679 to 0+095.679	Meridian	Rt.		9.000		
0+090.503 to 0+102.934	Meridian	Lt.		12.431		
0+095.679 to 0+113.682	Meridian	Rt.	8.003			
0+102.934 to 0+103.295	Meridian	Lt.	0.361			
0+106.705 to 0+108.992	Meridian	Lt.	2.287			
0+106.317 to 0+109.817	Meridian	Rt.	3.500			
0+108.992 to 0+117.992	Meridian	Lt.		9.000		
0+109.828 to 0+119.158	Meridian	Rt.		9.940		
0+119.758 to 0+127.856	Meridian	Rt.	8.098			
0+127.856 to 0+136.856	Meridian	Rt.		9.000		
0+117.992 to 0+141.028	Meridian	Lt.	23.036			
0+141.028 to 0+150.028	Meridian	Lt.		9.000		
0+136.856 to 0+144.124	Meridian	Rt.	7.268			
0+144.124 to 0+156.093	Meridian	Rt.		11.969		
0+156.093 to 0+158.501	Meridian	Rt.	2.408			
0+150.028 to 0+156.590	Meridian	Lt.	6.652			
0+156.590 to 0+168.739	Meridian	Lt.		12.149		
0+158.501 to 0+171.409	Meridian	Rt.		12.998		
0+171.489 to 0+178.938	Meridian	Rt.	7.449			
0+168.739 to 0+187.004	Meridian	Lt.	18.265			
0+206.401 to 0+217.187	Meridian	Rt.	10.786			
0+217.187 to 0+226.187	Meridian	Rt.		9.000		
0+226.187 to 0+233.142	Meridian	Rt.	6.955			
0+233.142 to 0+242.142	Meridian	Rt.		9.000		
0+242.142 to 0+247.673	Meridian	Rt.	5.531			
0+247.673 to 0+256.673	Meridian	Rt.		9.000		
0+214.500 to 0+263.298	Meridian	Lt.	48.798			
0+256.673 to 0+264.609	Meridian	Rt.	7.936			
0+264.609 to 0+273.609	Meridian	Rt.		9.000		
0+263.298 to 0+285.986	Meridian	Lt.		22.942		TAPER
0+273.609 to 0+288.147	Meridian	Rt.	14.538			
0+288.147 to 0+303.053	Meridian	Rt.		14.906		
0+303.053 to 0+304.295	Meridian	Rt.	1.242			
0+285.986 to 0+304.295	Meridian	Lt.	18.309			
0+307.705 to 0+327.426	Meridian	Lt.	19.721			
0+307.705 to 0+320.338	Meridian	Rt.	12.633			
0+320.338 to 0+335.963	Meridian	Rt.		15.625		
0+327.426 to 0+342.506	Meridian	Lt.		15.080		
0+335.963 to 0+353.794	Meridian	Rt.	17.831			
0+342.506 to 0+365.343	Meridian	Lt.	22.837			
0+353.794 to 0+367.538	Meridian	Rt.		13.744		
0+365.343 to 0+401.137	Meridian	Inter.	57.432			
0+437.005 to 0+446.763	Meridian	Rt.	9.758			
0+436.948 to 0+455.792	Meridian	Lt.		18.874		TAPER
0+446.763 to 0+461.912	Meridian	Rt.		15.000		
0+455.792 to 0+463.178	Meridian	Lt.		7.398		TAPER
0+463.178 to 0+466.250	Meridian	Lt.	3.076			TAPER
0+461.192 to 0+466.295	Meridian	Rt.	4.383			
0+469.705 to 0+484.067	Meridian	Rt.	14.362			
0+469.654 to 0+474.186	Meridian	Lt.	4.539			TAPER
0+474.186 to 0+481.335	Meridian	Lt.		7.161		TAPER
0+481.335 to 0+487.933	Meridian	Lt.	6.609			TAPER
0+518.121 to 0+526.392	Meridian	Lt.		8.311		TAPER
0+516.755 to 0+529.108	Meridian	Rt.		12.370		TAPER
0+526.392 to 0+532.118	Meridian	Lt.	5.724			TAPER
0+529.108 to 0+532.101	Meridian	Rt.	3.018			TAPER
0+398.791 to 0+413.280	Meridian	Lt.		14.489		
0+401.137 to 0+413.280	Meridian	Rt.	12.143			
0+416.690 to 0+440.324	Meridian	Rt.	23.634			
0+416.690 to 0+430.259	Meridian	Lt.	13.569			
0+430.259 to 0+445.310	Meridian	Lt.		15.051		
0+440.324 to 0+451.658	Meridian	Rt.		11.334		
0+445.310 to 0+456.975	Meridian	Lt.	11.665			
0+451.658 to 0+470.026	Meridian	Rt.	18.368			
0+456.975 to 0+466.262	Meridian	Lt.		9.287		
0+466.262 to 0+471.651	Meridian	Lt.	5.389			
0+471.651 to 0+480.651	Meridian	Lt.		9.000		
0+480.651 to 0+486.486	Meridian	Lt.	5.835			
0+470.026 to 0+482.676	Meridian	Rt.		12.650		
0+482.676 to 0+489.613	Meridian	Rt.	6.937			
0+486.486 to 0+495.872	Meridian	Lt.		9.386		
0+495.872 to 0+497.064	Meridian	Lt.	1.192			
0+489.613 to 0+498.613	Meridian	Rt.		9.000		
0+500.474 to 0+509.474	Meridian	Lt.		9.000		
0+501.248 to 0+515.732	Meridian	Rt.	14.484			
0+509.474 to 0+525.930	Meridian	Lt.	16.456			
0+515.732 to 0+524.732	Meridian	Rt.		9.000		
0+524.732 to 0+530.475	Meridian	Rt.	5.743			
0+525.930 to 0+534.989	Meridian	Lt.		9.059		

COMBINED CURB & GUTTER (AE) CONT.

STA. TO STA.	ROADWAY	SIDE	TYPE I (LIN. METERS)	TYPE II (LIN. METERS)	TYPE III (LIN. METERS)	STATION
0+534.989 to 0+539.191	Meridian	Lt.	4.202			
0+530.475 to 0+539.811	Meridian	Rt.		9.336		
0+539.191 to 0+548.983	Meridian	Lt.		9.792		
0+539.811 to 0+546.369	Meridian	Rt.	6.558			
0+546.369 to 0+558.119	Meridian	Rt.		11.750		
0+548.983 to 0+554.712	Meridian	Lt.	5.729			
0+554.712 to 0+563.712	Meridian	Lt.		9.000		
0+558.119 to 0+567.177	Meridian	Rt.	9.058			
0+563.712 to 0+570.309	Meridian	Lt.	6.597			
0+567.177 to 0+576.177	Meridian	Rt.		9.000		
0+576.177 to 0+581.065	Meridian	Rt.	4.888			
0+570.309 to 0+585.470	Meridian	Lt.		15.161		
0+585.470 to 0+588.246	Meridian	Lt.	2.776			
0+608.528 to 0+634.961	Meridian	Rt.	26.433			
0+616.124 to 0+631.698	Meridian	Lt.	15.574			
0+631.698 to 0+640.698	Meridian	Lt.		9.000		
0+634.961 to 0+648.253	Meridian	Rt.		13.292		
0+648.253 to 0+652.213	Meridian	Rt.	3.960			
0+640.698 to 0+646.450	Meridian	Lt.	5.752			
0+646.450 to 0+655.921	Meridian	Lt.		9.471		
0+652.213 to 0+665.532	Meridian	Rt.		13.319		
0+655.921 to 0+662.875	Meridian	Lt.	6.954			
0+662.875 to 0+671.875	Meridian	Lt.		9.000		
0+665.532 to 0+672.493	Meridian	Rt.	6.961			
0+671.875 to 0+677.184	Meridian	Lt.	5.309			
0+672.493 to 0+681.493	Meridian	Rt.		9.000		
0+677.184 to 0+687.773	Meridian	Lt.		10.589		
0+681.493 to 0+695.626	Meridian	Rt.	14.133			
0+687.773 to 0+692.920	Meridian	Lt.	5.147			
0+692.920 to 0+701.920	Meridian	Lt.		9.000		
0+695.626 to 0+706.569	Meridian	Rt.		10.943		
0+701.920 to 0+707.888	Meridian	Lt.	5.968			
0+706.569 to 0+710.579	Meridian	Rt.	4.010			
0+707.888 to 0+716.888	Meridian	Lt.		9.000		
0+710.579 to 0+719.579	Meridian	Rt.		9.000		
0+716.888 to 0+731.219	Meridian	Lt.	14.331			
0+719.579 to 0+741.047	Meridian	Rt.	21.468			
0+731.219 to 0+740.219	Meridian	Lt.		9.000		
0+740.219 to 0+745.902	Meridian	Lt.	5.683			
0+741.047 to 0+753.143	Meridian	Rt.		12.096		
0+745.902 to 0+754.920	Meridian	Lt.		9.018		
0+754.920 to 0+760.074	Meridian	Lt.	5.154			
0+753.143 to 0+787.937	Meridian	Rt.	34.794			
0+760.074 to 0+769.074	Meridian	Lt.		9.000		
0+769.074 to 0+775.291	Meridian	Lt.	6.217			
0+775.291 to 0+784.291	Meridian	Lt.		9.000		
0+784.291 to 0+787.986	Meridian	Lt.	3.695			
0+452.641 to 0+468.597	Meridian	Rt.	16.055			TAPER
0+452.641 to 0+463.695	Meridian	Lt.	11.120			
0+463.695 to 0+472.134	Meridian	Lt.		8.645		TAPER
0+468.597 to 0+483.064	Meridian	Rt.	14.467			
0+472.134 to 0+483.069	Meridian	Lt.	10.935			
0+520.878 to 0+539.076	Meridian	Rt.	18.198			
0+520.890 to 0+537.566	Meridian	Lt.	16.676			
0+539.076 to 0+562.555	Meridian	Rt.		23.608		TAPER
0+537.566 to 0+562.555	Meridian	Lt.		24.989		TAPER
0+818.259 to 0+826.360	Meridian	Lt.	8.098			TAPER
0+826.360 to 0+829.401	Meridian	Lt.		3.042		TAPER
0+817.673 to 0+830.101	Meridian	Rt.	12.441			TAPER
0+830.101 to 0+839.688	Meridian	Rt.		9.592		TAPER
0+829.401 to 0+843.877	Meridian	Lt.	14.485			TAPER
0+839.688 to 0+852.319	Meridian	Rt.	12.638			TAPER
0+843.877 to 0+850.418	Meridian	Lt.		6.545		TAPER
0+850.418 to 0+862.645	Meridian	Lt.	12.234			TAPER
0+852.319 to 0+863.477	Meridian	Rt.		11.161		TAPER
0+862.645 to 0+876.356	Meridian	Lt.	13.711			
0+876.356 to 0+878.099	Meridian	Lt.		1.743		
0+863.477 to 0+879.593	Meridian	Rt.	16.116			
0+879.593 to 0+881.347	Meridian	Rt.		1.754		
0+878.099 to 0+900.131	Meridian	Lt.	22.032			
0+881.347 to 0+900.888	Meridian	Rt.	19.541			
0+900.131 to 0+901.873	Meridian	Lt.		1.742		
0+901.873 to 0+918.292	Meridian	Lt.	16.419			
0+918.292 to 0+921.567	Meridian	Lt.		3.275		
0+921.567 to 0+936.137	Meridian	Lt.	14.570			
0+936.137 to 0+938.402	Meridian	Lt.		2.265		
0+928.342 to 0+941.431	Meridian	Rt.	13.089			
0+941.431 to 0+943.185	Meridian	Rt.		1.754		
0+938.402 to 0+950.984	Meridian	Lt.	12.582			
0+950.984 to 0+952.726	Meridian	Lt.		1.742		
0+943.185 to 0+956.072	Meridian	Rt.	12.887			
0+956.072 to 0+957.814	Meridian	Rt.		1.742		
0+956.384 to 0+977.257	Meridian	Lt.	24.530			
0+977.257 to 0+982.709	Meridian	Lt.		5.452		
0+957.814 to 0+997.358	Meridian	Rt.	20.713			
0+997.358 to 0+999.101	Meridian	Rt.		1.742		
0+999.101 to 1+010.596	Meridian	Rt.	11.495			

COMBINED CURB & GUTTER (AE) CONT.

STA. TO STA.	ROADWAY	SIDE	TYPE I (LIN. METERS)	TYPE II (LIN. METERS)	TYPE III (LIN. METERS)	STATION
0+982.709 to 0+996.515	Meridian	Lt.	10.397			
0+996.515 to 1+000.191	Meridian	Lt.		3.675		
1+000.191 to 1+005.899	Meridian	Lt.	5.709			
1+038.085 to 1+065.249	Meridian	Rt.	27.163			
1+065.249 to 1+067.217	Meridian	Rt.		1.968		
1+030.437 to 1+056.717	Meridian	Lt.	26.280			
1+056.717 to 1+058.459	Meridian	Lt.		1.742		
1+058.459 to 1+069.129	Meridian	Lt.	10.670			
1+069.125 to 1+070.872	Meridian	Lt.		1.742		
1+067.217 to 1+102.989	Meridian	Rt.	32.362			
1+102.989 to 1+104.731	Meridian	Rt.		1.742		
1+070.872 to 1+102.602	Meridian	Lt.	28.320			
1+102.602 to 1+104.344	Meridian	Lt.		1.742		
1+104.731 to 1+119.333	Meridian	Rt.	14.602			
1+119.333 to 1+121.075	Meridian	Rt.		1.743		
1+121.075 to 1+122.904	Meridian	Rt.	1.829			
1+104.344 to 1+130.074	Meridian	Lt.	25.730			
1+130.074 to 1+131.816	Meridian	Lt.		1.742		
1+131.816 to 1+145.313	Meridian	Lt.	10.085			
1+145.313 to 1+147.055	Meridian	Lt.		1.742		
1+147.055 to 1+160.687	Meridian	Lt.	13.632			
1+160.687 to 1+165.894	Meridian	Lt.		5.207		
1+149.584 to 1+169.347	Meridian	Rt.	19.763			
1+169.347 to 1+173.202	Meridian	Rt.		3.855		
1+173.202 to 1+196.806	Meridian	Rt.	23.604			
1+165.894 to 1+185.105	Meridian	Lt.	19.211			
1+208.051 to 1+217.766	Meridian	Lt.	9.714			
1+217.766 to 1+220.781	Meridian	Lt.		3.015		
1+220.781 to 1+228.037	Meridian	Lt.	33.866			
1+199.585 to 1+278.519	Meridian	Rt.	29.931			
1+256.057 to 1+270.845	Meridian	Rt.	14.788			
1+270.845 to 1+272.587	Meridian	Rt.		1.742		
1+258.037 to 1+259.780	Meridian	Lt.		1.742		
1+259.780 to 1+269.059	Meridian	Lt.	9.280			
1+269.059 to 1+271.969	Meridian	Lt.		2.909		
1+271.969 to 1+276.271	Meridian	Lt.	4.308			
1+276.271 to 1+279.224	Meridian	Lt.		2.953		
1+279.224 to 1+297.662	Meridian	Lt.	18.437			
1+297.662 to 1+299.404	Meridian	Lt.		1.742		
1+299.404 to 1+304.153	Meridian	Lt.	4.749			
1+304.153 to 1+306.314	Meridian	Lt.		2.161		
1+272.587 to 1+289.576	Meridian	Rt.	16.988			
1+289.576 to 1+293.454	Meridian	Rt.		3.879		
1+293.454 to 1+306.450	Meridian	Rt.	12.995			
1+309.454 to 1+312.201	Meridian	Rt.		5.751		
1+312.201 to 1+324.728	Meridian	Rt.	9.891			
1+324.726 to 1+328.409	Meridian	Rt.		3.683		
1+388.409 to 1+335.708	Meridian	Rt.	7.298			
1+306.314 to 1+317.558	Meridian	Lt.	11.244			
1+317.558 to 1+319.301	Meridian	Lt.		1.742		
1+319.301 to 1+338.762	Meridian	Lt.	16.826			
1+338.762 to 1+340.504	Meridian	Lt.		1.742		
1+340.504 to 1+362.180	Meridian	Lt.	21.649			
1+362.180 to 1+363.923	Meridian	Lt.		1.742		
1+363.111 to 1+370.081	Meridian	Rt.	6.971			
1+379.081 to 1+408.772	Meridian	Rt.	27.056			
1+363.923 to 1+400.668	Meridian	Lt.		34.110		
1+429.481 to 1+430.381	Meridian	Lt.	0.898			
1+430.381 to 1+445.844	Meridian	Lt.		15.474		
1+445.844 to 1+460.216	Meridian	Lt.	14.374			
1+436.243 to 1+453.290	Meridian	Rt.	17.046			
1+453.290 to 1+455.961	Meridian	Rt.		2.667		
1+455.961 to 1+460.216	Meridian	Rt.	4.529			
1+460.216 to 1+503.682	Meridian	Rt.	46.522			
1+503.682 to 1+515.032	Meridian	Rt.	14.093			
1+518.915 to 1+474.885	Meridian	Rt.			49.359	
1+474.885 to 1+474.965	Meridian	Rt.			1.469	
1+474.965 to 1+483.852	Meridian	Rt.			9.005	
1+483.852 to 1+498.218	Meridian	Rt.			15.801	
1+498.218 to 1+520.233	Meridian	Rt.			25.912	
1+503.984 to 1+504.465	Meridian	Rt.			1.891	
1+504.465 to 1+513.437	Meridian	Rt.			9.111	
1+513.437 to 1+511.735	Meridian	Rt.			8.015	
1+511.735 to 1+503.984	Meridian	Rt.			9.111	
TOTALS			1765.803	877.297	130.274	

MERIDIAN IMPROVEMENTS
SUMMARY OF QUANTITIES

SRB
924 NORTH MAIN
WICHITA, KANSAS 67203
http://www.kscon/~srb
316-264-8008
FAX 264-4621
E-Mail: srb@ink.com
SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER
472-76-245-82740-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
E.G.	T.C.R.	JCR	Jan. 8, 1999		539T

REVISED

SHEET NO. SQ002 — 76 / 162