ADJUST VALVE BOX, FIRE HYDRANT & WTR. METER					
STATION	OFFSET (m)	DESCRIPTION	EXIST. ELEV.	PROP. ELEV.	REMARKS
4+065.1	13.36 RT.	WV	59.57	59.91	
4+128.3	12.97 RT.	WV	59.78	58.89	
4+134.8	13.40 RT.	WV	59.66	58.72	

FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO	TOTAL SHEETS
7	KANSAS	STP-N012(901)	1999	12	131

DATE	BY	
		REFERENCES NOTED
		REFERENCES CHECKED

STA. 4+121.49, PAWNEE AVE.
CONST. CONC. PVMT. 200 mm
UNIFORM (AE)
SEE SHEET NO. 49

FIFTH ADDITION TO CHERRY CREEK HILLS

STA. 4+983.45 DALTON
SAW CUT & MATCH EXIST. PVMT.

RELOCATED GAS LINE

STA. 4+028.52 PAWNEE AVE. CONSTRUCT
STD. SHALLOW MANHOLE 12.24 m RT., DIA.=1.219 m
MANHOLE TOP=59.90
REMOVE EXIST. END SECTION
INSTALL 600 mm x 4.23 m
STORM SWR. (RCP)(NE)
SEE SHT. NO. 53 & 56

CONST LIMITS VARIES

C/L 6.10 m Util. Esmt.

PRESERVE EXIST. WOOD FENCE

7.62 m Setback

9.75 m R/W

C/L DALTON

3.44 m Util. Esmt.

4.57 m Bldg. Setback

15.24 m R/W

3.10 m Sidewalk

EX. RCP

REMOVE 15.5 m OF CULVERT

REMOVE 17.9 m CULVERT

C/L PAWNEE AVE.

PROP. 900 mm RCP

PROP. 600 mm RCP

EXIST. 600 mm RCP

1.80 m Sidewalk

9.00 m R. (Typ.)

CONST LIMITS 14.94 m RT.

STA. 4+030.74 PAWNEE AVE. CONSTRUCT
CURB INLET (TYPE 1A) 8.68 m RT.
L=1.93 m, W=1.63 m
INLET TOP=59.38
INSTALL 900 mm x 33.42 m
STORM SWR. (RCP)(E)
SEE SHT. NO. 51 & 56

STA. 4+057.25, PAWNEE
CONST. CONC. PVMT. 200 mm
UNIFORM (AE)
SEE SHEET NO. 49

STA. 5+016.55, CAPRI SAW CUT & MATCH EXIST. PVMT.

C/L CAPRI

STA. 4+064.16 PAWNEE AVE. CONSTRUCT
STD. SHALLOW MANHOLE 8.69 m RT., DIA.=1.524 m
MANHOLE TOP=59.14
INSTALL 900 mm x 66.0 m
STORM SWR. (RCP)(E)
SEE SHT. NO. 53 & 56

STA. 4+064.16 PAWNEE AVE.
EXIST. CURB INLET 17.65 m RT.
REMOVE EXIST. 450 mm RCP NE
INSTALL 450 mm x 8.98 m
STORM SWR. (RCP)(N)
SEE SHT. NO. 56

6.10 m Util. Esmt.

STA. 4+130.17 PAWNEE AVE. CONSTRUCT
CURB INLET (TYPE 1A) 8.68 m RT.
L=1.93 m, W=1.63 m
INLET TOP=58.76
INSTALL 900 mm x 28.59 m
STORM SWR. (RCP)(E)
SEE SHT. NO. 51 & 56

Conoco Pipeline Co.

OAK KNOLL ADDITION

OAK KNOLL ADDITION

BM #11 COW BM SW cor. of Pawnee & Dalton
0.9 m W of back of curb & 1.0 m N of SWS
inlet. 15.89 m Rt. of Pawnee C/L.
Sta. 4+139.88 Elev.=58.602

UTILITY OWNERS

TV – Cox Communications (316)262-4270
P1 – 12" Williams Natural Gas 1-800-324-9696
P2 – 20" Williams Natural Gas 1-800-324-9696
P3 – 4" Raytheon Aircraft (316)676-6867
P4 – 4" Raytheon Aircraft (316)676-6867
P5 – 18" Williams Natural Gas 1-800-324-9696
P6 – 6" Conoco Pipe Line Co. 1-800-231-2551
G – 6" Kansas Gas Service (316)832-3168
E – KGE (316)261-6944
SS – City of Wichita Water & Sewer Dept. (316)262-6000
SWS – City of Wichita Water & Sewer Dept. (316)262-6000
T – Southwestern Bell Telephone Co. 1-800-734-7590
W – 16" City of Wichita Water & Sewer Dept. (316)262-6000

Legend
Pavement, Median, Driveway and/or Sidewalk Removal

NO.	DATE	REVISIONS	BY	APP'D
2				
1				

KANSAS DEPARTMENT OF TRANSPORTATION

PAWNEE AVE.
STA. 4+020 TO STA. 4+140

PROJ. NO. 87 STP-N-0129-01

MKEC ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY:	JTC	CHECKED BY:	GJA	
DRAWN BY:	GJR,MLW	DATE: JUNE 1999	SHEET 12 OF 131	

G:\CIVIL\PAW-WEBB\98171\PAV\98171E8.DWG Wed Jul 26 09:45:37 2000