FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	STP-N012(901)	1999	36	131

DATE	BY	
		REFERENCES NOTED
		REFERENCES CHECKED

STA. 5+060.00 WEBB RD. CONSTRUCT
CURB INLET (TYPE 1A) 10.52 m LT.
L=1.93 m, W=1.63 m
INLET TOP=61.91
INSTALL 750 mm x 68.98 m STORM SWR. (RCP)(S)
SEE SHEET NO. 51 & 57

(14)

10.67 m Bldg. Stbk.

PROP. 22.86 m R/W

+023.05

CONST. LIMITS
22.56 m LT.

22.86 m R/W

3.10 m Sidewalk

CONST. LIMITS
14.94 m LT.

STA. 5+151.15 WEBB RD., MATCH LINE
END CONSTRUCTION NO. STP-N012(901)
PAWNEE AVE., FROM ROCK RD. TO WEBB
BEGIN PROJ. NO. STP-N012(601)
WEBB RD., FROM PAWNEE AVE. TO HARRY

+106.63 R/W

15.24 m R/W

+151.15
6.80 m LT.
END TAPER

+076.25 P.C.
9.40 m LT.
BEGIN TAPER

PROP. 750 mm RCP

62.19 62.10 62.02 62.08 62.10 62.22 62.33 62.45 62.52

2.09 2.00 1.92 1.98 2.00 2.12 2.23 2.35 2.42

PROP. 600 mm RCP

8.65 m

EXIST. BIT. PVMT.

20 40 60 80 5+100 20 40 60

2.37 2.36 2.27 2.19 2.25 2.27 2.37 2.42 2.47 2.52 2.57 2.59 2.63

C/L WEBB RD.

REMOVE EXIST. CULVERT

13.6 m

2.09 2.00 1.92 1.98 2.00 2.12 2.18 2.23 2.29 2.35 2.37 2.42

62.19 62.10 62.02 62.08 62.10 62.22 62.28 62.47 62.52

1.80 m Sidewalk

4.60 m R

+021.56
9.94 m RT.

CONST. LIMITS
22.56 m RT.

+035.72
8.65 m RT.

RELOCATED P3
RELOCATED P4

+076.17
8.65 m RT.
BEGIN TAPER

+076.17 R/W

+108.91 R/W

+108.91
7.82 m RT.

62.65

+119.64
10.00 m

62.70

15.24 m R/W

+129.41
7.35 m RT.

62.95

+136.35
6.81 m RT.

62.99

+143.32
7.80 m RT.

+151.15
6.80 m RT.
END TAPER

CONST. LIMITS
14.94 m RT.

22.86 m R/W +023.05

22.86 m R/W

(13)

STA. 5+060.00 WEBB RD. CONSTRUCT
CURB INLET (TYPE 1A) 10.38 m RT.
L=1.93 m, W=1.32 m
INLET TOP=62.02
INSTALL 600 mm x 20.90 m
STORM SWR. (RCP)(W)
SEE SHEET NO. 51 & 57

(13A)

STA. 5+060.00 WEBB RD. CONSTRUCT
DITCH INLET (TYPE 2) 14.88 m RT.
INLET TOP=62.09
W/ EROSION CONTROL BLANKET
INSTALL 600 mm x 4.50 m
STORM SWR. (RCP)(W)
SEE SHEET NO. 55 & 57

MATCH EXIST. GROUND
14.94 m RT.

MATCH EXIST. GROUND
14.94 m RT.

GRAVEL

P1 P2 P3 P4 P5 P6 TV E G SS SWS T W

UTILITY OWNERS

TV – Cox Communications (316)262-4270
P1 – 12" Williams Natural Gas 1-800-324-9696
P2 – 20" Williams Natural Gas 1-800-324-9696
P3 – 4" Raytheon Aircraft (316)676-6867
P4 – 4" Raytheon Aircraft (316)676-6867
P5 – 18" Williams Natural Gas 1-800-324-9696
P6 – 6" Conoco Pipe Line Co. 1-800-231-2551
G – 6" Kansas Gas Service (316)832-3168
E – KGE (316)261-6944
SS – City of Wichita Water & Sewer Dept. (316)262-6000
SWS – City of Wichita Water & Sewer Dept. (316)262-6000
T – Southwestern Bell Telephone Co. 1-800-734-7590
W – 16" City of Wichita Water & Sewer Dept. (316)262-6000

Legend

Pavement, Median, Driveway and/or Sidewalk Removal

NO.	DATE	REVISIONS	BY	APP'D
2				
1				

KANSAS DEPARTMENT OF TRANSPORTATION

WEBB RD.
STA. 5+020 TO STA. 5+160

PROJ. NO. 87 STP-N-0129-01

MKEC ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY:	JTC	CHECKED BY:	GJA	
DRAWN BY:	GJR,MLW	DATE: JUNE 1999	SHEET 36 OF 131	

G:\CIVIL\PAW-WEBB\98171\PAV\98171E00.DWG Thu Jul 27 09:39:27 2000

G:\CIVIL\PAW_WEBB\98171\PAV\98171E20.DWG