



DATE	
BY	
REFERENCES NOTED	
REFERENCES CHECKED	




**TEMPORARY TREE PROTECTION DETAIL**  
NOT TO SCALE

**MASTER PLANT LIST**

QTY.	COMMON NAME	BOTANICAL NAME	SIZE	CONDITION/REMARKS
<b>LARGE DECIDUOUS TREES</b>				
10	OCTOBER GLORY MAPLE	<i>Acer rubrum</i> 'October Glory'	2.5" cal.	Balled-in-Burlap
17	THORNLESS HONEYLOCUST	<i>Gleditsia triacanthos</i> 'Shademaster'	2.5" cal.	Balled-in-Burlap
1	PATMORE ASH	<i>Fraxinus pennsylvanica</i> 'Patmore'	2.5" cal.	Balled-in-Burlap
4	SHUMARD OAK	<i>Quercus shumardii</i>	2.5" cal.	Balled-in-Burlap
3	LACEBARK ELM	<i>Ulmus parvifolia</i>	2.5" cal.	Balled-in-Burlap
24	CHINESE PISTACHE	<i>Pistacia chinensis</i>	2.5" cal.	Balled-in-Burlap
<b>EVERGREEN TREES</b>				
16	LIMBER PINE	<i>Pinus flexilis</i>	8'	Balled-in-Burlap
18	AUSTRIAN PINE	<i>Pinus nigra</i>	8'	Balled-in-Burlap
<b>ORNAMENTAL TREES</b>				
13	OKLAHOMA REDBUD	<i>Cercis reniformis</i>	1.5" cal.	Balled-in-Burlap
4	FLAME AMUR MAPLE	<i>Acer ginnala</i> 'Flame'	1.5" cal.	Balled-in-Burlap
44	PRAIRIFIRE CRABAPPLE	<i>Malus sp.</i> 'Prairifire'	1.5" cal.	Balled-in-Burlap
39	SPRING SNOW CRABAPPLE	<i>Malus sp.</i> 'Spring Snow'	1.5" cal.	Balled-in-Burlap
20	SNOWDRIFT CRABAPPLE	<i>Malus sp.</i> 'Snowdrift'	1.5" cal.	Balled-in-Burlap
14	JAPANESE TREE LILAC	<i>Syringa reticulata</i>	1.5" cal.	Balled-in-Burlap
3	CHANTICLEER PEAR	<i>Pyrus calleryana</i> 'Chanticleer'	1.5" cal.	Balled-in-Burlap
<b>LAWN</b>				
20,443.84 S.M.	K-31 FESCUE	<i>Festuca arundinacea</i> 'K-31'	-	Hydraseed




**TREE TRIMMING DETAIL**  
NOT TO SCALE



**EVERGREEN TREE PLANTING DETAIL**  
NOT TO SCALE

NOTES:  
BALL OF PLANT TO BE KEPT MOIST AND PROTECTED FROM DAMAGE PRIOR TO PLANTING. ADD ROOT STIMULATOR TO SURFACE IMMEDIATELY AFTER PLANTING AS PER THE MANUFACTURER'S RECOMMENDATIONS. PLANTING DEPTH OF ROOTBALL SHALL BE EQUAL TO ITS ORIGINAL PLANTING DEPTH AT NURSERY.



**DECIDUOUS TREE PLANTING DETAIL**  
NOT TO SCALE

**NOTES:**

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY OF WICHITA SEEDING AND LANDSCAPING SPECIFICATIONS. AT ANY POINT WHERE DISCREPANCIES EXIST BETWEEN THESE NOTES/DETAILS AND THE SPECIFICATIONS, THE SPECIFICATIONS SHALL BE ADHERED TO.
- LANDSCAPE CONTRACTOR IS TO VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES (INCLUDING THOSE INDICATED ON THE PLAN) PRIOR TO INSTALLATION OF PLANT MATERIAL. UTILITIES CAN BE FLAGGED BY CALLING 687-2470.
- AREAS DENOTED AS SEEDED ARE TO BE HYDRA-SEEDED AS FOLLOWS:  
SEED:  
HYDRA-SEED K-31 GRASS AT A RATE OF 6-8#/1000S.F.  
FERTILIZER:  
OBTAIN SOIL TEST FROM CERTIFIED SOIL TESTING AGENCY FOR RECOMMENDED FERTILIZER TYPE AND AMOUNTS.
- EACH TREE SHALL BE LABELED WITH A WATERPROOF TAG BEARING LEGIBLE DESIGNATION OF BOTH THE BOTANICAL AND COMMON NAME.
- ALL PLANT MATERIAL SHALL RECEIVE A STARTER TREATMENT OF ROOT STIMULATOR. APPLY AS DIRECTED BY MANUFACTURER.
- SUBSTITUTION OF PLANT SPECIES TYPES FOR THOSE LISTED IN THE PLANT LIST IS NOT PERMISSIBLE UNLESS APPROVED BY MKEC (684-9600). ANY SUBSTITUTION WHICH HAS NOT BEEN APPROVED SHALL BE REMOVED IMMEDIATELY AND REPLACED WITH THE CORRECT PLANT.
- ALL TREE SAUCERS/PLANTING BEDS ARE TO BE MULCHED WITH A MINIMUM OF 4" SHREDDED WOOD MULCH.
- A MIN. 6" LAYER OF TOPSOIL SHALL BE PLACED IN ALL LAWN/PLANTING AREAS WITHIN THE CONSTRUCTION LIMITS.
- TOPSOIL SHALL BE FERTILE NATURAL TOPSOIL, TYPICAL OF THE LOCALITY, OBTAINED FROM WELL DRAINED AREAS. STOCKPILED TOPSOIL MAY BE USED. IT SHALL BE WITHOUT ADMIXTURE OF SUBSOIL OR SLAG AND SHALL BE FREE OF STONES, LUMPS, STICKS, PLANTS OR THEIR ROOTS, TOXIC SUBSTANCES OR OTHER EXTRANEIOUS MATTER THAT MAY BE HARMFUL TO PLANT GROWTH OR WOULD INTERFERE WITH FUTURE MAINTENANCE. TOPSOIL pH RANGE SHALL BE 5.5 TO 7.0.
- ANY TREE THAT IS NOT LABELED TO BE REMOVED SHALL BE PRESERVED BY THE CONTRACTOR. BEFORE ANY CONSTRUCTION BEGINS THESE TREES SHALL BE PROTECTED AS SHOWN IN THE "TEMPORARY TREE PROTECTION DETAIL" (THIS SHEET).
- EQUIPMENT AND CONSTRUCTION MATERIALS SHALL REMAIN OUT OF AND AWAY FROM TREE DRIPLINES SO AS NOT TO COMPACT THE ROOT ZONE OR DAMAGE THE TREE.
- ANY TREE THAT MUST HAVE BRANCHES REMOVED SHALL BE TRIMMED WITH A SHARP INSTRUMENT/TOOL THAT IS INTENDED FOR SUCH OPERATIONS. KNOCKING BRANCHES OFF WITH A BACKHOE OR OTHER SIMILAR MACHINES IS NOT ACCEPTABLE. REFER TO DETAIL ON THIS SHEET FOR TRIMMING PROCEEDURE.

2				
1				
NO.	DATE	REVISIONS	BY	APP'D
KANSAS DEPARTMENT OF TRANSPORTATION <b>ROAD SIDE IMPROVEMENTS</b> <b>PAWNEE AVE.</b> <b>STA. 5+060 TO STA. 5+180</b> PROJ. NO. 87 STP-N-0129-01 SEDGWICK COUNTY <b>MID-KANSAS ENGINEERING CONSULTANTS, INC.</b> WICHITA, KANSAS				
DESIGNED BY:	JTC	CHECKED BY:	GJA	
DRAWN BY:	GJR,MLW	DATE:	JUNE 1999	SHEET 91 OF 131